


Reviewed for Code Compliance

Hayden Scarnato

architecture

Planning Construction Management Interiors

SUITE 800 1602 W. BUSINESS 380 DECATUR, TEXAS 76234 214-244-0506



WILLIAM K HALL & CO
CONSULTING ENGINEERS
359 LAKE PARK ROAD; SUITE #106
LEWISVILLE, TEXAS 75057
TEL: 214-681-2179
TEXAS FIRM REGISTRATION #F-12258

A RENOVATION PROJECT
HQ OFFICE BUILDING
414 W. PARKWAY ST.
DENTON, TX

DATE: 12/30/2022

THIS DRAWING IS NOT TO BE REPRODUCED, EITHER IN WHOLE OR IN PART WITHOUT THE PERMISSION OF DALLAS PROCTOR, ARCHITECT

REVISIONS:

NO. DESCRIPTION DATE

REVIEWED BY: WKH

DRAWN BY: AH

DIAWN DI. A

DATE: 12/31/2022

PROJECT NO. 22-066
SHEET TITLE:

ELECTRICAL POWER PLAN SECOND FLOOR

SHEET:

E-4

POWER PLAN KEYED NOTES:

- NEW ROOFTOP UNIT. ALL POWER WIRING AND FINAL CONNECTION MUST BE BY ELECTRICAL CONTRACTOR. COORDINATE WITH MECHANICAL CONTRACTOR FOR THRU-THE-BASE ELECTRICAL UTILITY ACCESS. SEE PLAN FOR AMPERAGE AND NEMA RATING. COORDINATE RTU LOCATION WITH LANDLORDS STRUCTURAL ENGINEER.
- 2 EXISTING ROOFTOP UNIT. ALL POWER WIRING AND FINAL CONNECTION MUST BE BY ELECTRICAL CONTRACTOR. COORDINATE WITH MECHANICAL CONTRACTOR FOR THRU-THE-BASE ELECTRICAL UTILITY ACCESS. SEE PLAN FOR AMPERAGE AND NEMA RATING. COORDINATE RTU LOCATION WITH LANDLORDS STRUCTURAL ENGINEER.
- MINI SPLIT CEILING CASSETTE AHU. COORDINATE ELECTRICAL REQUIREMENTS WITH MECHANICAL CONTRACTOR. PROVIDE POWER VIA HEAT PUMP CIRCUIT OR AS REQUIRED BY MANUFACTURER.
- MINI SPLIT HEAT PUMP UNIT (ON ROOF). SEE PLAN FOR DISCONNECT SWITCH AMPERAGE AND NEMA RATING. PROVIDE WEATHER PROOF CONVENIENCE OUTLET WHERE REQUIRED. VERIFY FINAL UNIT LOCATION WITH OWNER AND MECHANICAL CONTRACTOR PRIOR TO INSTALLATION. COORDINATE FINAL MOCP OF UNIT WITH MECHANICAL CONTRACTOR.
- DEDICATED CIRCUIT FOUR—PLEX RECEPTACLE WITH ISOLATED GROUND FOR COMPUTER NETWORK SERVER. LOCATION IS SHOWN FOR REFERENCE ONLY. VERIFY LOCATION AND REQUIREMENTS WITH OWNER PRIOR TO INSTALLATION.
- ALL TELEPHONE, DATA, AND COMBINATION TELEPHONE/DATA OUTLET LOCATIONS TO BE APPROVED BY OWNER AND TENANT PRIOR TO CONSTRUCTION. INSTALL MINIMUM 3/4" CONDUIT TO ABOVE CEILING, BEND 90°, AND TERMINATE WITH PLASTIC BUSHING OR AS REQUIRED BY I.T. SUBCONTRACTOR. CABLING INSTALLATION IS BY OWNERS I.T. SUBCONTRACTOR.