



NOTES	
1	Existing light fixtures to be reused and relocated as needed
2	New flooring will be VCT
3	All interior walls will be repainted
4	Existing ceiling and ceiling tiles will be reused
5	Modify existing ductwork as needed
6	Install new HVAC equipment
7	All hardware will be ADA compliant

DOOR SCHEDULE					
Mark	Size	Jamb	Type	Hardware	Notes
1	Pair 3.0 x 7.0	Alum			Existing
2	3.0 x 7.0	Metal	Metal		Existing
3	Pair 3.0 x 7.0	Metal	Metal	Head & Foot Bolt Deadbolt on Active Leaf	
4	3.0 x 6.8	Metal	Hollow Core	Keylock	
5	3.0 x 6.8	Metal	Hollow Core	Passage Lock	
6	3.0 x 6.8	Metal	Hollow Core	Privacy Lock	Existing