
Architectural Plans By:



FORTUNE ARCHITECTS 8510 McALPINE PARK DR., SUITE 204 CHARLOTTE, NC 28211

Final Site Plan Approval Application

ORARIAN CHARDEL RO HWY 73

WICINITY MAP

VICINITY MAP NOT TO SCALE

Proposed

CORNELIUS VILLAGE CENTER LOT #1

Cornelius, Mecklenburg County, North Carolina

Applicant / Developer:

HEIDI STODDARD 17914 JOHN CONNOR RD. CORNELIUS, NC 28031

AUGUST 10TH, 2016

Plans Prepared By:



blending of man


NOTICE TO CONTRACTOR:
THIS LAND DEVELOPMENT PLAN HAS NOT BEEN REVIEWED OR APPROVED BY CMUD.
PLEASE CONTACT MIKE GARBARK AT 704-432-5797 MGARBARK@CI.CHARLOTTE.NC.US WITH CMUD
AND EXPLAIN YOUR DEVELOPMENT PRIOR TO CONSTRUCTION.


ANY LAND DEVELOPMENT PLAN REVISIONS CAUSED BY CMUD COMMENTS MAY REQUIRE ADDITIONAL REVIEW TIME AND ADDITIONAL FEES TO BE PAID BY THE OWNER/DEVELOPER/CONTRACTOR.


IT IS HIGHLY RECOMMENDED TO RECEIVE CMUD APPROVAL PRIOR TO LAND DEVELOPMENT APPROVAL

SHEET LEGEND

- C1 COVER SHEET
- C2 SITE PLAN
- C3 EXISTING CONDITIONS & DEMOLITION PLAN
- C4 GRADING & EROSION CONTROL PLAN
- C5 UTILITY PLAN
- C6 DETAILS
- 7 NOTES







NORTH ARROW

Project	CORNELIUS VILLAGE CENTER LOT #1	Location 19711 BETHEL CHURCH RD., CORNELIUS, NC 28031	Mecklenburg, Co.	Sheet Title	COVER SHEET
---------	---------------------------------	---	------------------	-------------	-------------

DEVELOPER/OWNER


HEIDI STODDARD 17914 JOHN CONNOE RD. CORNELIUS, NC 28031 704-906-1315


Designed	Ву			
	Wo	odbin	e D	esi
Drawn By				
***				ſ
Date				
			8/1	0/
Revisions				
		<u></u>		
			···	
				_
	•			
				-


Sheet C1 Of 7
Project Number 16026



IF ANY CONFLICTS, DISCREPANCIES, OR OTHER UNSATISFACTORY CONDITIONS
ARE DISCOVERED, EITHER ON THE CONSTRUCTION DOCUMENTS OR THE FIELD
CONDITIONS, THE CONTRACTOR MUST NOTIFY THE ENGINEER IMMEDIATELY,
AND SHALL NOT COMMENCE OPERATION UNTIL THE CONFLICTS, DISCREPANCIE







GRADING AND DRAINAGE NOTES:

- 1. ALL GRADING AND SITE PREPARATION WILL CONFORM TO SPECIFICATIONS AS GIVEN IN REPORT OF
- 2. CONTRACTOR SHALL VERIFY EXISTING TOPOGRAPHIC DATA. LOCATIONS OF EXISTING UTILITIES, AND ALL
- OTHER SITE CONDITIONS PRIOR TO BEGINNING CONSTRUCTION.
- 3. ALL STORM SEWER PIPE TO BE RCP, EXCEPT WHERE NOTED ON THE PLANS OR REQUIRED BY JURISDICTION.

- 5. FOR GRADING & DRAINAGE FACILITY DETAILS, SEE DETAIL SHEETS.
- 6. ALL CUT AND FILL SLOPES SHALL BE 3:1 OR FLATTER (SEE PLANS). UNLESS SHOWN OTHERWISE.
- 7. ALL CONSTRUCTION WITHIN STREET RIGHT-OF-WAY SHALL CONFORM TO APPLICABLE STATE AND LOCAL JURISDICTIONAL REQUIREMENTS.
- 8. ALL OPEN DRAINAGE SWALES SHALL BE GRASSED, AND RIPRAP MUST BE PLACED AS NECESSARY TO

9. GRADING CONTRACTOR IS RESPONSIBLE FOR STRIPPING AND STOCKPILING OF TOPSOIL. GRADING CONTRACTOR IS ALSO RESPONSIBLE FOR REMOVING FROM SITE EXCESS TOPSOIL. GRADING CONTRACTOR SHALL PREPARE

- 10. LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR TOPSOIL INSTALLATION IN LANDSCAPE ISLANDS.
- 11. CONTRACTOR SHALL CONFINE HIS OFF-SITE ACTIVITIES TO EXISTING RIGHTS OF WAY AND EASEMENTS.

1)APPROVAL OF THIS PLAN IS NOT AN AUTHORIZATION TO GRADE ADJACENT PROPERTIES. WHEN FIELD CONDITIONS WARRANT OFFSITE GRADING. PERMISSION MUST BE OBTAINED FROM THE AFFECTED PROPERTY OWNERS.

2) IN ORDER TO ENSURE PROPER DRAINAGE, KEEP A MINIMUM OF 0.5% SLOPE ON THE CURB.

3) THE PURPOSE OF THE STORM DRAIN EASEMENT (SDE) IS TO PROVIDE

STORM WATER CONVEYANCE. BUILDINGS ARE NOT PERMITTED IN THE EASEMENT AREA. ANY OTHER OBJECTS WHICH IMPEDE STORM WATER FLOW OR SYSTEM MAINTENANCE ARE ALSO PROHIBITED.

4) NO SOIL DISTURBANCE OR COMPACTION, CONSTRUCTION MATERIALS, TRAFFIC, BURIAL PITS, TRENCHING OR OTHER LAND DISTURBING ACTIVITY ALLOWED IN THE TREE PROTECTION ZONE

5) TREE BARRICADE MUST BE INSTALLED BEFORE ANY DEMOLITION, GRADING OR CONSTRUCTION BEGINS, AND NOT REMOVED UNTIL FINAL INSPECTION.

6) BEFORE GRADING/CLEARING/CONSTRUCTION BEGINS CALL FOR INSPECTION OF TREE PROTECTION BARRICADES BY URBAN FORESTER.

7) TREE PROTECTION BARRICADES MUST MEET OR EXCEED TREE ORDINANCE STANDARDS (IN CITY OF CHARLOTTE TREE ORDINANCE GUIDELINES, APPENDIX 3) OR LAND DEVELOPMENT STANDARDS MANUAL 40.02.

8) NO GRUBBING WITHIN TREE PROTECTION ZONE. LEAVE SOIL AND LEAF LITTER UNDISTURBED, SUPPLEMENT WITH 1-2 INCHES OF MULCH RE-SEED WITH GRASS ONLY IN DISTURBED/GRADED AREAS.

9) BRUSH, VINES AND SMALL TREES (<8" DIA., OR AS SMALL AS 2" IN CALIPER) MAY BE HAND CLEARED ONLY, CUT FLUSH WITH GROUND SURFACE. EXISTING TREES MAT BE LIMBED UP SIX FEET(LEAVING AT LEAST 3 OF THE BRANCHES TO IMPROVE VISIBILTY.

10) EXPOSED TREE ROOTS MUST BE CLEANLY CUT WITH A SHARP PRUNING TOOL; BACKFILL ASAP TO MINIMIZE EXPOSURE TO AIR.

11) ASBUILT DRAWINGS AND PLANS OF THE STORM DRAINAGE SYSTEM, INCLUDING DESIGNED DITCHES, MUST BE SUBMITTED PRIOR TO FINAL INSPECTION TO THE CITY/COUNTY ENGINEERING DEPARTMENT.

FLEXIBLE PIPE SLOPE DRAIN TEMPORARY SILT DITCH ----

TEMPORARY SILT FENCE ------------

TEMPORARY RIPRAP

FILTER BERM

RIP RAP APRON AT PIPE OUTLET

RISER TYPE SEDIMENT BASIN

BASIN

GRAVEL AND RIP RAP SEDIMENT

STORM INLET SEDIMENT TRAP

STONE INLET SEDIMENT TRAP (INSTALL SILT SACKS AFTER PAVING)

TEMPORARY ROCK CHECK DAM

STABLIZED CONSTRUCTION ENTRANCE

EROSION CONTROL LEGEND

TEMPORARY SEEDING

PERMANENT SEEDING

TEMPORARY STREAM CROSSING

DRAINAGE AREA LIMITS

NOTE: CONTRACTOR SHALL FIELD VERIFY ALL GRADES PRIOR TO CONSTRUCTION.

SEEDBED PREPARATION NOTES SURFACE WATER CONTROL MEASURES TO BE INSTALLED

ACCORDING TO PLANS.

AREAS TO BE SEEDED SHALL BE RIPPED AND SPREAD WITH

AVAILABLE TOPSOIL 3" DEEP. TOTAL SEEDBED PREPARED DEPTH SHALL BE 4".

LOOSE ROCKS,ROOTS, AND OTHER OBSTRUCTIONS SHALL BE

REMOVED FROM THE SURFACE SO THAT THEY WILL NOT INTERFERE WITH

UNIFORM.

IF NO SOIL TEST IS TAKEN, FERTILIZER AND LIME ARE
TO BE USED AS DESCRIBED ABOVE. IN ADDITION ,15 LBS/1000 S.F. OF
SUPERPHOSPHATE IS TO BE PROVIDED.
IF SOIL TEST IS TAKEN, PROVIDE FERTILIZER AND LIME
ACCORDING TO RESULTS OF TEST.
LIME AND FERTILIZER SHALL BE APPLIED UNIFORMLY AND
MIXED WITH THE SOIL DURING SEEDBED PREPARATION.

Erosion Control & Water Quality Inspector Nick Finelli - Cornelius, Davidson, Huntersville (980) 721-9390

Land Development Inspector: Tommy Keziah - Cornelius, Davidson, Huntersville (704) 634-6753

Zoning Inspector: Brian Sifford - Cornelius, Davidson, Huntersville

DENUDED AREA = 0.17ac.


Know what's below.

Call before you dig.

NORTH CAROLINA ONE-CALL CENTER INC.

DIAL 811 or 1-800-632-4949


2 BUSINESS DAYS BEFORE DIGGING www.nc811.org




IF ANY CONFLICTS, DISCREPANCIES, OR OTHER UNSATISFACTORY CONDITIONS ARE DISCOVERED, EITHER ON THE CONSTRUCTION DOCUMENTS OR THE FIELD

Ŏ









Graphic Scale 1'' = 10 ft.

EROSION CORNELIUS 19711 BETHEL


DEVELOPER/OWNER 17914 JOHN CONNOR RD.


CORNELIUS, NC 28031

Designed By Drawn By 8/10/16 Revisions 13/6/17-Revised Footprin

Project Number 16026

PLOTTED: 3/6/2017
H:__WOODBINEDESIGN_PROJECTS\16026 -CVC LOT |
#1_CAD\01A-CVC-LOT1-BASE.DWG |
#1_CAD\01A-CVC-LOT1-BASE.DWG |
OR OTHER UNSATISFACTORY CONDITIONS ARE RESOLVED.





- WIRE FENCING - FILTER FABRIC WOVEN FILTER FABRIC -

FILTER FABRIC FENCE SHALL BE A MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.

- WOVEN FILTER FABRIC BE USED WHERE SILT FENCE IS TO REMAIN FOR A PERIOD OF MORE THAN 30
- STEEL POSTS SHALL BE 5'-0" IN HEIGHT AND BE OF THE SELF-FASTENER ANGLE STEEL TYPE. WIRE FENCING SHALL BE AT LEAST #10 GAGE WITH A MINIMUM OF 6 LINE WIRES WITH 6" STAY SPACING.
- WIRE AND WASHED STONE IS REQUIRED TO BE SHOWN ON PLANS AT THE TOE OF SLOPES GREATER THAN
- ORANGE SAFETY FENCE IS REQUIRED AT BACK OF SILT FENCE WHEN GRADING IS ADJACENT TO SWIM BUFFERS, STREAMS OR WETLANDS (REFER TO SWIM BUFFER GUIDELINES). THE COLOR ORANGE IS RESERVED FOR VISUAL IDENTIFICATION OF ENVIRONMENTALLY SENSITIVE AREAS.
- DRAINAGE AREA CAN NOT BE GREATER THAN 1/4 ACRE PER 100 FT OF FENCE.
- SLOPE LENGTHS CAN NOT EXCEED CRITERIA SHOWN IN TABLE 6.62A NORTH CAROLINA EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL. 10. DO NOT INSTALL SEDIMENT FENCE ACROSS STREAMS, DITCHES, WATERWAYS OR OTHER AREAS OF CONCENTRATED FLOW.

MAINTENANCE NOTES:

HIGH HAZARD

TEMPORARY SILT FENCE

- FILTER BARRIERS SHALL BE INSPECTED BY THE FINANCIALLY RESPONSIBLE PARTY OR HIS AGENT IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS NEEDED SHALL BE MADE IMMEDIATELY.
- SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
- 3. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN DEPOSITS REACH HALF THE HEIGHT OF THE BARRIER. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS REMOVED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

GENTLE SLOPES

STEEP SLOPES

SEEDING MIXTURE	80 lbs/acre of tall fesue	100 lbs/acre tall fescue 30 lbs/acre Sericea lespedeza (unscarified after August 15) 10 lbs/acre Kobe lespedeza		
	FALL: August 25 — October Late winter: February 15 — April 15	FALL: August 25 — October 15 Late winter: February 15 — April 15		
SEEDING DATES	To extend spring seeding into June, add 15 lbs/acre hulled Bermudagrass	To extend spring seeding into June, add 15 lbs/acre hulled Bermudagrass		
DATES	Overseeding of Kobe lespedeza over fall—seeded tall fescue is very effective.	Overseeding of Kobe lespedeza over fall—seeded tall fescue is very effective.		
SEEDING AMENDMENTS	Apply lime and fertilizer per soil tests, or 4000 lbs/acre limestone and 1000 lbs/acre 10-10-10 fertilizer.	Apply lime and fertilizer per soil tests, or 4000 lbs/acre limestone and 1000 lbs/acre 10-10-10 fertilizer.		

Ground Cover—— Protective cover must be established on all disturbed areas within 14 calendar days after land disturbing activity is completed or has temporarily ceased.

Graded slopes and fills——Protective cover must be established on all graded slopes and fills within 7 calendar days after a phase of grading is completed or has temporarily ceased.

APPROVED DATE: 02/2007

MECKLENBURG COUNTY LAND DEVELOPMENT STANDARDS

WOVEN FILTER FABRIC-

SEEDING SCHEDULE

STD. NO. REV. 30.17A

NO: C-4063

NORTH ARROW

CORNELIUS, Co. CENTER

VILLAGE

CORNELIUS

BETHEL CHURCH Mecklenbu

19711

NOT TO SCALI

CLASS 1 OR 2 RIP-RAP-_washed stone (ncdot

- 1. SEDIMENT FILTER OUTLET SHALL BE 16 INCHES HIGH BUT NO TALLER THAN 18 INCHES.
- CLASS 1 OR 2 RIP—RAP SHALL BE USED AND COVERED WITH 4 INCHES OF NCDOT #5 OR #57 WASHED STONE ON THE UPSLOPE SIDE.
- 3. POSTS SHALL BE NO MORE THAN 4 FEET APART.

MECKLENBURG COUNTY

STANDARDS

- 4. SITE OUTLETS AT ANY POINT SMALL CONCENTRATED FLOWS ARE ANTICIPATED AND AT THE DIRECTION OF THE INSPECTOR.
- 5. ONE ACRE MAXIMUM DRAINAGE AREA PER OUTLET.

- 1. FILTER OUTLETS SHALL BE INSPECTED BY THE FINANCIALLY RESPONSIBLE PARTY OR HIS AGENT IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS NEEDED SHALL BE MADE IMMEDIATELY.
- 2. THE STONE SHALL BE REPLACED PROMPTLY AFTER ANY EVENT THAT HAS CLOGGED OR REMOVED IT 3. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN DEPOSITS REACH HALF THE HEIGHT OF THE BARRIER. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OUTLET IS REMOVED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

SILT FENCE OUTLET OPTION

STD. NO. | REV. 30.06C

30.06B STANDARDS 1. ALL CONCRETE TO BE 3600 P.S.I. COMPRESSIVE STRENGTH. 2. TYPE OF PIPE TO BE USED IS 1-5/8" MAX. O.D. BLACK IRON, LOW CARBON PIPE OR GALVANIZED. 3. ALL JOINTS TO HAVE A 1/2" FILLET WELD AT ALL JOINTS.

4. AFTER INSTALLATION PAINT ASSMBLY WITH BLACK ALL WEATHER ENAMEL.


APPROVED DATE: 02/2007 5. SEE DETAIL 50.04B FOR WARRANTS MECKLENBURG COUNTY LAND DEVELOPMENT STANDARDS


STD. NO. REV

NOT TO SCALI

NOT TO SCALE

STD. NO. REV





IF ANY CONFLICTS, DISCREPANCIES, OR OTHER UNSATISFACTORY CONDITIONS ARE DISCOVERED, EITHER ON THE CONSTRUCTION DOCUMENTS OR THE FIELD

Drawn By

DEVELOPER/OWNER

HEIDI STODDARD 17914 JOHN CONNOR RD.

CORNELIUS, NC 28031

8/10/16

Sheet C6 of 7 Project Number 16026

PLOTTED: 8/10/2016 CONDITIONS, THE CONTRACTOR MUST NOTIFY THE ENGINEER IMMEDIATELY,
H:__WOODBINEDESIGN_PROJECTS\16026 - 19711 BETHEL
CHURCH ROAD -CVC LOT #1_CAD\CVC-LOT#1-BASE.DWG
OR OTHER UNSATISFACTORY CONDITIONS ARE RESOLVED.

MECKLENBURG COUNTY LAND DEVELOPMENT HANDRAIL SHALL BE INSTALLED UNDER ANY OF THE FOLLOWING CIRCUMSTANCES IN BOTH NEW CONSTRUCTION AND IN

. WHEN THE CULVERT-CROSSING DETAIL (STD. #10.36A-B) APPLIES.

RETROFITTING OR RECONSTRUCTION OF EXISTING ROADWAYS OR SITES:

2. IF THERE IS A 2:1 OR STEEPER FILL SLOPE THAT IS 10 FEET OR TALLER THAT BEGINS WITHIN 5 FEET OF A SIDEWALK.

3. IN ANY OF THE FOLLOWING COMBINATIONS OF DROPOFF AND OFFSET FROM SIDEWALK: a. 18" OR LARGER DROPOFF WITHIN 2 FEET OF THE EDGE OF THE SIDEWALK b. 36" OR LARGER DROPOFF WITHIN 4 FEET OF THE EDGE OF THE SIDEWALK

c. 60" OR LARGER DROPOFF WITHIN 6 FEET OF THE EDGE OF THE SIDEWALK THESE CLEARANCES ASSUME THAT THE CROSS-SLOPE OF THE BERM

BETWEEN THE SIDEWALK AND THE DROPOFF (PEDESTRIAN CLEAR ZONE) IS 6:1 OR FLATTER.

4. AT THE TOP OF ANY DROPOFF WHERE PEDESTRIANS CAN REASONABLY BE EXPECTED IN THE VICINITY.

5. AT THE DIRECTION OF TOWN PUBLIC WORKS OR LUESA LAND DEVELOPMENT STAFF BASED ON FIELD CONDITIONS.

FOR PURPOSES OF THIS STANDARD, THE TERM "SIDEWALK" IS USED GENERICALLY AND SHALL MEAN ANY PATH OR SURFACE TO BE USED FOR BICYCLE AND/OR PEDESTRIAN TRANSPORTATION. EXAMPLES INCLUDE, BUT ARE NOT LIMITED TO, SIDEWALKS, BIKE PATHS, SHARED-USE PATHS, PEDESTRIAN PATHS, AND GREENWAYS.

DEFINITIONS

* DROPOFF -- A SLOPE OF 2:1 OR STEEPER. EXAMPLES INCLUDE HEADWALLS, RETAINING WALLS, AND CULVERTS. * PEDESTRIAN CLEAR ZONE -- 10 FEET OF ANY COMBINATION OF SIDEWALK, SLOPE, AND SHOULDER SLOPED AT 6:1 OR FLATTER. SIDEWALK DOES NOT NEED TO BE PRESENT.

APPROVED DATE: 02/2007

MECKLENBURG COUNTY LAND DEVELOPMENT STANDARDS

HANDRAIL WARRANTS

50.04B

STD. NO. | REV.

TYPICAL HANDRAIL

LAND DEVELOPMENT 50.04A

GENERAL NOTES:

- 1. Locations, elevations, and dimensions of existing utilities, structures and other features are shown according to the best information available at the time of preparation of these plans. The Contractor shall verify the locations, elevations, and dimensions of all existing utilities, structures and other features, affecting this work, prior to construction.
- 2. Prior to the initiation of site construction, the Contractor shall verify any existing utilities including gas, water, electric, cable, TV, communications, sanitary sewers and storm drainage systems, on and/or adjacent to the site. Remove or cap as
- 3. The Contractor shall exercise caution in areas of buried utilities and shall call "ULOCO" at 1—800—632—4949 at least 48 hours prior to construction to arrange for field locations of buried utilities.
- 4. The Contractor is responsible for repairing any damage to existing facilities, above or below ground, that may occur as a result of the work performed by the Contractor or Subcontractors as called for in these contract documents.
- 5. It is the Contractor's responsibility to become familiar with the permit and inspection requirements specified by the various governmental agencies and the Engineer. The Contractor shall obtain all necessary permits prior to construction, and schedule inspections according to agency instruction/requirements.
- 6. The Contractor shall submit shop drawings on all precast and manufactured items to the Owner's Engineer for approval. Failure to obtain approval before installation may result in removal and replacement at the Contractor's expense.
- 7. All utility service stub—outs (water, sanitary sewer, etc.) are to be installed within 5' of buildings, unless otherwise noted on plans.
- 8. Contractor to coordinate with the applicable electric utility supplier regarding any necessary relocation(s) of underground and/or overhead electric facilities and for the location and installation of transformer pad(s) and associated electric facilities.
- 9. <u>Safety:</u>
- A. During the construction and/or maintenance of this project, all safety regulations are to be enforced. The Contractor or his representative shall be responsible for the control and safety of the traveling public and the safety of his/her personnel.
- B. Labor safety regulations shall conform to the provisions set forth by OSHA in the federal register of the Department of Trasportation.
- C. The minimum standards as set forth in the current edition of "NC Department of Transportation Standard Drawings" shall be followed in the design, application, installation, maintenance and removal of all traffic control devices, warning devices and barriers necessary to protect the public and construction personnel from hazards within the project limits.
- D. All traffic control markings and devices shall conform to the provisions set forth the "Manual on Uniform Traffic Control Devices" prepared by the U.S. Department of Transportation Federal Highway Administration.
- E. All subsurface construction shall comply with the "Trench Safety Act". The Contractor shall insure that the method of trench protection and construction is in compliance with the Occupational Safety and Health Administration (OSHA) regulations.
- IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO COMPLY AND ENFORCE ALL APPLICABLE SAFETY REGULATIONS. THE ABOVE INFORMATION HAS BEEN PROVIDED FOR THE CONTRACTOR'S INFORMATION ONLY AND DOES NOT IMPLY THAT THE OWNER OR ENGINEER WILL INSPECT AND/OR ENFORCE SAFETY REGULATIONS.
- 10. It shall be the responsibility of the Contractor to obtain an "On—site Piping Permit" (if required) for construction of the proposed utilities. This permit must be obtained by a duly licensed Plumbing Contractor (or Class A General Contractor) prior to the start of construction. These plans and any subsequent revisions to these plans that are issued by the Engineer, will be subject to the approval conditions of this permit.
- 11. The graphic information depicted on these plans has been compiled to proportion by scale as accurately as possible. However, due to reproductive distortion, reduction, and/or revisions, information contained herein is not intended to be scaled for construction purposes.
- 12. All specifications and documents referenced herein shall be of the latest revision.
- 13. All underground utilities must be in place, tested and inspected prior to base and surface construction.
- 14. Work performed under this contract shall interface smoothly with any other work being performed on—site by other Contractor/Subcontractors and utility companies. It well be necessary for the General Contractor to coordinate and schedule his/her activities accordingly.
- 15. All disturbed areas within the City, County and/or State right—of—way shall be sodded.
- 16. Where applicable utility trenches crossing pavement areas shall be backfilled with granular material in 12—inch layers and compacted to 100% maximum density as determined by AASHTO T—99.
- 17. Contractor shall acquire right—of—way utilization and/or underground utility permits from City, County and/or State prior to construction.
- 18. Contractor shall acquire excavation/fill permit from City, County and/or State for this project.
- 19. Contractor shall be responsible for the restoration of any traffic signal equipment including but not limited to fiber, loop sensors, pull boxes, conduit, traffic signals and cabinets. Any items damaged by the contractor will be restored to their original conditions unless otherwise agreed upon by the County Traffic Engineer.
- 20. The Contractor will import topsoil at no additional cost if necessary.

SHOP DRAWINGS:

- 1. Contractor must provide shop drawings to Architect two
- (2) weeks prior to construction for each of the following components: Sanitary System, Drainage System, Water Distruibution System, and Pavement Sections.
- 2. Refer to specifications for additional requirements.

CLEARING AND SITE PREPARATION NOTES:

- 1. The Contractor shall be responsible for the proper installation of the erosion control devices, as shown on the construction plans, prior to any site clearing and/or demolition. Refer to the "Erosion Control Notes" section contained herein for additional requirements.
- 2. Prior to any site clearing, all trees shown to remain, as indicated on the construction plans shall be protected in accordance with local tree ordinances, and details contained in these plans. It shall be the Contractor's responsibility to maintain these trees in good condition. No tree(s) shown to remain shall be removed without wrintten approval from the Owner and local agency having jurisdiction over these activities.
- 3. The Contractor shall clear and grub only those portions of the site necessary for construction. All disturbed areas must be seeded, mulched, sodded or planted with other approved landscape material immediately following construction.
- 4. The top 4" to 6" of ground removed during clearing and grubbing activities shall be stockpiled to be used for landscaping purposes unless otherwise directed by the Owner. Remaining earthwork that results from clearing and grubbing or site excavation is to be utilized on—site, provided the material is deemed suitable by the Owner's soils testing company. Excess material is to either be stockpiled on—site, as directed by the Owner or Owner's Engineer, or removed from the site. The Contractor shall be responsible for acquiring any permits that are necessary for removing any excess material from the site.
- 5. All existing debris (above or below ground), construction debris and other waste material shall be disposed of off—site by the Contractor in accordance with applicable regulatory agency requirements.
- 6. The contractor is to prepare the site in accordance with the soils report; copies of which are provided in the specifications.
- 7. Contractor to be responsible for installation of temporary construction fence around entire perimeter of property. Type of fence to be submitted by Contractor to Engineer for approval.

EROSION & SILT CONTROL 1. GENERAL

- All erosion and siltation control methods shall be implemented prior to the start of construction. During construction, denuded areas shall be covered by mulches such as straw, hay and filter fabric. All storm sewer inlets in the vicinity of the project shall be protected by approved inlet protection methods. These shall be maintained and modified during the construction process to minimize downstream siltation. When construction is completed, detention areas will be reshaped, cleaned of silt, mud and debris, and re—sodded to properly detain the intended storm quantities.
- 2. PROTECTION AND STABILIZATION OF ON—SITE SOIL STOCKPILES: Fill material stockpiles shall be protected at all times by on—site drainage controls which prevent erosion of the stockpiled material. Control of dust from such stockpiles may be required, depending upon their location and the expected length of time the stockpiles will be present. In no case shall any unstockpiles material remain more than thirty (30) calendar days after substantial project completion.
- 3. PROTECTION OF EXISTING STORM SEWER SYSTEMS:
 During construction, all storm sewer inlets in the vicinity of the project shall be protected by sediment traps such as hardware cloth & gravel, sod, stone, etc.
 Which shall be maintained and modified as required by construction progress, and which must be approved by the Engineer before installation.
- 4. SEDIMENT BASINS AND TRAPS, SEDIMENT TRAPPING MEASURES: Perimeter berms, sediment barriers, vegetative buffers and other measures intended to trap sediment and/or prevent the transport of sediment onto adjacent properties, or into existing bodies of water, must be installed, constructed or, in the case of vegetative buffers, protected from disturbance, as a first step in the land alteration process, such systems shall be fully operative before any other disturbance of the site begins. Earthen structures including but not limited to berms, earth filter, dams or dikes shall be stabilized and protected from drainage damage or erosion within one week of installation.
- 5. ALL SWALES, DITCHES AND CHANNELS: Channels leading from the site shall be sodded with Tall Fescue within three (3) days of excavation.
- 6. THE CONSTRUCTION OF UNDERGROUND UTILITY CONSTRUCTION:
 Underground utility lines and other structures shall be done in accordance with the
- A. No more than 500 linear feet of trench shall be open at any one time;
 B. Wherever consistent with safety and space consideration, excavated material shall be cast to the uphill side of trenches. Trench material shall not be cast into or onto the slope of any stream, channel, road, ditch or waterway.
- 7. ALL EROSION AND SILTATION CONTROL DEVICES SHALL BE MAINTAINED: Checked regularly, especially after each rainfall and will be cleaned out and/or repaired as required.

SECTION 1: GENERAL EROSION CONTROL:

- 1.1 General erosion control best management practices shall be employed to minimze soil erosion and potential pond slope cave—ins. While the various techniques required will be site and plan specific, they should be employed as soon as possible during construction activites.
- 1.2 Cleared site development areas not continually scheduled for construction activities shall be covered with hay or overseeded and periodically watered sufficiently to stabilize the temporary groundcover.
- 1.3 Slopes of banks of retention/detention ponds shall be constructed not steeper than 3:1 from top of bank to two feet below the control elevation.
- 1.4 Sod shall be placed for a 2—foot wide strip adjoining all curbing and around all inlets. Sod shall be placed before silt barriers are removed.

PAINT NOTE:

1. Where applicable double yellow striping, handicap, stop bars and fireline striping to be thermoplastic.

SECTION 2: <u>PROTECTION OF SURFACE WATER QUALITY DURING AND</u> AFTER CONSTRUCTION:

- 2.1 Surface water quality shall be maintained by employing the following best management practices in the construction planning and construction of all improvements.
- 2.2 Where practical, stormwater shall be conveyed by swales.
- 2.3 Erosion control measures shall be employed to minimize turbidity of surface waters located downstream of any construction activity. While the various measures required will be site specific, they shall be employed as needed in accordance with the following:
- A. In general, erosion shall be controlled at the furthest practical upstream
- B. Stormwater inlets shall be protected during construction as shown on plans Protection measures shall be employed as soon as practical during the various stages of inlet construction. Silt barriers shall remain in place until sodding around inlets is complete.
- 2.4 Heavy construction equipment parking and maintenance areas shall be designed to prevent oil, grease, and lubricants from entering site drainage features including stormwater collection and treatment systems. Contractors shall provide broad dikes, hay bales or silt screens around, and sediment sumps within such areas as required to contain spills of oil, grease or lubricants. Contractors shall have available, and shall use, absorbent filter pads to clean up spills as soon as possible after occurrence.
- 2.5 Silt barriers: Any silt which accumulates behind the barriers, and any fill used to anchor the barriers shall be removed promptly after the end of the maintenance period specified for the barriers.
- 2.6 Where required to prevent erosion from sheet flow across bare ground from entering a lake or swale, a temporary sediment sump shall be constructed. The temporary sediment sump shall remain in place until vegetaion is established on the ground draining to the sump.

SECTION 3: CONTROL OF WIND EROSION:

- 3.1 Wind erosion shall be controlled by employing the following methods as necessary and appropriate:
- A. Bare earth areas shall be watered during construction as necessary to minimize the transport of fugitive dust. It may be necessary to limit construction vehicle speed if bare earth has not been effectively watered. In no case shall fugitive dust be allowed to leave the site under construction.
- B. As soon as practical after completion of construction, bare earth areas shall be vegetated.
- C. At any time both during and after site construction that watering and/or vegetation are not effective in controlling wind erosion and/or transporrt of fugitive dust, other methods as are necessary for such control shall be employed. These methods may include erection of dust control fences. If required, dust control fences shall be constructed in accordance with the detail for a silt fence except the minimum height shall be 4 feet

DEMOLITION NOTES:

- 1. Contractor shall submit demolition schedule to Owner prior to proceeding with demolition activities.
- 2. Extent of site clearing is shown on drawings.
- S. Site demolition work includes, but is not limited to:
 - A. RoadwayB. Drainage area

D. Landscaping

- C. Site Utilities
- 4. Conduct site demolition operations to ensure minimum interference with roads, streets, walks, and other adjacent occupied or used facilities. Do not close or obstruct streets, walks or other occupied or used facilities without permission from authorities having jurisdiction.
- 5. Provide protection necessary to prevent damage to existing improvements indicated on plan "Existing To Remain".
- 6. Restore damaged improvements to their original condition, as acceptable to parties having jurisdiction.
- 7. Remove waste materials and unsuitable and excess topsoil from property and dispose of off—site in a legal manner.
- 8. Locate existing above ground and underground utilities in areas of work. If utilities are to remain in place, provide adequate means of support and protection during demolition operation.
- 9. Should uncharted, or incorrectly charted piping or other utilities be encountered during demolition, consult Project Engineer and Utilit; y Owner for immediate action.
- 10. Demolish and completely remove from site material indicated on plan or notes "To Be Removed".
- 11. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout and other hazards created by the demolition operation.
- Furthermore, Contractor shall provide to Engineer photograph of pre—construction conditions and post—construciton conditions as noted on plans.

12. Contractor shall restore all disturbed areas to existing conditions or better.

- 13. Contractor shall maintain stormwater management system during construction to insure no damage to adjacent properties occurs during storm events.
- 14. Contractor to remove all visible or reasonably identifiable material, equipment, etc. from the site if not needed for new construction.

SIGN NOTES:

- Stop signs are to be high intensity grade.
- . Proposed signage shall be in accordance with Local Ordinance.

DEWATERING NOTES:

- 1. During the excavation of the stormwater ponds the Contractor must construct a sediment basin to provide a discharge point for dewatering. The sediment basin can be a cell in the proposed excavation area of a pond or it can be a bermed area above ground. All dewatering must be held in the sediment area until the water is clean such that there would be no turbid discharge. After the water in the sediment basin is clean the water may be released into the existing stormwater system provided there is no adverse impact to the existing system.
- 2. Under no circumstances will the discharge from the dewatering be released directly into on—site wetland areas if present.
- 3. If Contractor encounters silty/clay sand, which may cause the water to become turbid, Contractor shall treat the sediment basin with chemical additive such as allum in order to promote the coagulation of the particles which allow the silts to settle and the water to become less turbid. If turbid water is encountered during excavation of the ponds, the Contractor shall notify the Engineer of record immediately to determine the course of action that is appropriate to eliminate the turbity and allow discharge that meets Water Quality Standards.
- 4. The Contractor shall sequence the excavation of the stormwater ponds such that a sediment basin will be available at all times. The sediment basin can be relocated as necessary subject to the water within the sediment basin being non—turbid and acceptable for discharge off—site.

BEST MANAGEMENT PRACTICES:

Contractor shall ensure compliance with appropriate conditions of Local and/or State Development Regulations pertaining to the Best Management Practices. The Contractor prepared plan shall address the following areas:

- 1. General Erosion Control.
- 2. Protection of surface water quality during and after construction.
- 3. Control of wind erosion.

The various techniques of actions identified under each section indicate the appropriate situation when the techniques should be employed. Also identified is a cross—reference to a diagram or figure representing the technique. It should be noted that the measures identified on this plan are only suggested BMP(S). The Contractor shall provide pollution prevention and erosion control measures as necessary for each specific application.

GRADING AND PAVING NOTES:

pavement meets existing pavement.

- 1. All existing utilities shall be field located and flagged prior to the start of work.
- 2. The Contractor shall remove all vegetation, surplus soil, demolition rubble, and other undesirable materials. Such materials shall be promptly hauled from the site and disposed of in accordance with governing laws and codes. The Contractor shall shape the sub-grade in accordance with the grading plan, taking into account the thickness of the paving system. The tolerance of rough grading shall be within 1/2" high to 1" low.
- 3. Where asphalt paving meets concrete paving such as at concrete curbing, the asphalt should be finished 1/4" to 1/2" above the concrete surface to allow for further traffic compaction of the asphalt.
- 4. A joint plan for the concrete paving shall be prepared by the Contractor and submitted to the Architect for approval. Joints shall be provided along property lines where all driveways cross.
- 5. During preparation of the sub-grade and until the paving is in place, the Contractor shall promptly take reasonable measures to obtain and maintain a dry site condition. Such measures shall include pumping of free surface water, minor hand and/or machine shaping of facilitate water removal and other operations to speed drying.
- 6. All deleterious subsurface material (i.e. mulch, peat, buried debris, etc.) is to be excavated and replaced with suitable/compacted soils as directed by Owner's soils testing company. Deleterious material is to be stockpiled or removed from the site as directed by the Owner, excavated areas are to be backfilled with approved materials and compacted as shown on these plans. Contractor is responsible for acquiring any permits that are necessary for removing deleterious material from the
- 7. The Contractor shall be responsible for protecting excavations against collapse and will provide bracing, sheeting or shoring as necessary. Dewatering methods shall be used as required to keep trenches dry while pipe and appurtenances are being placed.
- 8. All necessary fill and embankment that is placed during construction shall consist of material specified by the Owner's soils testing company of Engineer and be placed and compacted according to these plans.
- 9. Proposed spot elevations represent finished pavement of ground surface grades, unless otherwise noted.10. It may be necessary to field adjust pavement elevations to preserve the root
- systems of trees shown to be save. Contractor to coordinate with Owner's Engineer prior to any elevation changes.

 11. Contractor shall trim, tack and match existing pavement at locations where new
- 12. All traffic control pavement markings shall be made in accordance with Local and/or State Standards.
- 13. The Contractor will stabilize by seed and mulch, sod, or other approved materials any disturbed areas within one week following construction of the utility systems and pavement areas. Contractor shall maintain such areas until final acceptance by Owner. Contractor to coordinate with Owner regarding type of material, landscaping and irrigation requirements.
- 14. The Contractor shall restore off—site construction areas to equal and/or better condition than existing prior to start of construction.
- 15. Unless otherwise noted, grade to meet existing elevation at property lines.
- 16. Survey monuments or benchmarks which have to be disturbed by this work shall be replaced upon completion of work by a registered Land Surveyor.
- 17. Final grades shown include sod height. All areas shall be graded to drain away from the buildings.

 IF ANY CONFLICTS, DISCREPANCIES, OR OTHER UNSATISFACTORY CONDITIONS

PLOTTED: 8/10/2016

H:__WOODBINEDESIGN_PROJECTS\16026 - 19711 BETHEL
CHURCH ROAD -CVC LOT #1_CAD\CVC-LOT#1-BASE.DWG

OR OTHER UNSATISFACTORY CONDITIONS

ARE DISCOVERED, EITHER ON THE CONSTRUCTION DOCUMENTS OR THE FIELD


CONDITIONS, THE CONTRACTOR MUST NOTIFY THE ENGINEER IMMEDIATELY,

AND SHALL NOT COMMENCE OPERATION UNTIL THE CONFLICTS, DISCREPANCIES,

OR OTHER UNSATISFACTORY CONDITIONS ARE RESOLVED.

Woodbine Design, P.C.
Land planning & civil engineering

980.722.2669 704.315.8367



SEAL ROOM NO. C-4063 C NO. C-40

NORTH ARROW

ORNELIUS VILLAGE CENTER LOT #1

19711 BETHEL CHURCH RD., CORNELIUS, NC 28031

Mecklenburg, Co.

NOTES

DEVELOPER/OWNER

HEIDI STODDARD
17914 JOHN CONNOR RD.
CORNELIUS, NC 28031

Designed By

Woodbine Design
Drawn By

PW
Date

8/10/16
Revisions

Sheet C7 Of 7
Project Number 16026