		LETTER OF TRANSMITTAL		
	MSA ARCHITECTS, INC. AAC000895	DATE 03.02.23 JOB NO. 1652		
	8950 SW 74th COURT SUITE 1513	ATTENTION Ben Spivey, Tiffany Yost, John Arnold		
ARCHITECTURE & PLANNING	MIAM, FLORIDA 33156 (305) 273-9911	RE: Tortoise One Apartments		
TO Verdex Construction 840 N. Dixie Highway West Palm Beach, Florida 33401 Phone: (561) 440-1600		SUBMITTAL No. MSA 321/GC 15400-4.1		
WE ARE SENDING YOU Attached Shop Drawings Prints Copy of Letter Change O	Plans	Specifications		
COPIES DATE NO.	DESCRIPTION			
THESE ARE TRANSMITTED as checked <i>below</i> :				
For review Vo exception	on taken	Resubmit copies for approval		
For your use Make corre	ection indicated	Submit copies for distribution		
As requested Rejected/R	lesubmit	Return corrected prints		
For review and comment				
FOR BIDS DUE		Prints returned after loan to us		
REMARKS :				
Refer to attached reviewed submittal by FR	ANYIE Eng., MEP of	f Record.		



Submittal #321 [-Prev. SUB #47-] Submittal #15400-4.1 15400 - Plumbing

Verdex Construction 1545 Centrepark Drive N. West Palm Beach, Florida 33401 Phone: (561) 440-1600 Project: 22-007 - Tortoise One Apartments 840 N. Dixie Highway West Palm Beach, Florida 33401

Grease Interceptor

SPEC SECTION:	15400 - Plumbing	SUBMITTAL MANAGER:	Dario Freijanes (Verdex Construction)
STATUS:	Open	DATE CREATED:	02/23/2023
ISSUE DATE:	02/23/2023	REVISION:	1
RESPONSIBLE CONTRACTOR:	Alpadex Plumbing, LLC	RECEIVED FROM:	
RECEIVED DATE:		SUBMIT BY:	
FINAL DUE DATE:	03/6/2023	LOCATION:	
SUB JOB:		COST CODE:	
	Pen Snivey (Verdex Construction) Jim Devicion (Verdex Construction) Fileen Disz (MSA Architecto June)		

APPROVERS: Ben Spivey (Verdex Construction), Jim Danielson (Verdex Construction), Eileen Diaz (MSA Architects, Inc.)

BALL IN COURT:

Jim Danielson (Verdex Construction), Eileen Diaz (MSA Architects, Inc.)

DISTRIBUTION:

Michael Conley (Verdex Construction), Jim Danielson (Verdex Construction), Eileen Diaz (MSA Architects, Inc.), Dario Freijanes (Verdex Construction), Luis Velez (MSA Architects, Inc.), Tiffany Yost (Hensel Phelps)

DESCRIPTION:

ATTACHMENTS:

SUBMITTAL WORKFLOW

NAME	SUBMITTER/ APPROVER	SENT DATE	DUE DATE	RETURNED DATE	RESPONSE	ATTACHMENTS	COMMENTS
Andre Leslie	Submitter		9/19/2022	2/23/2023	Submitted	GREASE INTERCEPTOR Submittal (CORRECTED).pdf	
Ben Spivey	Approver	2/23/2023	3/9/2023	2/23/2023	For Record Only	<u>GREASE</u> INTERCEPTOR <u>Submittal</u> (CORRECTED).pdf	
Jim Danielson	Approver	2/23/2023	3/6/2023		Pending		
Eileen Diaz	Approver	2/23/2023	3/6/2023		Pending		

TORTOISE ONE APARTMENTS

GREASE INTERCEPTOR


	V		
	SHOP DRAWIN	IG / SUBMITTAL REVIEW	
X Reviewed	Reviewed As Noted	Revised and Resubmit	Rejected
expressed in the Contra deviations from require	act Documents. Review of Sul ments of the Contract Docume	formance with information given omittals does not relieve the sub- ints by review/approval of submit	mitting entity of responsibility for
expressed in the Contra deviations from require	act Documents. Review of Sul	omittals does not relieve the sub- ents by review/approval of submit ns of the Contract Agreement.	mitting entity of responsibility for
expressed in the Contra deviations from require approval of such deviat	act Documents. Review of Sut ments of the Contract Docume ion per the terms and condition	omittals does not relieve the sub- ents by review/approval of submit ns of the Contract Agreement.	mitting entity of responsibility for the second structure of the second se
expressed in the Contra deviations from require approval of such deviat Submittal: #1	act Documents. Review of Sub ments of the Contract Docume ion per the terms and condition Project: 22-007	omittals does not relieve the subi ints by review/approval of submit ns of the Contract Agreement. Tortoise One	mitting entity of responsibility for the second structure of the second se

	SD# 321			
SEE NOTES	REVISE & RESUBMIT			
with the information given dimensions to be confirmed a coordination of all trades. Any conflict found in the Co Drawings must be brought to Any deviation from the Contr noted and highlighted in these Any such item not clearly not The submittal of these shop	nce with the design concept of the project and compliance in the M/E/P Drawings. Contractor is responsible for it the job site for means and methods of construction, and ntract Documents during the preparation of these Shop the attention of the A/E of Record. act Documents (or proposed substitution) must be clearly a Shop Drawings in order to receive specific consideration. ed is to be considered rejected. drawings indicate acceptance by the contractor that the s contract and no additional costs are involved.			
BY: E. Recio	DATE: March 1, 2023			
FRANYIE ENGINEERS, INC.				

GB-250

Great Basin[®] High Efficiency Grease Interceptor Technical Data

Submittal | Special Precautions | Specifications | Installation | Application Specific Details



SUBMITTAL

STANDARD: 4" plain end inlet/outlet | Capacities - Liquid: 275 gal. (1,041 L); Grease: 1,076 lbs. (488.1 kg) (147.4 gal./558 L); Solids: 105 gal. (397.5 L); Highway traffic load rated, bolted, gas/water tight composite covers. (16,000 lbs.)

APPROVAL:

OPTIONS:

4" Male Thread Inlet/Outlet High Water Anchor Kit Signature: 6" Plain End Inlet/Outlet **TeleGlide Risers** 6" Male Thread Inlet/Outlet Date: **SR24** (x2) 5" – 23" (stainless steel) LR24 (x2) >23" - 38" Company: Pedestrian Rated Covers - 2,000 lbs. **SR24** (x4) >38" - 43" H20 Load Rated Pickable Specifying Engineer: SR24 (x2) + LR24 (x2) >43" - 58" Cast Iron Covers **LR24** (x4) >58" - 72" **Engineering Firm:** Integral Membrane Clamping Collar Kit Pumpout Port (Large) MODEL NUMBER: DESCRIPTION: Polyethylene Grease Interceptor **GB-250** 100 GPM - 275 gallon capacity

LIFETIME GUARANTEED GREASE INTERCEPTORS PART #: 4055-001-XX DWG BY: B. Karrer DATE: 10/08/2015 REV: 3

10/13/2017

9500 Woodend Road | Edwardsville, KS 66111 | Tel: 913-951-3300 | Fax: 913-951-3399 | www.schierproducts.com


ECO:

page 1 of 7




Installation Instructions

Installation instructions and additional components are located inside the interceptor. Read all instructions prior to installation. This interceptor is intended to be installed by a licensed plumber in conformance with all local codes.




When Installing Interceptor Inside

If your dishwashing sink(s) discharges into a floor drain/sink (drain), you must regulate the flow into the drain to avoid an overflow of water onto the kitchen floor. This can be done by installing a valve or flow restriction cap on the sink piping that discharges into the drain. See drawing below for guidance. For detailed guidance on indirect connections, go to: http://webtools.schierproducts.com/Technical_Data/Indirect_Connections.pdf




Hydrostatic Slabs (or Pressure Slabs)

When installed under a hydrostatic slab (slab designed to withstand upward lift, usually caused by hydrostatic pressure) interceptor must be enclosed in a watertight concrete vault. Failure to follow this guidance voids your warranty.



High Temperature Kitchen Water


If water is entering the interceptor at excessive temperature (over 140° F), a drain water tempering valve (DTV) must be installed. Most state and local plumbing codes prohibit water above 140° F being discharged into the sanitary sewer. Water above 140° F will weaken or deform PVC Schedule 40 pipe, poly drainage fixtures like interceptors and erode the coating of cast iron (leading to eventual failure). Failure to follow this guidance voids your warranty.



High Water Table Installations

Interceptors and risers are not designed to withstand water table height in excess of the top of the unit when buried (see figure). If it is possible for this to occur, install the interceptor and risers in a water-tight concrete vault or backfill with concrete or flowable fill (wet concrete and flowable backfill should be poured in stages to avoid crushing the interceptor). At risk areas include but are not limited to tidal surge areas, floodplains and areas that receive storm water. Failure to follow this guidance voids your warranty.

Models GB-50, GB-75, and GB-250 that are direct buried in high water table scenarios must be installed with model AK1 anchor kit or warranty is void.





SPECIFICATIONS

NOTES

- **1.** 4" plain end inlet/outlet
- 2. Unit weight w/composite covers: 230 lbs.; w/cast iron covers: 340 lbs. (For wet weight add 2290 lbs.)
- Maximum operating temperature: 140° F continuous
 Capacities Liquid: 275 gal.; Grease: 1,076 lbs. (147.4
- gal.); Solids: 105 gal.
- **5.** Built-in Flow control.
- For gravity drainage applications only.
 Do not use for pressure applications.
- B. Cover placement allows full access to tank for proper maintenance.
- 9. Vent not required unless per local code.
- **10.**Engineered inlet and outlet diffusers are removable to inspect/clean piping.
- **11.** Integral air relief / Anti-siphon / Sampling access.

DIFFUSION FLOW TECHNOLOGY

The inlet diffuser splits influent into three paths, creating laminar flow and utilizing the entire liquid volume of the tank for efficient grease separation. The calibrated openings greatly reduce effluent turbulence. The effluent enters the main chamber without disturbing the existing grease or sediment layers.


The integral air relief/anti-siphon in the top of the outlet diffuser allows pressure stabilization within the unit during operation. The bottom of the outlet diffuser allows only effluent which is free of grease to exit the tank. It can easily be attached to any of the three outlets provided to ease job site piping layouts.


ENGINEER SPECIFICATION GUIDE


Schier Great Basin[™] grease interceptor model # GB-250 shall be lifetime guaranteed and made in USA of seamless, rotationally-molded polyethylene. Interceptor shall be furnished for above or below grade installation. Interceptor shall be certified to ASME A112.14.3 (type C) and CSA B481.1, with field adjustable riser system, built-in flow control, built-in test caps and three outlet options. Interceptor flow rate shall be 100 GPM. Interceptor grease capacity shall be 1,076 lbs. Cover shall provide water/gas-tight seal and have minimum 16,000 lbs. load capacity.


CERTIFIED PERFORMANCE

Great Basin hydromechanical grease interceptors are third party performance-tested and listed by IAPMO to ASME #A112.14.3 and CSA B481.1 grease interceptor standards and greatly exceed requirements for grease separation and storage. They are compliant to the Uniform Plumbing Code and the International Plumbing Code.











INSTALLATION (1 of 3)

WARNING! DO NOT AIR TEST UNIT OR TELEGLIDE RISER SYSTEM! Doing so may result in property damage,

personal injury or death.

LEAK/SEAL TESTING

Cap/plug all base unit plumbing connections and remove covers. For base unit testing, fill with water to just above the highest connection. For riser system testing (if required) fill with water to finished grade level. CAUTION: Risers must be supported before filling with water to prevent tipping. Inspect unit, connections and all gaskets and clamps (if applicable) for leaks. Check water level at specific time intervals per local code.

GENERAL INSTALLATION INSTRUCTIONS

Schier grease interceptors are manufactured with an internal flow control system. They do not require an external flow control system or air intake vent. Schier grease interceptors are not to be installed in any other manner except as shown. Consult local codes for separate trapping requirements, cleanout locations and additional installation instructions.

- 1. The **flow control plate is not installed** on this unit. When the unit is installed 13 feet or more below the fixtures that flow into the unit, or a high flow/increased head pressure condition exists (causing a flow rate above 100 GPM), install the inlet diffuser flow control plate to maintain proper flow rate.
- 2. Set unit on level solid surface as close as possible to fixtures.
- **3.** Connect outlet diffuser to the desired outlet (A,B,C). Unit is shipped with the outlet diffuser in leasting A and C.
- the outlet diffuser in location B and sealing caps on locations A and C.
 4. Connect inlet and outlet drainage lines to unit. Mechanically couple pipes to unit. Do not solvent weld.

5. For units with cast iron covers, remove retainer clips prior to burial.

NOTE: Do not install below a hydrostatic slab.

BELOW GRADE INSTALLATION INSTRUCTIONS

EXCAVATION

- 1. Surrounding soil must be undisturbed soil or well compacted engineering fill.
- 2. Width and length of excavation shall be a minimum of 12" greater than the tank on all sides and depth shall be 6" deeper than tank bottom.
- **3.** Set the tank level on a 6" deep layer of well-packed crushed aggregate material and connect waste piping per General Installation Instructions.

BACKFILL


- 1. Preparation of sub grade per geotech recommendations.
- 2. Stabilize and compact sub grade to 95% proctor.
- **3.** Fill unit with water before backfilling to stabilize unit and prevent float-out during backfilling. Secure covers and risers (if necessary) to the unit.
- Backfill evenly around tank using crushed aggregate (approximately 3/4" size rock or sand, with no fines), or flowable fill. Do not compact backfill around unit.


FINISHED CONCRETE SLAB

Slab must extend 18" minimum outside the unit footprint.


Pedestrian traffic or greenspace areas: 4" Thick reinforced concrete slab required.

Vehicular traffic areas: Minimum 8" Thick concrete slab with rebar required; final thickness of concrete around cover to be determined by specifying engineer. If traffic loading is required the concrete slab dimensions shown are for guideline purposes only. Concrete to be 28 day compressive strength to 4,000 PSI. Use NO. 4 rebar (Ø1/2") grade 60 steel per ASTM A615: connected with tie wire. Rebar to be 2-1/2" from edge of concrete and spaced in a 12" grid with 4" spacing around access openings.





BACKFILL DETAIL



SIDE VIEW DETAIL TOP VIEW 18" 18" min min ¥. 18" min Concrete Slab-4"Thick for pedestrian 4 8" Thick for vehicular ¥ Rebar 18" min 4 ELEVATION VIEW Finished grade





INSTALLATION (2 of 3)

TELEGLIDE RISER (24 SERIES) INSTALLATION GUIDELINES

Tools needed: 7/16" Nut driver tool/bit (included), marker (included), tape measure and drill with 1/2" chuck. Jigsaw, circular saw or reciprocating saw will be needed if risers need to be cut.

NOTE: To remove a component or adjust its position, the Upper Band Clamp needs to be loosened or removed using nut driver bit. Loosened clamps should be re-tightened to 5 - 8 ft lbs. of torque (same as a rubber no-hub coupling). The Lower Band Clamp is factory set and should not be adjusted or removed.

Riser Assembly Instructions/Steps

- 1. Set unit so the pipe connections line up with job site piping and measure riser height needed from top of cover to finished grade. See Table 1 to select risers needed.
- 2. Remove covers from adapters. Remove adapters from main unit. On a level surface, per-assemble the risers and adapters, adjusting the components upwards or downwards to achieve the riser height needed. Make sure to maintain minimum and maximum insertion depths as shown in Figure 2. If components are too long, make a circular line around the sidewall with marker and cut with a power saw. The lowest cut line on the riser assembly will be 6" beyond the riser height needed to allow for ideal insertion depth (See Figure 1). An alignment mark should be drawn 2" beyond the riser height needed which will align with the top of the base unit gasket. **DO NOT** cut the alignment mark. The Adapters and risers should sit level with each other. Tighten upper clamps to keep riser/adapter assembly from shifting. Make alignment marks on the sidewalls at the top of all riser gaskets to aid final assembly.
- 3. **IMPORTANT:** Before the next step, make sure both diffusers are installed inside the main unit at the appropriate locations. Check if there needs to be any flow control adjustment at the inlet diffuser (see general installation instructions).
- 4. Take apart riser assembly and clean all sidewalls and insides of gaskets to remove dust/debris. Install components into the main unit starting from the lowest riser and work your way up to finished grade. Ensure that riser will not interfere with diffuser, allow min. 1" clearance. Maintain minimum and maximum insertion depths for all components (see Figure 2). Tighten Upper Clamps to specified torque after correctly positioning components. Riser assembly may need to be supported during backfill.
- 5. If tilting of the adapter is required to be flush with grade, do so AFTER all clamps have been tightened with riser(s)/adapter in a vertical and level position. Tilting is done using gasket flexibility. Tilting before tightening clamps may ruin a perfect gasket seal. Schier recommends tilting only the adapter versus the entire riser assembly to make sure your riser height and proper tank access is maintained.
- 6. If riser height conditions change after completing above steps, there may be room for adjustment. As long as minimum and maximum insertion depths are maintained (see Figure 2), the adapters/risers can be adjusted/cut as many times as necessary. When riser system installation is complete, see Leak/Seal Testing procedure if required (pg 3 of 6).

ANCHOR KIT INSTALLATION

Stainless steel anchor kit is recommended for installation in high water table conditions to prevent float out. Necessity to be determined by specifying engineer. Hold down force achieved by backfill weight acting on Anchor Plate.

Slide Anchor Hook over tie down point on end wall and bolt to Anchor Strap. Bolt Anchor Strap to Anchor Plate using provided stainless steel hardware. If required, Anchor Plate may be bolted to concrete slab using provided holes.







SR24


Short Riser


LR24

Long Riser









ANCHOR KIT INSTALLATION DETAIL



INSTALLATION (3 of 3)

EXPANDING GREASE CAPACITY

Multiple grease interceptor configurations must be piped as shown to ensure the system works properly as designed. For below grade installations, all units must be level in the excavation pit. Hybrid systems combining parallel and series installations are available per written approval from Schier.

All inlet manifolds, outlet manifolds, piping between units and two-way cleanout tees by others.

Series Installation of Multiple Grease Interceptors

For lower flow rates and higher grease storage requirements.

For below grade installations it is recommended to install a two-way cleanout tee extended to finished grade before the inlet of the first unit, after the outlet of the last unit and in between units (if there is a long run of pipe between units) for line cleaning purposes.

NOTE: When the flow control plate is required, it should only be installed on the first unit in the series.


Parallel Installation of Multiple Grease Interceptors


For flow rates above 100 GPM and higher grease storage requirements.

Units must be equally spaced to ensure equal effluent flow distribution.

For below grade installations it is recommended to install a two-way cleanout tee extended to finished grade before and after each unit for line cleaning purposes.


Flow Splitter™ (FS-DUO, FS-TRIO, FS-QUAD) sold separately.







APPLICATION SPECIFIC DETAILS



9500 Woodend Road | Edwardsville, KS 66111 | Tel: 913-951-3300 | Fax: 913-951-3399 | www.schierproducts.com