

Luminaire Schedule

Project: EMERALD GREENS - SITE OKECHOMEE, FL 09/03/2019

Symbol	Qty	Label	Arrangement	Manufacturer	Description	Luminaire Lumens	LLP	Luminaire Watts	Assembly Watts
	7	SA	SINGLE	Lithonia Lighting	DSX1 LED P9 40K T9W MVOLT MINI POLE MOUNT A.F.S.	2842	0.903	241	241
	23	SB	SINGLE	Lithonia Lighting	DSX1 LED P9 40K T9W MVOLT MINI POLE MOUNT A.F.S.	27377	0.903	241	241
	7	SC	SINGLE	Lithonia Lighting	DSX1 LED P9 40K T9W MVOLT MINI POLE MOUNT A.F.S.	14437	0.903	126	126
	31	SD	SINGLE	Lithonia Lighting	RADPT P4 40K PATH MINI-POST TOP MOUNT A.F.S. (Top of Future)	8599	0.903	85.6762	85.6762
	42	SE	SINGLE	Lithonia Lighting	RADPT P4 40K PATH MINI-POST TOP MOUNT A.F.S. (41.9" BOLLARDS)	293	0.903	8.21	8.21
	20	SW	SINGLE	Lithonia Lighting	TWS LED P1 50K MVOLT PL MINI WALL MOUNT A.F.S. (Bottom of Future)	2086	0.855	18.6	18.6

Calculation Summary

Project: EMERALD GREENS - SITE OKECHOMEE, FL 09/03/2019

Label	Calc Type	Units	Avg	Max	Min	Avg/Wk	Max/Wk
PARKING LOT	Maintenance	Ft.	2.99	7.8	0.7	3.70	10.71
RESIDENT'S STORAGE	Ft.	2.55	7.5	0.8	3.66	8.88	
LAKE SIDEWALKS	Maintenance	Ft.	2.21	6.1	0.5	4.42	12.29
WALK BIWAY	Maintenance	Ft.	6.48	8.8	3.1	5.77	27.4
PERIMETER SIDEWALKS	Maintenance	Ft.	1.91	7.8	0.5	3.22	12.29

