

FLOOR PLAN GENERAL NOTES


- CONTRACTOR MUST VERIFY ALL INTERIOR AND EXTERIOR DIMENSIONS.
- CALL ARCHITECT IMMEDIATELY IF THERE ARE ANY DISCREPANCIES.
- REFER TO A601 FOR DOOR & WINDOW SCHEDULE & DETAILS.
DOORS MARKED AS **101**
WINDOWS/ STOREFRONT MARKED AS **A**
- REFER TO A311 THROUGH A312 FOR WALL SECTIONS.
- COORDINATE LOCATION OF DOORS WITH TENANT IMPROVEMENT DRAWINGS BEFORE INSTALLATION.
- CONTRACTOR NOTIFY TENANT A MINIMUM OF TWO WEEKS PRIOR TO SLAB POURING FOR COORDINATION.
- DETAILS MARKED AS "O.H." TO BE OPPOSITE HAND AND "SIM." TO BE SIMILAR.

GENERAL NOTES


- GENERAL CONTRACTOR SHALL DELIVER A LEVEL AND SMOOTH CONCRETE SLAB FREE OF LEVELING PRODUCTS WITH NOT MORE THAN ONE QUARTER INCH (1/4") VARIATION IN TEN FEET (10'). ALL EXPANSION AND CONTROL JOINTS SHALL BE PROPERLY INSTALLED AND SHALL BE READY TO ACCEPT TENANT'S FLOOR FINISHES. FLOOR SLAB SHALL BE BROOM CLEAN, FREE OF TRASH AND DEBRIS.
- REVIEW DOCUMENTS, VERIFY DIMENSIONS AND FIELD CONDITIONS, AND CONFIRM THAT WORK IS BUILDABLE AS SHOWN, REPORT ANY CONFLICTS OR OMISSIONS TO THE ARCHITECT FOR CLARIFICATION PRIOR TO PERFORMING ANY WORK IN QUESTION.
- DO NOT SCALE DRAWINGS. IF DIMENSIONS ARE IN QUESTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING CLARIFICATIONS FROM THE ARCHITECT.
- PARTITIONS ARE DIMENSIONED FROM FINISH FACE TO FINISH FACE, U.N.O. MAINTAIN DIMENSIONS MARKED CLEAR, ALLOW FOR THE THICKNESS OF FINISHES AS REQUIRED.
- ALL CONSTRUCTION TO COMPLY WITH ALL APPLICABLE STATE AND LOCAL BUILDING CODES, REGULATIONS, AND CITY ORDINANCES.
- REFER TO SHEET A601 FOR DOOR/FRAME/HARDWARE TYPES AND SCHEDULES.
- ALL NEW DOORS TO HAVE ADA COMPLIANT LEVER HARDWARE SETS, U.N.O. REFER TO A601 FOR DOOR/HARDWARE SCHEDULES.
- CAULK AT JUNCTURE OF INTERIOR FACES OF DOOR FRAMES, VIEW WINDOW FRAMES, EXT. WINDOW FRAMES, CABINET WORK, AND CASEWORK W/ADJACENT MATERIALS EVEN THOUGH JOINT MAY NOT BE VISIBLE.
- G.C. TO PROVIDE HM DOORS & FRAMES AT SERVICE ROOMS, VERIFY W/ OWNER FOR DOOR LOCATIONS.

FLOOR PLAN KEYNOTES

- | | |
|----|---|
| 1 | REINFORCED CONCRETE FLOOR SLAB, LEVEL & SMOOTH, RE: STRUCTURAL |
| 2 | CONCRETE LEAVE OUT 5'-0" WIDE COORDINATE WITH STRUCTURAL DRAWINGS |
| 3 | STEEL TUBE COLUMN, RE: STRUCTURAL DWGS |
| 4 | ELECTRICAL GUTTER LOCATION, RE: ELECTRICAL DWGS |
| 5 | SCHEDULED STOREFRONT WINDOW SYSTEM, RE: A601 |
| 6 | SCHEDULED STOREFRONT DOOR SYSTEM, RE: A601 |
| 7 | SCHEDULED HOLLOW METAL DOOR, RE: A601 |
| 8 | PREFABRICATED METAL CANOPY ABOVE, RE: SECTIONS |
| 9 | ROOF ACCESS LADDER, RE: A3/A314 |
| 10 | SCHEDULED PREFINISHED ROOF SCUPPER & DOWNSPOUT, RE: A1 & B1/A521 |
| 11 | NOT USED |
| 12 | FIRE RISER ROOM |
| 13 | GAS LEAVE OUT, RE: STRUCTURAL PLAN |
| 14 | 1HR RATED FIRE PARTITION WALL |
| 15 | DRIVE THROUGH WINDOW, RE: A601 |



A1 OVERALL FLOOR PLAN
SCALE: 1/8" = 1'-0"



© 2024 IDENTITY ARCHITECTS INC.
Under the Copyright Act, 17 U.S.C. as amended December 1, 1990, also known as the "Architectural Works Protection Act of 1990", these documents are copyrighted and are subject to copyright protection as an "Architectural Work". The design, spatial form, ideas, compositions and arrangement of forms delineated in this set of plans are the property of Identity Architects. Unauthorized use of these plans can legally result in the cessation of such construction or building being seized and razed.

OWNER:
AHV Enterprises, LLC
94 Heathrow Lane
Sugarland, TX 77479
Email : hpkolluru@yahoo.com
Ph.No : (281)543-8818

CIVIL:
Amani Engineering, Inc.
11011 Richmond ave.
Houston, TX 77042
Email :
dbrown@amaniengineering.com
Ph.No : (713)270-5700-104

STRUCTURE:
Paramount Engineering LLC
10145 Long Point Rd.
Houston, TX 77043
Ph. No. : (713) 636-9977 /
(281) 888-9128
M. (832) 470-5791
www.pelictx.com

MEP:
EBE, Inc.
12603 Southwest Freeway, Suite 170
Stafford, TX 77477
Email : cdoehn@ebemce.com
Ph. no. : (713)840-0711

LANDSCAPE:
CMB Landscape Architecture
18135 FM 362
Navasota, Texas 77868
Attn: Charles Bridges
832-428-1209
cbridges@cmlandarch.com

NO.	DATE	REVISION ISSUE
	11.30.2023	ISSUE FOR PERMIT
A	03.01.2024	CITY COMMENTS 1
B	04.15.2024	CITY COMMENTS 2
0	07.15.2024	ISSUE FOR CONSTRUCTION

PROJECT NAME AND ADDRESS:
FULSHEAR GATEWAY BUILDING A

7385 FM 389 RD S
FULSHEAR (FORT BENT COUNTY),
TEXAS 77441

DRAWN: MC.PG PROJ. MGRBC

REFERENCE NUMBER: **23012-02**

TITLE:
OVERALL FLOOR PLAN

DRAWING NUMBER:

A101