



KEY NOTES

1. ALL POWER/TELE/DATA SHOWN IS NEW. TYPICAL THROUGHOUT. SURFACE MOUNT RECEPTACLES WHERE LOCATED AT CONCRETE BLOCK WALLS. V.I.F.
2. PROVIDE NEW FLUSH FLOOR OUTLET. GC TO VERIFY EXACT LOCATION WITH TENANT. SAW CUT FLOOR AS REQUIRED TO NEAREST WALL AT GROUND FLOOR. PROVIDE 1" DIA. CONDUIT TO NEW CREDENZA AND J-BOX, FOR FUTURE CONNECTION TO PLASMA SCREEN OR CEILING PROJECTOR.
3. PROVIDE NEW 2-TON 24,000 BTU 24 HOUR A/C FOR SERVER ROOM. NEW A/C UNIT TO BE ROOF MOUNTED AND DUCTED TO THIS ROOM.
4. PROVIDE NEW 4' X 8' X $\frac{3}{4}$ " FIRE RETARDANT TREATED PLYWOOD BACKBOARD. MOUNT TOP OF BOARD AT CEILING AND FINISH TO MATCH ADJACENT WALL.
5. PROVIDE NEW WALL BACKING WITH DUPLEX OUTLET AND DATA JACK AT +60" A.F.F. FOR NEW PLASMA SCREEN. PROVIDE CONDUIT AND J-BOX AT BACK OF NEW CREDENZA FOR VCR CONNECTION TO PLASMA SCREEN.
6. ALL FURNITURE SHALL BE PROVIDED AND INSTALLED BY TENANT. U.O.N.
7. PROVIDE NEW CONDUIT AND J-BOX FOR LOW VOLTAGE CARD READER SYSTEM WHERE SHOWN. (2) LOCATIONS TOTAL. CONFIRM EXACT LOCATION IN FIELD WITH OWNER. NOTE: OWNER TO PROVIDE CARD READERS.
8. NOTE: POWER IS REQUIRED ON THE ROOF PARAPET, FOR OWNER'S EXTERIOR SIGNAGE. REFER TO ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.
9. PROVIDE DUPLEX OUTLET MOUNTED TO THE UNDERSIDE OF FLOOR JOISTS ABOVE FOR FUTURE PROJECTOR. ALSO PROVIDE J-BOX AND 3/4" CONDUIT TO STRUCTURAL COLUMN. SURFACE MOUNT CONDUIT AND J-BOX ON COLUMN AT +18" A.F.F. FOR FUTURE COMMUNICATION CABLE TO PROJECTOR.
10. PROVIDE NEW WALL BACKING WITH DUPLEX OUTLET AND DATA JACK AT +60" A.F.F. FOR NEW PLASMA SCREEN.

EQUIPMENT LIST

- UNDERCOUNTER REFRIGERATOR
- GARBAGE DISPOSER
- INSTA-HOT WATER HEATER
- COFFEE MAKER
- PLASMA SCREEN
- MICROWAVE

LEGEND

- SHADED AREA N.I.C. (NOT IN CONTRACT).
- WALL MOUNTED RECEPTACLE
- FLUSH WALL MOUNTED DUPLEX
- FLUSH WALL MOUNTED DEDICATED DUPLEX
- FLUSH WALL MOUNTED DEDICATED SWITCHED DUPLEX
- FLUSH WALL MOUNTED DEDICATED DUPLEX
- FLUSH WALL MOUNTED DEDICATED FOURPLEX
- FLUSH WALL MOUNTED TELE/DATA RECEPTACLE
- FLUSH FLOOR MOUNTED DUPLEX
- FLUSH FLOOR MOUNTED FOURPLEX
- FLUSH FLOOR MOUNTED TELE/DATA RECEPTACLE
- FLUSH WALL MOUNTED TELEPHONE RECEPTACLE
- FLUSH FLOOR MOUNTED, POKE-THRU, COMBINATION QUADRAPLEX & VOICE/DATA RECEPTACLES
- FLUSH WALL-MOUNTED VOICE/DATA IN-FEED FOR CONNECTION
- FLUSH WALL MOUNTED POWER JUNCTION BOX WITH HARDWIRE CONNECTION
- COMBINATION FLUSH FLOOR JUNCTION BOX WITH HARDWIRE CONNECTION
- CARD READER
- ELECTROMAGNETIC DOOR HOLDER WITH RELAY TO FIRE/LIFE SAFETY ALARM SYSTEM
- +XX" DENOTES SPECIAL HEIGHT
- \$ SWITCH
- E DENOTES EXISTING
- M DENOTES MODIFY

SHEET NOTES

1. THE BLDG STD WALL MOUNTED TELEPHONE AND DATA OUTLETS SHALL BE A SINGLE GANG OUTLET BOX VERTICALLY MOUNTED IN WALL AT 18" A.F.F. TO CENTERLINE OF BOX, WITH 3/4" METAL CONDUIT STUBBED UP 8" ABOVE CEILING GRID WITH PULL STRING INSTALLED BY THE GENERAL CONTRACTOR. COVERPLATE BY TELEPHONE INSTALLER.
2. ALL FURNITURE AND EQUIPMENT SHOWN ARE NOT IN THE CONTRACT UNLESS OTHERWISE NOTED.
3. ALL OUTLETS ARE NEW UNLESS INDICATED WITH AN "E" FOR EXISTING. ALL NEW ELECTRICAL OUTLETS TO BE INSTALLED @ 18" A.F.F., TO COMPLY WITH TITLE 24 REQUIREMENTS.
4. WHEN INDICATED, REMOVE OUTLETS AND SAFE-OFF TO SOURCE. WALLS AND/OR FLOORS AT REMOVED OUTLET LOCATIONS SHALL BE PATCHED AND PREPARED FOR FINISH.



STREAMLINE SOLUTIONS
9930 IRVINE CENTER DRIVE
IRVINE, CA 92618

Gensler

4675 MacArthur Court
Suite 350
Newport Beach, CA 92660
Telephone 949.863.9434
Facsimile 949.553.1676

Issue	Date & Issue Description	By	Check
01	05/12/09	SO	SB
ISSUE FOR ENGINEERING			
02	05/20/09	SO	DL
RE-ISSUE FOR ENGINEERING			
03	05/27/09	SO	SB
RE-ISSUE FOR ENGINEERING			
04	05/29/09	SO	SB
RE-ISSUE CLIENT REVISIONS FOR ENGINEERING			
05	06/03/09	SO	SB
ISSUE FOR PLAN CHECK & BID			

Seal/Signature

Project Name
STREAMLINE SOLUTIONS

Project Number
07.91350.050

CAD File Name
A03-01

Description
POWER & COMM. PLAN
FIRST FLOOR

Scale 1/4"=1'-0"

0 1' 2' 4' 8'

A03.01

©2009 Gensler