



(605) 431-2778
wrightwellservicesllc@gmail.com
13116 Cliff Drive
Piedmont, SD 57769

Well Test Report – North Well

Location:

21305 Vanocker Canyon Rd.

Well Construction Details:

- Total Depth: 65 feet
- Casing: 6-inch PVC
- Static Water Level (pre-test): 25 feet

Pumping Test Details:

- Test Duration: 90 minutes
- Pumping Rate: 8 gallons per minute (GPM)
- Static Water Level During Pumping: Stabilized at approximately 45 feet

Observations & Results:

The well was pumped continuously for 90 minutes at a rate of 8 GPM. Throughout the test, the well maintained a consistent flow rate with a stabilized static water level at 45 feet. No excessive drawdown or recovery issues were observed during the testing period.

Conclusion:

Based on the pumping test performed, the well demonstrated the ability to sustain an 8 GPM flow rate. This production level is considered sufficient to support typical domestic household use at the time of testing.