

Wayne Fazzinga

39 Babbitt Road
Bedford Hills, NY 10507
914-242-3646 • Fax: 914-242-5412



Carpentry
Roofing
Custom Copper Work
Serving the community for over 25 Years

August 23rd, 2021

Mr. Tony Giardina
PO Box 158
Mt. Kisco, NY 10549

For Services Rendered at 9 Kiskon Avenue, Mt Kisco

New Roof (4 Family Structure)

1. Removed existing layer of roofing down to sheathing.
2. Removed rotted sheathing. (1 Sheet)
3. Furnished and installed the following:
 - ½" CDX Plywood sheathing
 - F- 5 ½ Brown aluminum drip edge to eaves
 - 6' of GAF Weather Watch Ice and Water Shield at eaves
 - GAF Tiger Paw Underlayment to remainder
 - GAF Weather Blocker starter shingles
 - GAF Lifetime Timberline HD Dimensional roof shingles (Color: Charcoal)
 - (2) 3" Custom copper vent pipe flashing
 - GAF Snow Country ridge vent (5')
 - GAF Timbertex hip & ridge caps
4. Removed all debris from job site.


Cost of Labor & Material..... \$ 13,500.00
Less Credit for ½" CDX Plywood..... (110.00)
Cost of Labor & Material..... \$ 13,390.00

Roof Coating (2 Family Structure)

1. Scraped any existing loose coating.
2. Swept and blew roof surface clean of debris.
3. Repaired vent pipe flashing and applied SBS membrane with Karnak 81 cement to drip edge at eave.
4. Furnished and applied (1) coat of Karnak 169 non fibrated aluminum roof coating to entire roof surface.
5. Removed all debris from job site.

Cost of Labor & Material..... \$ 1,200.00
Sales Tax @ 8.375%..... \$ 100.50
Total Cost of Labor & Material..... \$ 1,300.50

Total Amount Due Upon Receipt..... \$ 14,690.50

Thank you,

Wayne Fazzinga

Prompt payment is appreciated. 1.5% added after 30 days. (18% per year)
Purchaser agrees to pay all cost of collection of past due accounts, including legal fees.