



**NORTH BUILDING
FIRST FLOOR PLAN**

PLAN NOTES

1. REPLACE ROOF SKYLIGHTS.
2. REMOVE EXISTING CONCRETE SLAB. REPLACE WITH 5" CONCRETE INCLUDING MESH ROOF.
3. EXPANSION JOINT - FIBER.
4. 5/8" TYPE X GYP BOARD UNDER STAIR @ WALLS / CEILINGS.
5. REPLACE EXISTING WOOD DOOR (E = EXISTING).
6. ADD 1 1/2" DIAMETER STAINLESS STEEL HANDRAILS @ SIDE / BACK OF TOILET.
7. REPLACE EXISTING GLASS WITH LAMINATED TINTED SAFETY GLASS STRIP ALL WALLS. REPLACE WITH GYP BOARD FINISH.
8. EXISTING STEEL COLUMN - WRAP WITH WOOD FRAME & GYP BOARD FINISH.
9. EXISTING ELECTRICAL EQUIPMENT (SEE E1).
10. NEW ELECTRICAL (SEE E1).
11. EXISTING 8" C.M.U. WALLS.
12. EXISTING 2 X 4 WOOD STUD WALLS.
13. 2 X 12 @ 12" FLOOR JOINT ABOVE.
14. 2 X FURRING OVER CONCRETE BLOCK WALL.
15. EXISTING WINDOWS TO REMAIN.
16. EXISTING WINDOW TO BE REPLACED WITH NEW WINDOW IN EXISTING OPENINGS.
17. REPLACE EXISTING WH.
18. TELEPHONE EQUIPMENT JUNCTION.
19. COMPUTER EQUIPMENT JUNCTION.
20. EXISTING 4 X 14 PURLIN @ 8' O.C.
21. EXISTING 2 X 4 RAFTERS @ 24" O.C.
22. EXISTING 5 1/8 X 16 1/2" GLB.
23. EXISTING 2 X 4 T-BAR CEILING.
24. 2 X 6 @ 12" O.C. CEILING JOISTS - EXISTING
25. 2 X 4 @ 12" O.C. CEILING JOISTS - EXISTING
26. EXISTING STEEL TRESSES - OPEN WEB
27. 2 X 10 RAFTERS @ 24" O.C.

COUNTY OF LOS ANGELES
 DEPT. OF PUBLIC WORKS
 ENVIRONMENTAL PROGRAMS DIVISION
 CLEARANCE
 FOR INDUSTRIAL WASTES

Facility for the collection and disposal of liquid industrial wastes including...
 Date: 11/23/97

APPROVED

By: _____
 Date: _____

DEA CONSULTANTS