
# SITE DEVELOPMENT PLANS FOR VICTOR JEEP - 6560 ANTHONY DRIVE


TOWN OF VICTOR, ONTARIO COUNTY, NEW YORK P.N. 20182599.0002





VICTOR EAST AUTO GROUP 7200 PITTSFORD VICTOR RD

> John F. Caruso, P.E. David L. Cox, P.E. Carole G. Harvey











NOT FOR CONSTRUCTION






1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL EITHER "T" OR "U" TYPE OR HARDWOOD. 2. FILTER CLOTH TO BE TO BE FASTENED SECURELY TO WOVEN WIRE

FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
FENCE SHALL BE WOVEN WIRE, 12 1/2 GAUGE, 6" MAXIMUM ME 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILINKA 1140N, OR APPROVED EQUIVALENT.

4. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUIVALENT. 5. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.

SILT FENCE DETAIL



### CONSTRUCTION SEQUENCE FOR GRADING AND **EROSION CONTROL:**

2. INSTALL STABILIZED CONSTRUCTION ENTRANCE.

3. CLEAR AND GRUB THE PROJECT IMPROVEMENTS AREAS. 4. STRIP TOPSOIL AND TRUCK EXCESS OFF-SITE.

5. GRADE IMPROVEMENTS AREAS WITHIN THE PROJECT SITE. AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN 7 DAYS WILL BE STABILIZED WITH A TEMPORARY SEED AND MULCH WITHIN 7 DAYS OF THE LAST DISTURBANCE.

6. REPLACE TOPSOIL AND FINE GRADE.

7. HYDRO-SEED ALL DISTURBED AREAS WITHIN 7 DAYS AFTER FINAL GRADING, CONTRACTOR IS RESPONSIBLE TO RESEED IF GRADING IS UNSATISFACTORY.

8. UPON APPROVAL OF THE TOWN, REMOVE ALL TEMPORARY SILTATION CONTROLS. 9. SLOPES SHALL NOT EXCEED 1' VERTICAL TO 3' HORIZONTAL MAX. MAINTAIN 1:4 WHERE POSSIBLE.

10. MINIMUM OF 6" OF TOPSOIL IS TO BE PLACED ON ALL GRASS AREAS. 11. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BASED UPON ACTUAL FIELD CONDITIONS

AOBE. CONTRACTOR SHALL PROVIDE FOR THIS COST IN HIS CONTRACT. 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SILTATION AND EROSION CONTROL MEASURES FROM INSTALLATION THROUGH MAINTENANCE AND REMOVAL AFTER REVEGETATION HAS BEEN ESTABLISHED.

13. ALL END SECTIONS WILL BE PROVIDED WITH RIP-RAP APRONS. 14. ALL EROSION AND SEDIMENT CONTROL METHODS WILL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND

15. ALL EROSION CONTROL MEASURES WILL BE REMOVED AFTER APPROVED BY QUALIFIED PROFESSIONAL.

AT THE VERY MINIMUM, EROSION CONTROL SHALL BE AS SHOWN ON THIS PLAN. EROSION CONTROL MAY CONSIST OF SEDIMENT TRAPS AND/OR ENVIRONMENTAL FENCES. THE CONTRACTOR AND THE DEVELOPER SHALL BE RESPONSIBLE FOR THE INTEGRITY, MAINTENANCE AND REMOVAL OF EROSION CONTROL MEASURES UNTIL NO LONGER DEEMED NECESSARY BY THE TOWN OR IT'S REPRESENTATIVE. THE CONTRACTOR SHALL MAINTAIN THE STORM SEWER SYSTEM UNTIL THE PROJECT IS DEVELOPED AND APPROVED BY THE TOWN AND

ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED IN GOOD WORKING ORDER. THE OWNER SHALL BE RESPONSIBLE FOR MAINTENANCE OF THE STONE FILL. CORRECTIVE ACTIONS, AS IDENTIFIED BY THE DEVELOPER'S ONSITE REPRESENTATIVE OR A TOWN REPRESENTATIVE, SHALL BE INITIATED WITHIN 24 HOURS OF BEING REPORTED. THE TOWN MAY REVIEW THE PROJECT SITE AT ANY TIME. REVIEW OF EROSION CONTROL MEASURES BY THE TOWN DOES NOT RELIEVE THE DEVELOPER OF HIS OBLIGATIONS TO EXECUTE RESPONSIBLE STANDARD

## CONSTRUCTION SEQUENCE FOR STEEP SLOPE STABILIZATION/ JUTE MESH INSTALLATION FOR SLOPES OF 1:3 OR GREATER:

STRIP TOPSOIL ON SLOPE.
 GRADE SLOPE PER PLAN. CONTRACTOR SHALL TAKE CARE TO NOT OVER EXCAVATE EMBANKMENT.

. TRACK TOPSOIL WITH A BULLDOZER IN A DIRECTION PERPENDICULAR TO THE PROPOSED CONTOUR LINES.

IMMEDIATELY SEED AND FERTILIZE TOPSOIL PER PLAN. IMMEDIATELY APPLY JUTE MESH BY UNROLLING THE PRODUCT DOWN THE SLOPE. DO NOT STRETCH THE MESH, ALLOWING

IT TO FULLY CONTACT THE SOIL. 7. SECURE THE JUTE MESH WITH STAPLES (11 GAUGE - 8"x1"x8") 24" APART THOUGH OUT THE MATTING (APPROXIMATELY 200

STAPLES PER 100 SY). STAPLES SHOULD BE DRIVEN FLUSH WITH THE GROUND. 8. SECURE BEGINNING AND END OF ROLL BY ANCHORING THE MATTING INTO 6" DEEP SLOTS CUT INTO THE SOIL. THEN STAPLE MATTING AT CHECK SLOTS.

### SEEDING NOTE

TO PROVIDE THE FOLLOWING SEED MIXTURES DURING CONSTRUCTION:


RYEGRASS (ANNUAL OR PERENNIAL) @ 120 LBS. PER ACRE OR 0.7 LBS. PER 1000 SQUARE

65% KENTUCKY BLUEGRASS BLEND @ 85LBS. PER ACRES OR 2.0-2.6 LBS. PER 1000 SQUARE

20% PERENNIAL RYEGRASS @ 26-35 LBS. PER ACRE OR 0.6-0.8 LBS. PER 1000 SQUARE FEET 15% FINE FESCUE @ 19-26 LBS. PER ACRE OR 0.4-0.6 LBS. PER 1000 SQUARE FEET

FOR ALL SEEDING & STABILIZATION MEASURES IT IS THE RESPONSIBILITY OF THE OWNER & DEVELOPER TO ENSURE THAT FINAL STABILIZATION OCCURS AS REQUIRED BY THE NYSDEC AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN 7 DAYS WILL BE STABILIZED WITH A TEMPORARY SEED AND MULCH WITHIN 7 DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN AREA THAT AREA WILL BE STABILIZED WITH PERMANENT SEED AND MULCH. AFTER THE ENTIRE SITE IS STABILIZED, THE ACCUMULATED SEDIMENT WILL BE REMOVED FROM THE SEDIMENT BASIN(s).





LOCATION SKETCH N.T.S.

VICTOR EAST AUTO GROUP 7200 PITTSFORD VICTOR RD VICTOR, NY 14564

### PASSERO ASSOCIATES (585) 325-1000 Fax: (585) 325-1691

Principal-in-Charge

John F. Caruso, P.E. Project Manager David L. Cox, P.E. Designed by Carole G. Harvey



No.	Date	Ву	Description
1			
-			
,			
		L	
UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS IN VIOLATION OF STATE EDUCATION LAW ARTICLE 145 SECTION 7209 AND			
APTICLE 147 CECTION 7207 THESE IN ANS ARE CONVEIGHT PROTECTED			

**NOTES & DETAILS** 

6560 ANTHONY DR.

Town/City: VICTOR County: ONTARIO

State: NEW YORK 20182599.0002

C201

If you excavate anywhere in **New York State,** except NYC or Long Island, call

**New York** 

1-800-962-7962 I-Notice = www.DigSafelyNewYork.com

NOVEMBER 2018

N.T.S.

NOT FOR CONSTRUCTION