

175 ALDER DR
MT 59901-8607

Creator	Date	Estimate #
VF	5/1/2024	7596

Name / Address
Jim Haun 4395 Hwy 93 West Whitefish, Mt jhaun123@gmail.com 1-541-490-0085

Project
Jim Haun 4395 Hwy 93 West Whitefish, Mt

Project	Customer Phone
	Customer Alt. Phone

Description	Qty	U/M	Amount
*1-NEW 1000 GALLON DOSING TANK WITH NEW PUMP INSTALLATION & ADDITIONAL DRAINFIELD MATERIALS			
-Existing pump is not adequate to accomadate the alteration			
-Existing tank will need filter removed from Baffle wall and installed on outlet, 3-4" low holes will need to be drilled out of Baffle wall. These modifications are needed to change the tank from a combination, two compartment tank to a septic tank. Modifications to existing combination tank will need to be provided by others.			
1000 GALLON DRAINFIELD DOSING TANK	1		
PUMP PAD 14.5" round x 2.25" tall	1		
4" SCH 40 S/W PVC PIPE (580' LIFT)	20		
1-1/2" SCH 40 PVC PIPE	260		
PUMP INSTALLATION FOR EFFLUENT PUMPS	1		
Weephole after the union and above the off float			
set floats 17" apart			
+2" HLA			
2" SCH 80 PVC PIPE	20		
ASHLAND (EP75M1-20) 3/4HP EFFLUENT PUMP 115V	1		
SJE RHOMBUS INDOOR/OUTDOOR TANK ALERT W/TERMINAL (TAXT-01HTB) 120 V (includes float)	1		
SJE RHOMBUS 115V FLOAT (DOUBLE FLOAT) 15" CORD (1002026)	1		
2" SCH 80 MALE ADAPTER	1		
2" SCH 80 90-ELL	3		
2" SCH 80 PVC UNION	1		
4" 3034 TO 4" SCH40 ADAPTER	1		
4" 3034 PVC SEWER PIPE - SOLID	0.33		
-Parts needed to put existing filter on outlet of septic tank			

	Total
--	--------------

175 ALDER DR
MT 59901-8607

Creator	Date	Estimate #
VF	5/1/2024	7596

Name / Address
Jim Haun 4395 Hwy 93 West Whitefish, Mt jhaun123@gmail.com 1-541-490-0085

Project
Jim Haun 4395 Hwy 93 West Whitefish, Mt

Project	Customer Phone
	Customer Alt. Phone

Description	Qty	U/M	Amount
SB3-PVC SPLICE BOX W/3 CORD GRIPS	1		
2" SCH 40 TEE	4		
2" SCH 40 90-ELL	1		
2" X 1-1/2" SCH 40 PVC BUSHING	5		
1-1/2" SCH 40 FEMALE ADAPTER	4		
1-1/2" SCH 40 45-ELL	4		
1-1/2" GALVANIZED THREADED PLUG	4		
MIRAFI FILTER FABRIC - 36 in X 360 ft	1		
FIBERGLASS LID 24" W/NEOPRENE GASKET; 4 BOLTS	2		
24" DIAMETER X 14' ULTRARIB RISER PIPE (GREEN)	24	in	
24" DIAMETER X 14' ULTRARIB RISER PIPE (GREEN)	24	in	
1" GROMMET INSTALLED	1		
Subtotal			
*1-NEW LIFT STATION FOR EXISTING 4-BEDROOM HOUSE TO CONNECT TO EXISTING 2500 GALLON TANK			
4" SCH 40 S/W PVC PIPE (580' LIFT)	20		
2" SCH 40 PVC PIPE	160		
CLEAN OUT	1		
BAFFLE PL68 FITS 3"/4" PIPE	2		
4" X 2" SCH 40 PVC BUSHING	1		
FIBERGLASS LID, 24" W/NEOPRENE GASKET; 4 BOLTS, 2" INSULATION	1		
24" DIAMETER X 14' ULTRARIB RISER PIPE (GREEN)	18	in	
1" GROMMET (not installed)	1		
PRTA24 -ABS RISER/TANK ADAPTER 24" DIAMETER	1		
MA320 -200G EPOXY KIT	1		
58" MANHOLE FLAT TOP LID (24" HOLE)	1		

	Total
--	--------------

Glacier Precast Concrete

175 ALDER DR
MT 59901-8607

Estimate

Creator	Date	Estimate #
VF	5/1/2024	7596

Name / Address
Jim Haun 4395 Hwy 93 West Whitefish, Mt jhaun123@gmail.com 1-541-490-0085

Project
Jim Haun 4395 Hwy 93 West Whitefish, Mt

Project	Customer Phone
	Customer Alt. Phone

Description	Qty	U/M	Amount
1 VF 48" ID BARREL	6		
48" MANHOLE BASE	1		
HOLES FOR PIPE PENETRATION	2		
8 QRS PSX BOOT	1		
2" X 1/2" GALVANIZED TEE (INSTALLED)	1		
48" MANHOLE BASE	1		
1" ROLLS SEALANT (8 ROLLS PER BOX) PRICE IS PER ROLL	3		
PUMP INSTALLATION FOR GRINDER PUMPS	1		
ASHLAND (SW40M1-20) 4/10HP SEWAGE PUMP 115V	1		
MF1P Mechanical Float, Normally Open w/collar 10"(BLUE)	3		
S1CT-SIMPLEX PANEL, 115V W/CT	1		
SB4-PVC SPLICE BOX W/4 CORD GRIPS	1		
RRFB-RISER FLOAT BRACKET	1		
2" SCH 80 90-ELL	3		
2" TRUE UNION BALL CHECK VALVE TREAD & SOCKET ENDS	1		
2" SCH 40 BALL VALVE	1		
2" SCH 80 MALE ADAPTER	3		
8 ft FLOAT TREE	1		
2" SCH 80 PVC PIPE	20		
MISC. PLUMBING	1		
48" GRINDER STATION			
DELIVERY	1		

	Total	\$8,973.84
--	--------------	------------