



EROSION & SEDIMENT CONTROL LEGEND

- ⑫ TEMPORARY STONE CONSTRUCTION ENTRANCE STANDARD & SPEC. 3.02
- ⑬ SILT FENCE STANDARD & SPEC. 3.05
- ⑭ INLET PROTECTION STANDARD & SPEC. 3.07
- ⑮ TEMPORARY SEEDING STANDARD & SPEC. 3.31
- ⑯ SAFETY FENCE STANDARD & SPEC. 3.01
- ⑰ PROVIDE A TEMPORARY SAFETY FENCE WITH TEMPORARY DUST BARRIER (SEE DETAIL ON SHEET C1) ALONG PERMITS OF SITE TO CONTAIN TRASH, CONSTRUCTION DEBRIS, ETC. FROM LEAVING SITE DURING CONSTRUCTION.

EXISTING TREES

[illegible]

 DENOTES TREES TO BE REMOVED

NOTE: STAGING AND STOCKPILE AREA SHOWN MAY BE RELOCATED/ADJUSTED AT THE DISCRETION OF THE CIVIL INSPECTOR.

EROSION CONTROL & DEMOLITION PLAN

FIELD CHANGE #1

AUTOMOTIVE SALES

PROJECT LOCATED IN:		DATE FOR:	
VIRGINIA BEACH, VIRGINIA		EMIL N. YUSUBOV	
DESIGN BY:	DRAWN BY:	CHECKED BY:	DATE:
DRB	J.B	DRB	FEBRUARY 2, 2017
SCALE:		SHEET	
1" = 20'		3 / 17	
GALLUP SURETYSORS & ENGINEERS, LTD. VIRGINIA BEACH, VIRGINIA 22444 (757)428-8132 (757)425-2390 FAX			