

1 FLOOR PLAN – NEW WORK
3/16"=1'-0"

N

FINISH MARKER:
F1 | B1 | W1 | C1
FLOOR / BASE / CEILING / WALL

FINISH LEGEND:

GENERAL:
EX – EXISTING FINISH TO REMAIN

FLOORS:
F1 – VCT; ARMSTRONG 12"X12" EXCELON SERIES; COLOR TO BE SELECTED
F2 – SEALED CONCRETE; H&C CONCRETE SEALER; WATER BASED-WET LOOK

BASE:
B1 – RUBBER BASE; 4" COVE BASE; BLACK

PAINT
W1 – PAINT; BENJAMIN MOORE; "WHITE DIAMOND" 2121-60. EGGSHELL SHEEN

CEILING
C1 – ACOUSTICAL CEILING SYSTEM; USG #808 2'X4' OR EQUIVALENT
C2 – OPEN TO STRUCTURE, DO NOT PAINT
C3 – OPEN TO STRUCTURE, PAINT JOIST AND DECK TO MATCH W1

KEYNOTES – NEW WORK:

1. REMOVE EXISTING PARTITION TO PROVIDE ACCESS TO EXISTING ROLL-UP DOOR
2. INSTALL BLACKOUT FILM AND CONSTRUCT NEW SECURITY PARTITION AT INTERIOR OF WINDOW. REFER TO PARTITION TYPE
3. LOCK DOOR AND REMOVE EXTERIOR HARDWARE
4. OWNER PROVIDED FURNITURE OR WORKSTATION, PROVIDE POWER AND DATA PER ELECTRICAL
5. MAX 8' HIGH SHELVING BY OWNER
6. EXISTING FIRE ALARM PULLSTATION TO REMAIN AT EXIT DOORS, TYP
7. SECURITY MONITOR BY OWNER. COORDINATE BLOCKING REQUIREMENTS WITH OWNER. PROVIDE POWER AND DATA PER ELECTRICAL
8. HR MONITOR BY OWNER. COORDINATE BLOCKING REQUIREMENTS WITH OWNER. PROVIDE POWER AND DATA PER ELECTRICAL
9. EXISTING ELECTRICAL PANEL TO REMAIN, SEE ELECTRICAL
10. EXISTING PARTITION AND OVERHEAD DOOR TO REMAIN
11. EXISTING 4 HOUR RATED DEMISING WALL. FIELD VERIFY THAT ANY EXISTING PENETRATIONS ARE SEALED PER UL DESIGN REQUIREMENTS.
12. REMOVE EXISTING SAFETY SHOWER

D = 6"
C = 3 5/8"
B = 6"
A2 = 3 5/8"
A = 6"

HUMAN ELEMENT
ARCHITECTS
324 Lawrence St. NE,
Marietta, Georgia 30060
ph: 678.402.1879 fax: 678.666.1351
david@hearchitects.com

SEAL:
STATE OF FLORIDA
DAVID LEE HUMAN
AR94572
REGISTERED ARCHITECT
11/6/18

CLIENT:
SURTERRA WELLNESS

ISSUE	DESCRIPTION	DATE
0	FOR PERMIT AND CONSTRUCTION	11/6/18

SURTERRA DC
5570 LEE STREET
LEHIGH ACRES, FL 33971

PROJECT NUMBER: 1888

SHEET TITLE:
FLOOR PLAN

SHEET NUMBER:
A100