

Interpretation

The following graphics depict the interpretation of lot development standards. The official definitions for these terms can be found in [Article 10, Definitions](#), and should be used for any legal determinations.

Lot Area Dimensions

Lot Area

- Ⓐ Lot Width
- Ⓑ Lot Depth (Interior or Through Lot Only)

Setbacks

Principal

- Ⓒ Front Yard
- Ⓓ Side Yard
- Ⓔ Rear Yard

Accessory


- Ⓕ Side Yard
- Ⓖ Rear Yard

Coverage

- Ⓗ Buildable Area

Maximum Height

- Ⓘ Principal Building
- Ⓝ Story
- Ⓚ Accessory Building



Amended on 9.28.2020

Districts

For uses allowed in each district, please see section 103.2 Use Table

102.1 AR Agricultural Residential District

A. Purpose

The Agricultural Residential district provides an environment where limited agricultural endeavors can operate compatibly with a greater density of population than is normally found in farming areas.

B. Lot Development Standards

| Use | Lot Area | Lot Width Min. | Min. Front Setback | Min. Side Setback | Min. Rear Setback | Min. Heated Floor Area | Max. Lot Coverage | Max. Building Height |
|------------|-------------|----------------|--------------------|-------------------|-------------------|---|-------------------|----------------------|
| Principal | 1 Acre min. | 300 ft. | 50 ft. | 10 ft. each yard | 40 ft. | Single story- 2,000 sq. ft. Two story- 2,400 sq. ft. | 60% | 35 ft. |
| Accessory* | - | - | - | 15 ft. | 15 ft. | - | - | 35 ft. |

Barns and other agricultural structures are permitted at any size for active agriculture activity.

* Accessory structures are prohibited in the front yards.

C. Protective Covenant

The development shall have a mandatory community association(s) to provide maintenance for all common areas (including the maintenance of landscaping within internal rights-of-way and immediately adjacent external rights-of-way), and enforce reasonable and customary property maintenance standards through covenants on all residences within the community. The covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional 5% hardship) may be leased to third parties by individual owners.

Amended on 9.28.2020

102.2 RS-180 Single-Family Residential District

A. Purpose

The RS-180 Single-Family Residential District is intended for single-family homes and designed to stabilize and protect the residential characteristics of the district.

B. Lot Development Standards

| Use | Min. Lot Area | Lot Width Min. | Min. Front Setback | Min. Side Setback | Min. Rear Setback | Min. Heated Floor Area | Max. Lot Coverage | Max. Building Height |
|----------------------------|----------------|----------------|--------------------|-------------------|-------------------|---|-------------------|----------------------|
| Principal | 18,000 sq. ft. | 100 ft. | 50 ft. | 10 ft. each yard | 40 ft. | Single story- 2,000 sq. ft. Two story- 2,400 sq. ft. | 25% | 35 ft. |
| Accessory* One/lot max. | - | - | - | 5 ft. | 5 ft. | * | - | 18 ft. |

* Maximum of 400 square feet. Accessory structures are prohibited in the front yards. Utilities shall be underground.

C. Mandatory Homeowners Association. As part of the planning process for the development of a subdivision, the developer shall propose at the time of the request for development a Home Owners Association to be attached to the development of the property. The Home Owners Association shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

D. Protective Covenant

The development shall have a mandatory community association(s) to provide maintenance for all common areas (including the maintenance of landscaping within internal rights-of-way and immediately adjacent external rights-of-way), and enforce reasonable and customary property maintenance standards through covenants on all residences within the community. The covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional 5% hardship) may be leased to third parties by individual owners.

Amended on 9.28.2020

102.3 RS-150 Single-Family Residential District

A. Purpose

The RS-150 Single-Family Residential District is intended for single-family homes and designed to stabilize and protect the residential characteristics of the district.

B. Lot Development Standards

| Use | Lot Area | Lot Width Min. | Min. Front Setback | Min. Side Setback | Min. Rear Setback | Min. Heated Floor Area | Max. Lot Coverage | Max. Building Height |
|---------------------------|----------------|----------------|--------------------|-------------------|-------------------|--|-------------------|----------------------|
| Principal | 15,000 sq. ft. | 85 ft. | 35 ft. | 10 ft. each yard | 40 ft. | Single story- 2,000 sq. ft Two story- 2,400 sq. ft. | 30% | 35 ft. |
| Accessory* One/lot max | - | - | - | 5 ft. | 5 ft. | * | - | 18 ft. |

* 400 square feet maximum. Accessory structures are prohibited in the front yards. Utilities shall be underground.

C. Mandatory Homeowners Association. As part of the planning process for the development of a subdivision, the developer shall propose at the time of the request for development a Home Owners Association to be attached to the development of the property. The Home Owners Association shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

D. Protective Covenant

The development shall have a mandatory community association(s) to provide maintenance for all common areas (including the maintenance of landscaping within internal rights-of-way and immediately adjacent external rights-of-way), and enforce reasonable and customary property maintenance standards through covenants on all residences within the community. The covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional 5% hardship) may be leased to third parties by individual owners.

102.4 RS-60 Single-Family Residential District

A. Purpose

This zoning district is intended to allow the construction of Single-Family developments on very small lots.

B. Lot Development Standards

Development size requirement: 10 acres minimum.

| Use | Lot Area | Lot Width Min. | Min. Front Setback | Min. Side Setback | Min. Rear Setback | Min. Heated Floor Area | Max. Lot Coverage | Max. Building Height |
|---------------------------|---------------|----------------|--------------------|-------------------|-------------------|--|-------------------|----------------------|
| Principal | 7,500 sq. ft. | 60 ft. | 35 ft. | 5 ft. each yard | 20 ft. | 1,800 sq. ft (1 story) 2,000 sq. ft. (2 story) | 75% | 35 ft. |
| Accessory* One/lot max | - | - | - | 5 ft. | 5 ft. | * | - | 18 ft. |

* 400 square feet maximum. Accessory structures are prohibited in the front yard.

C. Miscellaneous Provisions

This zoning classification will contain provisions for green space areas for common benefit of the community to be maintained by a homeowner's association. The zoning district shall be considered through individual rezoning applications where water supply and sewage facilities are available or can be obtained and where there is convenient access to collector streets, major thoroughfares, or state and interstate highways. A complete detailed site plan shall be submitted with each application showing, among other things, open space and recreational amenities. Such application shall also include additional information, such as architectural renderings and restrictive covenant controls to be used by the Planning Commission and the City of Lawrenceville to determine if a proposed project is in the interest of the health, safety, and welfare of the community for which it is proposed.

D. Mandatory Homeowners Association, Minimum Restrictive Covenant Requirements:

As part of the planning process for the development of a subdivision, the developer shall propose at the time of the request for development a Home Owners Association to be attached to the development of the property. The Home Owners Association shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

E. Protective Covenant

The development shall have a mandatory community association(s) to provide maintenance for all common areas (including the maintenance of landscaping within internal rights-of-way and immediately adjacent external rights-of-way), and enforce reasonable and customary property maintenance standards through covenants on all residences within the community. The

Amended on 9.28.2020

covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional 5% hardship) may be leased to third parties by individual owners.

F. Green Space

Every RS-60 single-family residential development shall be required to construct an area of public green space within the confines of the development. The minimum green space required shall be 15% of the total acreage of the project excluding 50% of the 100-year flood plain and wetland areas. . The green space shall be designed and constructed pursuant to the following regulations:

1. Contiguous green space is encouraged. Green space that is across a right of way shall not be counted towards the required amount.
2. All green space must have at least thirty (30) feet of width to be considered in the calculations.
3. The green space must be commonly owned by all of the residents of the subdivision. The developer shall establish a homeowner's association for purposes of transferring title to the green space at the time development begins on the subdivision.
4. The green space shall be constructed as part of the first phase of development.
5. The green space shall be passive except for walking trails which may be constructed therein. Active recreation areas, including swimming pools, tennis courts, basketball courts, clubhouses, and other recreational amenities may not be constructed in the green space.
6. All green space shall be undisturbed, until after the final plat has been approved and recorded.

G. Utility Restrictions

All utilities shall be located underground.

102.5 RM-8 Townhouse Residential District

A. Purpose

The RM-8 Townhouse Residential District is designed to provide for townhome development that will be compatible when located near and among lower- and moderate-density types of developments.

Property in the RM-8 Townhouse Residential District shall be developed in accordance with the Minimum Lot Area requirement and the applicable site related provisions of the City of Lawrenceville Development Regulations.

B. Lot Development Standards

| Min. Lot Area | Unit Width Min. | External Min. Front Setback | External Min. Side Setback | External Min. Rear Setback | Min. Heated Floor Area | Impervious surface Max. Lot Coverage | Max. Building Height | Min. % Com. Area |
|---------------|-----------------|-----------------------------|----------------------------|----------------------------|------------------------|--------------------------------------|----------------------|------------------|
| 5 acre | 20 ft. | 25 ft. | 20 ft.* | 20 ft. | See table below | 40% | 35 ft. | 15% |

- 40 feet if located on Major Arterial
- This Minimum Lot Area shall not be reduced by a Variance. If property was zoned (RM-12) General Residence, 3,600 Sq. Ft. District at the time of adoption of the City of Lawrenceville Zoning Ordinance 2020 (ZON-ORD 2020-9), on May 20, 2020, and property does not meet the Minimum Lot Area then the property owner may apply for a Variance.
- Duplexes shall be prohibited.

| Minimum Heated Floor Area | | | | |
|---------------------------|-----------|---------------|----------------|---------------|
| Studio | 1-bedroom | 2-bedroom | 3-bedroom | 4-bedroom |
| - | 1,000 | 1,200 sq. ft. | 1,400 sq. ft.* | 1,600 sq. ft* |

| Min. Unit width | |
|-------------------|--------|
| Double-car garage | 20 ft. |

*Three-bedroom units shall be limited to 40% of the entire townhouse development.

*Four-bedroom units shall be limited to 10% of the entire townhouse development.

C. Mandatory Homeowners Association

As part of the planning process for the development of a townhome subdivision, the developer shall propose at the time of the request for development a Homeowners Association to be attached to the development property. The Homeowners Association shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

The development shall have a mandatory community association(s) to provide maintenance for all common areas (including the maintenance of landscaping within internal rights-of-way and immediately adjacent external rights-of-way), and enforce reasonable and customary property

Amended on 9.28.2020

maintenance standards through covenants on all residences within the community. The, and provide other services to be defined within the covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional 5% hardship) may be leased to third parties by individual owners.

Restrictive Covenant shall include the following:

- a. Development amenities shall include a resort style pool, cabana, fitness center, and community room for residents. Community room shall be sized large enough for activities such as student after school programs, etc. Common area(s)/Park(s) shall be programed with amenities to maximize use such as benches, tables, grills, etc.

D. Architectural Standards

Subject to review and approval by the Director of Planning and Development.

1. Each building shall consist of a minimum of two alternating roof types, specifically, open gable, boxed gable, dormer, hip, or flat roof lines.
2. Front, side, and rear facades shall be finished with primarily brick or stone on each elevation.
3. Elevations shall be staggered with alternating exterior treatments such as porches, balconies, awnings, chimney, stoops, decks, patios, and terraces.
4. Provide a unique architectural entrance with door surround.
5. Incorporate changes in building material texture, and color.
6. Provide elements such as shutters and roof eave brackets.
7. Refer to [Article 6, Architectural and Design Standards](#), for types of materials allowed in the district.


See figures for examples:

Rear Entry



Amended on 9.28.2020

Front Entry



E. Development Standards:

The following minimum requirements shall be applied to the property:

1. All vehicles shall be parked on a subdivision lot on an approved hard surface.
2. Internal yard requirements: A 20-foot grassed or landscaped strip shall be provided between all buildings (facades/elevations) and interior private drives.
3. A minimum of three and a maximum of eight units shall be allowed in each row of townhouses.
4. Private Drive shall be installed with the following dimensions:
 - a. Street width shall be 24 feet. Two foot curb and gutter required (dimensions are back to back of curbs).
 - b. A 5-foot sidewalk is required and shall be 2 feet off of the back of the curb.
5. All utilities shall be underground and shall be located within the required right-of-way.
6. All townhouses must be rear entry; driveways shall have no access to exterior streets.
7. Front entry units shall require the approval of an associated Special Use Permit. If approved, shall abide by the following rules and regulations:
 - a. Front entry garages: may not be converted into heated interior space without being replaced with another garage within the building of the property subject to the terms of this Ordinance.
 - b. Front entry units shall be setback 27 feet from required 24-foot Private Drive.
 - c. Driveway must provide two external parking spaces (9 ft. x 20 ft.).
8. Each townhome residence shall have a two-car garage as a minimum requirement.
9. Rear entry garages:
 - a. May not be converted into heated interior space without being replaced with another garage within the building of the property subject to the terms of this Ordinance.
 - b. Require an 18-foot alley width.

Amended on 9.28.2020

- c. Shall be 20 feet off of required alley.
 - d. Driveway must provide two external parking spaces (9 ft. x 20 ft.).
 - e. Front facade shall be setback 20 feet from the required 24-foot Private Drive.
10. No plumbing or heating vents shall be placed on the front side roof of any structure in this district.
 11. Building fronts shall be staggered to provide architectural relief.
 12. Sidewalks on both sides of all streets including cul-de-sacs shall be required as set forth in the subdivision regulations of the City of Lawrenceville.
 13. The term “pavement width of streets” as used in this Ordinance shall be defined as from the back of curb to back of curb.
 14. No driveway shall have access to exterior streets.
 15. Centralized mail kiosk shall have a minimum three-car stacking lane for every 100 units served.
 16. Dumpsters and recycle bins shall be screened from all units and not visible from right of way.

F. Utility Restrictions

1. All utilities shall be located underground.
2. All utilities meters shall be located along a side or rear elevation.

G. Green/Common Space:

1. Every development shall be required to construct an area of public green space within the confines of the development.
2. At least 15% of the net project acreage (total acreage of the project excluding 50% of the 100-year floodplain and wetland areas) shall be designated on a recorded plat as a permanent common area for the use of the residents of the development.
3. Depending on the scale of the development, the common area shall include at least one conveniently-located public gathering area or activity center with related amenities and improvements in the form of a square, green, plaza, or similar approved element that is accessible to the residents from at least three points of entry by sidewalks. Active recreation areas, including swimming pools, tennis courts, basketball courts, clubhouses, and other recreational amenities may not be constructed in the green space.
4. 50% of the townhouses must be adjacent to or directly across the street from a common area such as a public green, park, or square. These units shall be rear entry only.
 - a. The minimum size for a public green, park or square 3,000 square feet
 - b. Provide a mix of undisturbed natural plantings and/or formal plantings
 - c. Provide benches, tables, seat walls, planters, play structure, and/or picnic areas/shelter.
 - d. Install outdoor lighting.

H. Zoning Exhibit

As part of the application for rezoning, an exhibit shall be submitted that includes the following information:

- a. A location map showing the boundaries of the property with the current zoning of the property, as well as zoning on adjacent properties.
- b. A plan showing applicable details, to include lots, streets and right-of-ways, setback lines, dwelling sizes, off-street parking, on-street parking, street trees, sidewalks, multi-use trails, stormwater management facility areas, floodplain and wetlands, topography, and common space.
- c. Specifications, calculations, and applicable percentages for common area, density calculations, lot sizes, land use, gross and net acreage, dwelling units, and parking.
- d. Color elevations of front, sides, and rear of all typical units, including proposed building materials, building heights and any other structures.
- e. Other architectural and engineering data necessary to demonstrate conformity with applicable standards of the district and with the Article 6, Architectural and Design Standards.
- f. Conceptual Signage Plan.

102.6 RM-12 Multifamily Residential District

A. Purpose

The RM-12 Multifamily Residential District is designed to provide for low-rise and medium-density apartment developments that will be compatible when located near and among lower- and moderate-density types of developments. Dormitories are limited specifically to Georgia Gwinnett College campus.

Property in the RM-12 Multifamily Residential District shall be developed in accordance with the Minimum Lot Area requirement and the applicable site related provisions of the City of Lawrenceville Development Regulations.

B. Development Standards

| Min. Lot Area | Lot Width Min. | Min. Front Setback | Min. Side Setback | Min. Rear Setback | Min. Heated Floor Area | Max. Lot Coverage | Max. Building Height |
|---------------|----------------|--------------------|-------------------|-------------------|------------------------|-------------------|----------------------|
| 5 acre | 100 ft. | 50 ft. | 25 ft. | 40 ft. | See table below | 60% | 35 ft. |

| Min. Heated Floor Area | Studio | 1-bedroom | 2-bedroom | 3-bedroom |
|------------------------|-------------|-------------|--------------|---------------|
| Apartments* | 650 sq. ft. | 800 sq. ft. | 1000 sq. ft. | 1,200 sq. ft. |

- No more than 10% of the total units shall be three-bedroom apartments.
- This Minimum Lot Area shall not be reduced by a Variance. If property was zoned (RM-12) General Residence, 3,600 Sq. Ft. District at the time of adoption of the City of Lawrenceville Zoning Ordinance 2020 (ZON-ORD 2020-9), on May 20, 2020, and property does not meet the Minimum Lot Area then the property owner may apply for a Variance.
- Duplexes shall be prohibited.

C. Mandatory Professional Property Management.

The development shall have a Property Management and shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

- Voluntary compliance with the Gwinnett County Crime Free Multi-Housing program is strongly suggested.

D. Architectural Standards

Subject to review and approval by the Director of Planning and Development.

1. Each building shall consist of a minimum of two alternating roof types, specifically, open gable, boxed gable, dormer, hip or flat rooflines.
2. Common entrances shall incorporate a distinctive architectural entrance structure such as a tower element, arched portal, or arbor/trellis.
3. Front, side, and rear facades shall be finished with a minimum of 75 percent brick on each elevation. Elevations shall be staggered with alternating exterior materials and treatments such as porches, balconies, awnings, chimney, stoops, decks, patios, and terraces.
4. Provide unique architectural entrance surrounding single entryway.
5. Front façade and elevations visible from right-of-way shall include, at a minimum, one window and associated shutters shall provide decorative elements.
6. Refer to [Article 6, Architectural and Design Standards](#), for types of materials allowed in the district.

See figures for examples:



Source: Humphreys & Partners Architects

Amended on 9.28.2020

E. Development Standards

Subject to review and approval by the Director of Planning and Development.

1. No more than three stories.
2. Each unit is accessed internally, via a double-loaded corridor; a building design in which there are apartments or other individual units on both sides of a passage corridor connecting twelve or more attached units.
3. Provide pedestrian corridors within and beyond the development.
4. Provide potential future connections to adjacent sites or parallel roads.
5. Organize buildings around a park to create more park views and provide security that is natural in appearance.
6. Buildings should be oriented parallel to both external and internal streets, providing a frontage that helps frame the public realm.
7. Break up parking to avoid large areas of asphalt.
8. Buildings should be used to screen the large parking areas from street view.
9. Provide a decorative entrance to the development.
10. Provide a 50-foot wide landscaped setback along all exterior street frontages. The landscaped setback shall incorporate a six-foot berm, natural vegetation, and include a decorative fence/wall and entrance monument. The fence shall be constructed as a wrought iron-style fence with brick or stone columns (maximum 30-feet on-center) that are consistent with the exterior architectural treatments of the building. The fence may be placed along the 50-foot setback.
11. The landscape may vary heights, sizes, and types of plant materials around the building foundation but are subject to review and approval by the Director of Planning and Development.
12. Create focal cluster groups of plants adjacent to the building entry points.
13. Incorporate perennials and annuals to add color.
14. Centralized mail kiosk shall have a minimum three-car stacking lane for every 100 units served.
15. Dumpsters and recycle bins shall be screened from all units and not visible from right of way.
16. The development shall be included in a Crime Free Multi-Housing Program similar to Gwinnett County's program.
17. A Professional Property Management shall be provided and shall include at a minimum maintenance of all fencing, landscaping, paving, common areas, detention ponds, and exteriors of all structures.
18. Development amenities shall include a resort style pool, cabana, fitness center, and community room for residents. Community room shall be sized large enough for activities such as student after school programs, etc. Common area(s)/Park(s) shall be programed with amenities to maximize use such as benches, tables, grills, etc.
19. Property shall have one owner. Subdividing portions of the property is prohibited.

F. Utility Restrictions

1. All utilities shall be located underground.
2. All utilities meters shall be located along a side or rear elevation.

G. Green/Common Space:

1. Every development shall be required to construct an area of public green space within the confines of the development.
2. At least 15% of the net project acreage (total acreage of the project excluding 50% of the 100-year floodplain and wetland areas) shall be designated on a recorded plat as a permanent common area for the use of the residents of the development.
3. Depending on the scale of the development, the common area shall include at least one conveniently-located public gathering area or activity center with related amenities and improvements in the form of a square, green, plaza, or similar approved element that is accessible to the residents from at least three points of entry by sidewalks. Active recreation areas, including swimming pools, tennis courts, basketball courts, clubhouses, and other recreational amenities may not be constructed in the green space.
4. 50% of the townhouses must be adjacent to or directly across the street from a common area such as a public green, park, or square. These units shall be rear entry only.
 - a. The minimum size for a public green, park or square 3,000 square feet
 - b. Provide a mix of undisturbed natural plantings and/or formal plantings
 - c. Provide benches, tables, seat walls, planters, play structure, and/or picnic areas/shelter.
 - d. Install outdoor lighting.

H. Zoning Exhibit

As part of the application for rezoning, an exhibit shall be submitted that includes the following information:

- a. A location map showing the boundaries of the property with the current zoning of the property, as well as zoning on adjacent properties.
- b. A plan showing applicable details, to include lots, streets and right-of-ways, setback lines, dwelling sizes, off-street parking, on-street parking, street trees, sidewalks, multi-use trails, stormwater management facility areas, floodplain and wetlands, topography, and common space.
- c. Specifications, calculations, and applicable percentages for common area, density calculations, lot sizes, land use, gross and net acreage, dwelling units, and parking.
- d. Color elevations of front, sides, and rear of all typical units, including proposed building materials, building heights and any other structures.
- e. Other architectural and engineering data necessary to demonstrate conformity with applicable standards of the district and with the Article 6, Architectural and Design Standards.
- f. Conceptual Signage Plan.

102.7 RM-24 Multifamily Residential District

A. Purpose

The RM-24 Multifamily Residential District is designed to provide for medium-rise and high-density apartment developments that will be compatible when located near and among lower- and moderate-density types of developments. Apartments may be allowed in this district.

Property in the RM-24 Multifamily Residential District shall be developed in accordance with the Minimum Lot Area requirement and the applicable site related provisions of the City of Lawrenceville Development Regulations.

B. Development Standards

| Min. Lot Area | Lot Width Min. | Min. Front Setback | Min. Side Setback | Min. Rear Setback | Min. Heated Floor Area | Max. Lot Coverage | Max. Building Height |
|---------------|----------------|--------------------|-------------------|-------------------|------------------------|-------------------|----------------------|
| 10 acre | 100 ft. | 50 ft. | 25 ft. | 40 ft. | See table below | 60% | 70 ft. |

| Min. Heated Floor Area | Studio | 1-bedroom | 2-bedroom | 3-bedroom |
|------------------------|-------------|-------------|--------------|---------------|
| Apartments* | 650 sq. ft. | 800 sq. ft. | 1000 sq. ft. | 1,200 sq. ft. |

- No more than 10% of the total units shall be three-bedroom apartments.
- This Minimum Lot Area shall not be reduced by a Variance. If property was zoned (RM-12) General Residence, 3,600 Sq. Ft. District at the time of adoption of the City of Lawrenceville Zoning Ordinance 2020 (ZON-ORD 2020-9), on May 20, 2020, and property does not meet the Minimum Lot Area then the property owner may apply for a Variance.
- Duplexes shall be prohibited.

C. Mandatory Professional Property Management. The development shall have a property management and shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

- Voluntary compliance with the Gwinnett County Crime Free Multi-Housing program is strongly suggested.

D. Architectural Standards

Subject to review and approval by the Director of Planning and Development.

- Each building shall consist of a minimum of two alternating roof types, specifically, open gable, boxed gable, dormer, hip or flat rooflines.

Amended on 9.28.2020

2. Common entrances shall incorporate a distinctive architectural entrance structure such as a tower element, arched portal, or arbor/trellis.
3. Front, side, and rear facades shall be finished with a minimum of 75 percent brick on each elevation. Elevations shall be staggered with alternating exterior materials and treatments such as porches, balconies, awnings, chimney, stoops, decks, patios, and terraces.
4. Provide a unique architectural entrance surrounding single entryway.
5. Front façade and elevations visible from right-of-way shall include, at a minimum, one window and associated shutters shall provide decorative elements.
6. Refer to [Article 6, Architectural and Design Standards](#), for types of materials allowed in the district.

See figures below for examples:



Source: Humphreys & Partners Architects

E. Development Standards

Subject to review and approval by the Director of Planning and Development.

1. No more than five stories.
2. Each unit is accessed internally, via a double-loaded corridor; a building design in which there are apartments or other individual units on both sides of a passage corridor connecting twelve or more attached units
3. Provide pedestrian corridors within and beyond the development.
4. Provide potential future connections to adjacent sites or parallel roads.
5. Organize buildings around a park to create more park views and provide security that is natural in appearance.
6. Buildings should be oriented parallel to both external and internal streets, providing a frontage that helps frame the public realm.
7. Break up parking to avoid large areas of asphalt.
8. Buildings should be used to screen the large parking areas from street view.
9. Provide a decorative entrance to the development.
10. Provide a 50-foot wide landscaped setback along all exterior street frontages. The landscaped setback shall incorporate a six-foot berm, natural vegetation, and include a decorative fence/wall and entrance monument. The fence shall be constructed as a wrought iron-style fence with brick or stone columns (maximum 30-foot on-center) that are consistent with the exterior architectural treatments of the building. The fence may be placed along the 50-foot setback.
11. The landscape may vary heights, sizes, and types of plant materials around the building foundation but are subject to review and approval by the Director of Planning and Development.
12. Create focal cluster groups of plants adjacent to the building entry points.
13. Incorporate perennials and annuals to add color.
14. Centralized mail kiosk shall have a minimum three-car stacking lane for every 100 units served.
15. Dumpsters and recycle bins shall be screened from all units and not visible from right of way.
16. shall be included in a Crime Free Multi-Housing Program similar to Gwinnett County's program.
17. A Professional Property Management shall be provided and shall include at a minimum maintenance of all fencing, landscaping, paving, common areas, detention ponds, and exteriors of all structures.
18. Development amenities shall include a resort style pool, cabana, fitness center, and community room for residents. Community room shall be sized large enough for activities such as student after school programs, etc. Common area(s)/Park(s) shall be programed with amenities to maximize use such as benches, tables, grills, etc.
19. Property shall have one owner. Subdividing portions of the property is prohibited

F. Utility Restrictions

1. All utilities shall be located underground.
2. All utilities meters shall be located along a side or rear elevation.

Amended on 9.28.2020

G. Green/Common Space:

1. Every development shall be required to construct an area of public green space within the confines of the development.
2. At least 15% of the net project acreage (total acreage of the project excluding 50% of the 100-year floodplain and wetland areas) shall be designated on a recorded plat as a permanent common area for the use of the residents of the development.
3. Depending on the scale of the development, the common area shall include at least one conveniently-located public gathering area or activity center with related amenities and improvements in the form of a square, green, plaza, or similar approved element that is accessible to the residents from at least three points of entry by sidewalks. Active recreation areas, including swimming pools, tennis courts, basketball courts, clubhouses, and other recreational amenities may not be constructed in the green space.
4. 50% of the townhouses must be adjacent to or directly across the street from a common area such as a public green, park, or square. These units shall be rear entry only.
 - a. The minimum size for a public green, park or square 3,000 square feet.
 - b. Provide a mix of undisturbed natural plantings and/or formal plantings.
 - c. Provide benches, tables, seat walls, planters, play structure, and/or picnic areas/shelter.
 - d. Install outdoor lighting.

H. Zoning Exhibit

As part of the application for rezoning, an exhibit shall be submitted that includes the following information:

- a. A location map showing the boundaries of the property with the current zoning of the property, as well as zoning on adjacent properties.
- b. A plan showing applicable details, to include lots, streets and right-of-ways, setback lines, dwelling sizes, off-street parking, on-street parking, street trees, sidewalks, multi-use trails, stormwater management facility areas, floodplain and wetlands, topography, and common space.
- c. Specifications, calculations, and applicable percentages for common area, density calculations, lot sizes, land use, gross and net acreage, dwelling units, and parking.
- d. Color elevations of front, sides, and rear of all typical units, including proposed building materials, building heights and any other structures.
- e. Other architectural and engineering data necessary to demonstrate conformity with applicable standards of the district and with the Article 6, Architectural and Design Standards.
- f. Conceptual Signage Plan.

102.8 MH Manufactured Home Residential District

A. Purpose

The MH Manufactured Home Residential District is designed to provide for the inclusion of manufactured and mobile home parks and subdivisions as additional uses in residential districts at locations which are suitable for manufactured home dwellings.

B. Lot Development Standards

The development shall not exceed eight units per acre.

| Use | Lot Area | Lot Width | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-------------|---------------|-------------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Development | 10 acres min. | 200 sq. ft. | 50 ft. | 10 ft. | 40 ft. | 60% | 18 ft. |

Accessory structures shall be prohibited.

C. Mandatory Professional Property Management.

As part of the planning process for the development of a subdivision, the developer shall propose at the time of the request for development a Professional Property Management to be attached to the development of the property. The Home Owners Association shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

D. Protective Covenants

The development shall have a mandatory community association(s) to provide maintenance for all common areas of landscaping within internal right-of-ways and immediately adjacent external right-of-ways), and enforce reasonable and customary property maintenance standards through covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Said subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional five percent hardship) may be leased to third parties by individual owners.

- a. Voluntary compliance with the Gwinnett County Crime Free Multi-Housing program is strongly suggested.”

E. Green/Common Space:

1. Every development shall be required to construct an area of public green space within the confines of the development.
2. At least 15% of the net project acreage (total acreage of the project excluding 50% of the 100-year floodplain and wetland areas) shall be designated on a recorded plat as a permanent common area for the use of the residents of the development.

Amended on 9.28.2020

3. Depending on the scale of the development, the common area shall include at least one conveniently-located public gathering area or activity center with related amenities and improvements in the form of a square, green, plaza, or similar approved element that is accessible to the residents from at least three points of entry by sidewalks. Active recreation areas, including swimming pools, tennis courts, basketball courts, clubhouses, and other recreational amenities may not be constructed in the green space.
4. 50% of the houses must be adjacent to or directly across the street from a common area such as a public green, park, or square. These units shall be rear entry only.
 - a. The minimum size for a public green, park or square 3,000 square feet
 - b. Provide a mix of undisturbed natural plantings and/or formal plantings
 - c. Provide benches, tables, seat walls, planters, play structure, and/or picnic areas/shelter.
 - d. Install outdoor lighting.

102.9 CMU Community Mixed-Use District

A. Purpose

The purpose of the CMU Community Mixed-Use District is to promote complementary groupings of small-scale mixed-use buildings that are within walking distance and compatible with the surrounding neighborhood. It is the intent of this district to provide for diverse housing options to accommodate multigenerational communities within a range of residential building forms, lot sizes, and dwelling sizes and neighborhood-oriented retail, services, and low-intensity office uses that are within convenient walking distances.

Property in the CMU Community Mixed-Use District shall be developed in accordance with the Minimum Lot Area requirement and the applicable site related provisions of the City of Lawrenceville Development Regulations.

B. Land Use Mix

Each CMU development shall include a mix of land uses, as indicated in the table below.

1. The intent of allowing these nonresidential uses is to create a small node of retail and commercial services primarily for the convenience and amenity of residents of the CMU District. Nonresidential development must be compatible with the residential component of the development, and in general with the Architectural Design Standards specified in this section and [Article 6, Architectural Standards and Design Guidelines](#).

| Land Use | Percentage of Gross Land Area | |
|--|-------------------------------|---------|
| | Minimum | Maximum |
| Residential Uses | 30% | 75% |
| Civic/Institutional Uses | 15% | 50% |
| Commercial/Retail, Light Industrial or Office Uses | 15% | 50% |

2. This district provides for a diversity of housing types. Each CMU development shall include at least one housing option, including apartments, single-family residences, or townhomes.

| |
|---|
| a. Single-family detached dwellings on large lots (at least 9,500 sq. feet) |
| b. Single-family detached dwellings on mid-size lots (7500-9499 sq. feet) |
| c. Single-family detached dwellings on small lots (4500-7499 sq. feet) |
| d. Townhouses (see RM-8 standards above) |
| e. Multifamily (see RM-12 and RM-24 standards above) |

Amended on 9.28.2020

C. Lot Development Standards

| Project Area Standard | | | Off Internal Streets or Private Driveways | | |
|-----------------------|---------------|-------------|---|-------------------|-------------------|
| Minimum | Road Frontage | Max. Height | Min. Front Setback | Min. Side Setback | Min. Rear Setback |
| 5 acres | 40 ft./lot | 45 ft. | 5-15 ft. | 10-20 ft. | 25-40 ft. |

- This Minimum Lot Area shall not be reduced by a Variance. If property was zoned (RM-12) General Residence, 3,600 Sq. Ft. District at the time of adoption of the City of Lawrenceville Zoning Ordinance 2020 (ZON-ORD 2020-9), on May 20, 2020, and property does not meet the Minimum Lot Area then the property owner may apply for a Variance.
- Duplexes shall be prohibited.

D. Mandatory Homeowners Association. As part of the planning process for the development of a subdivision, the developer shall propose at the time of the request for development a Home Owners Association to be attached to the development of the property. The Home Owners Association shall be recorded in the deed records of the Superior Court of Gwinnett County either as written restrictive covenants or on the plat for development of the subdivision.

E. Protective Covenants

The development shall have a mandatory community association(s) to provide maintenance for all common areas of landscaping within internal right-of-ways and immediately adjacent external right-of-ways), and enforce reasonable and customary property maintenance standards through covenants, conditions, and restrictions that will be recorded with the City prior to the issuance of the first building permit. The covenants will run for 20 years and automatically renew every 20 years unless 51% of the persons owning lots in the subdivision vote to terminate the covenants as governed by O.C.G.A. 44-5-60. Said subject to applicable City, local, and federal rules, laws, regulations, and rulings of courts having competent jurisdiction over the subject property, said covenants shall include a restriction that no more than 10% of the single-family units (with an additional five percent hardship) may be leased to third parties by individual owners.

- Voluntary compliance with the Gwinnett County Crime Free Multi-Housing program is strongly suggested.

F. Green/Common Space:

1. Every development shall be required to construct an area of public green space within the confines of the development.
2. At least 15% of the net project acreage (total acreage of the project excluding 50% of the 100-year floodplain and wetland areas) shall be designated on a recorded plat as a permanent common area for the use of the residents of the development.
3. Depending on the scale of the development, the common area shall include at least one conveniently-located public gathering area or activity center with related amenities and improvements in the form of a square, green, plaza, or similar approved element that is accessible to the residents from at least three points of entry by sidewalks. Active recreation

areas, including swimming pools, tennis courts, basketball courts, clubhouses, and other recreational amenities may not be constructed in the green space.

4. 50% of the houses must be adjacent to or directly across the street from a common area such as a public green, park, or square. These units shall be rear entry only.
 - a. The minimum size for a public green, park or square 3,000 square feet
 - b. Provide a mix of undisturbed natural plantings and/or formal plantings
 - c. Provide benches, tables, seat walls, planters, play structure, and/or picnic areas/shelter.
 - d. Install outdoor lighting.

F. Connectivity

1. Interconnected network. It is the intent of this section that the public-access-ways, walkways, transportation facilities, and improvements in the mixed-use district contribute to an interconnected and continuous network providing convenient vehicular and pedestrian access to abutting properties. The design of the development and related public improvements shall provide for maximum connections for automobiles, pedestrians, bicycles, and public transportation to off-site and on-site attractions such as concentrations of employment, shopping, housing, community services, public parking parks, and public facilities.
2. Vehicular connectivity
 - a. No streets may be longer than 400 feet without an intersection with another street or alley.
 - b. The street network shall form a connected pattern (grid system), with a minimum of cul-de-sacs approved by the Director of Planning and Development only in cases of topographical hardship. Street shapes should be varied with loop streets, curving crescents, ovals, and courts providing visual interest and traffic calming effects. Approved cul-de-sac streets may be no longer than 400 feet in length. Street patterns shall be designed to respect and follow existing terrain as much as possible to minimize earthmoving and disruption of the existing topography.
 - c. New streets shall contribute to an interconnected network and meet all of the following standards:
 - i. Location of the new street shall be reviewed and approved by the appropriate City department. Such approval shall be contingent on a finding that the new street will serve a public purpose such as improving traffic safety, reducing traffic congestion, or improving vehicular and pedestrian circulation and access to major thoroughfares.
 - ii. Right-of-way and design of the new street shall meet applicable requirements of the appropriate City department.
3. Pedestrian Connectivity
 - a. There shall be an adequate separation of pedestrian walkways from automobile traffic within a development. Appropriate design elements or traffic-calming measures, such as paving material variation or barriers (structural or spatial), shall be provided to distinguish vehicular and pedestrian access points.
 - b. Safe, convenient, and continuous pedestrian walkways shall be provided:
 - i. Between building entrances for all buildings in the same block.
 - ii. Along both sides of the street frontage of all streets.
 - iii. Through parking lots and parking structures at regular intervals connecting to building entrances and the public sidewalks on surrounding streets.

Amended on 9.28.2020

G. Public Improvements

1. Sidewalks shall meet the Engineering Department Requirements.
2. Crosswalks and pedestrian crossing signage shall be provided consistent with the most recent edition of the Manual of Uniform Traffic Control Devices (MUTCD) and AASHTO, as per Engineering Department approval.
3. Greenway Access
 - a. Greenways shall be provided in accordance with the Trail Master Plan and maintained in accordance with the plan and other applicable sections of the Zoning Ordinance. Final location of the greenways shall be coordinated with the Engineering Department.
 - b. If a project abuts a greenway, then a multiuse path shall be provided connecting to the greenway for pedestrian and bicycle use.

H. Access Easements and Inter-parcel Access

1. Inter-parcel access, joint driveways, cross-access drives, and access easements shall be provided as follows except where the Director of Planning and Development determines that they are not feasible due to topographic or other site-specific constraints:
 - a. Inter-parcel driveway connection or provision of a future inter-parcel driveway stub (with appropriate cross-access easements) shall be required between adjacent non-residential properties on arterials or major collectors designated on the Gwinnett County Long Range Road Classification Map.
 - b. Joint driveways and cross-access easements shall be established for non-residential tracts wherever feasible along streets classified as arterials or major collectors on the Gwinnett County Long Range Classification map.
 - c. Roads are to be designed with a design speed of 25 mph and a two-way travel aisle with a minimum of 20 feet to accommodate automobiles, service vehicles, and loading vehicles.
 - d. Driveway aprons, stub-outs, and other design features or traffic calming features may be required by the Director or Engineering Department to indicate cross access or service drive for traffic safety or per City standards.

I. Parking

1. Vehicle Parking
 - a. The minimum number of required off-street parking spaces shall be provided in [Article 5, Parking](#) or in accordance with the following standards, whichever is lower:
 - i. Five parking spaces are required for every 1,000 square feet of the gross floor area of non-residential use.
 - ii. 1.5 parking spaces are required for each residential dwelling unit.
 - iii. The number of required off-street parking spaces may be reduced by an equal number of on-street parking spaces, or by a shared parking agreement.
 - b. All off-street parking must be located to the side or rear of the principal buildings within the CMU District and screened from residential districts. Off-site parking in the front yard is not permitted within the CMU District.
2. Bicycle Racks
 - a. All uses that are required to provide off-street parking spaces for motorized vehicles also shall provide bicycle racks consistent with each of the standards below:

- i. Uses that require more than 50 off-street parking spaces for motorized vehicles shall provide at least one bicycle rack space for every 25 parking spaces required for motorized vehicles.
 - ii. No single building shall be required to provide more than 20 bicycle rack spaces.
 - iii. Bicycle racks shall be located outside of the street right-of-way; in a well-lit area; and no more than 75 feet from the intended use area or building.
- 3. Transit-Oriented Development Parking
 - a. The Director of Planning and Development may grant an administrative variance to reduce the number of parking spaces by no more than 20 percent of the required parking spaces for uses that are located along pedestrian walkways and within 1,320 feet of a fixed public transportation stop.

J. Landscape, Buffers, and Tree Protection

- 1. The purpose of landscaping in the Community Mixed-Use District is to provide for flexibility of design based upon pedestrian and vehicular connectivity; the types of common space areas; architectural design; and density. The objective is to maintain the health and well-being of the trees.
- 2. Buffers and tree protection shall be in conformity with [Article 4, Buffers](#).
- 3. Trees within the Community Mixed-Use development must meet the street tree, parking lot tree, and 16 tree density units per acre requirements. Street trees may count as units toward the tree density requirement.
 - a. Street Trees
 - i. Trees on major entry drives throughout the development shall be canopy trees.
 - ii. Trees on local streets throughout the development may be canopy or small trees.
 - iii. If tree wells are provided within sidewalks, a tree grate or pavers shall be provided for each tree. Engineered soils and irrigation for each tree is required. An owner or developer shall submit to the Department the engineered soil specifications prior to issuance of the development permit. Details of the tree grates are required to be on the plan.
 - b. Parking Lot Trees
 - i. Parking rows shall terminate with a planting island unless adjacent to a landscape strip.
 - ii. Recommendations for parking lot planting area designs:
 - 1) The use of elongated planting strips that is perpendicular to the parking stalls;
 - 2) Irrigation and a long term maintenance plan for newly planted trees and shrubs; and,
 - 3) The use of at-grade planting areas (bioswales) in parking lots to promote Stormwater runoff treatment.
- 4. Screening off-street parking lots
 - a. Off-street parking lots may be screened from adjacent roadways and sidewalks by a five-foot landscape strip with the following requirements:
 - i. One tree for every 25 linear feet of strip length shall be provided. Deciduous trees shall be at least 2-inches caliper and evergreen trees shall be at least 6 feet in height at time of planting. Trees shall be a species native or suitable to this region as provided in [Article 4, Buffers](#).

- ii. One evergreen shrub for each 8 linear feet of strip length shall be provided. Each shrub shall be a species native or suitable to this region.
5. If landscape strips are provided within the right-of-way, they shall be a minimum of five feet in width, measured from the back of the curb and sidewalk.
6. Individual lot trees are not required on detached residential lots.

K. Streetscape Design

1. The location and specifications of other improvements in public right-of-ways, including street lights, bike racks, trash receptacles, benches, street trees, and landscaping, shall be as provided in accordance with the [Article 6, Architectural and Design Standards](#) and the following design criteria:
 - a. Lighting
 - i. A unified lighting plan must be submitted with the concept plan for approval by the Director to be in accordance with [Article 6, Architectural and Design Standards](#), and other sections as applicable. Such lighting provides adequate vehicular and pedestrian visibility and security of on-site areas such as building entrances, parking, service delivery, and pedestrian walkways. Light fixtures shall include glare shields to limit direct rays onto adjacent residential properties. Such a lighting plan must include typical designs for shielded light fixtures, light poles, and lighting levels that are compatible with or complement the surrounding developments.
 - b. Pedestrian Amenities
 - i. Public gathering areas shall be designed with approximately scaled and thematic site furnishings or amenities such as decorative seating, planters, or water fountains. Site furnishings and amenities shall be located outside of the street right-of-way and be privately maintained.
 - ii. Materials should be durable and variable in texture, color, and form. Plastic or petroleum-based resin materials are prohibited.
 - c. Landscaping shall be separated from vehicular uses by some form of barrier such as a high back concrete curb, bollards, curb stops, or other suitable permanent alternatives.

L. Utilities

All existing and proposed utilities located along streets in the Community Mixed-Use District, except for substations and major electric transmission lines located on separate easements, are required to be placed underground or relocated to the rear of the property so that they will be less visible from streets.

M. Signs

Signs for buildings with an individual use or tenant shall be permitted in accordance with [Article 7, Signs](#).

N. Architectural Standards

1. The applicant for a building permit in the Community Mixed-Use District shall prepare and submit preliminary architectural plans and elevations of all buildings for review by the Director. The Director shall review such plans and elevations in order to determine if they conform to the City of Lawrenceville Architectural Standards and are substantially consistent with the City of Lawrenceville Zoning Ordinance.
2. Odor Scrubbing
 - a. When residential uses are located with other non-residential uses within the same building, odor-scrubbing equipment shall be required of the non-residential tenant to eliminate obnoxious odor as deemed appropriate for each use.
3. Doors and Entrances
 - a. Buildings must have a primary entrance door facing a public sidewalk. Entrances at building corners may be used to satisfy this requirement.
 - b. Building entrances may include doors to individual shops or businesses, lobby entrances, entrances to pedestrian-oriented plazas, or courtyard entrances to a cluster of shops or businesses.

O. Outdoor Operations

1. All uses and operations except off-street parking, off-street loading and delivery, and walk-up customer service windows shall be conducted completely within enclosed buildings, except as follows:
 - a. Outdoor seating for restaurants shall be subject to the supplemental use regulations of [Article 2, Section 200.3.50, Outdoor Seating](#) and be located outside of the street right-of-way.
 - b. Outdoor display or sales of merchandise shall be subject to the supplemental use regulations of [Article 2, Section 200.3.49 Outdoor sales, or display](#) and be located outside of the street right-of-way.

P. Property Owners Association

1. Common areas, stormwater management facilities, and floodplain and wetland areas shall be owned in fee simple by a mandatory property owners association or approved entity. The developer shall record the deed to the common area prior to, or concurrent with, the recording of the first final subdivision plat.
2. The property owners association or other approved entity shall be responsible for the continuous maintenance and protection of buffers, common areas, and recreation areas established pursuant to this Section.
3. At a minimum, the property owners association's bylaws or covenants shall contain the following provisions:
 - a. Governance of the association by the [Georgia Property's Association Act \(OCGA Section 44-3-220 et seq.\)](#) or a successor to that Act that grants lien rights to the association for maintenance expenses and tax obligations.
 - b. Responsibility for maintenance of the open space or common area.
 - c. Responsibility for insurance and taxes.
 - d. Automatic compulsory membership of all lot purchasers and their successors and compulsory assessments.

Amended on 9.28.2020

- e. Conditions and timing of transferring control of the association from the developer to the lot owners.
- f. Guarantee that the association will not be dissolved without the advance approval of the City Council.

Q. Application Process

- 1. The Community Mixed-Use rezoning process shall follow the process for rezoning as prescribed in [Article 9, Section 907, Rezoning Application Public Hearing Procedures](#) with the following modifications:
 - a. All such rezoning applications shall be accompanied by a Zoning Exhibit for review and approval by the Director of Planning and Development. The Zoning Exhibit shall provide all information necessary to demonstrate that it achieves the criteria 1 through 6 (see below) as applicable.
 - b. If the rezoning application is approved by the City Council, then such rezoning shall be conditioned on the applicant's substantial conformity with the Zoning Exhibit, including any modifications or conditions approved by the City Council pursuant to its deliberations on the application.
 - c. Zoning Exhibit approval shall not constitute entitlement to permits.
 - d. Each applicant for the mixed-use district shall provide evidence of the unified control of the entire parcel. During the development process, more than one owner may participate in the development of the approved plan so long as each parcel of land remains subject to all of the terms and conditions of the Zoning Exhibit approved for the property as a whole.

R. Zoning Exhibit

- 1. As part of the application for rezoning, an exhibit shall be submitted that includes the following information:
 - a. A location map showing the boundaries of the property with the current zoning of the property, as well as zoning on adjacent properties.
 - b. A plan showing applicable details, to include lots, streets and right-of-ways, setback lines, dwelling sizes, off-street parking, on-street parking, street trees, sidewalks, multi-use trails, stormwater management facility areas, floodplain and wetlands, topography, and common space.
 - c. Specifications, calculations, and applicable percentages for common area, density calculations, lot sizes, land use, gross and net acreage, dwelling units, and parking.
 - d. Color elevations of front, sides, and rear of all typical units, including proposed building materials, building heights and any other structures.
 - e. Other architectural and engineering data necessary to demonstrate conformity with applicable standards of the district and with the [Article 6, Architectural and Design Standards](#).
 - f. Conceptual Signage Plan.

S. Phasing Plan

A phasing plan shall be submitted with the Concept Plan and approved by the Director unless the entire development is to be completed at one time. Such phasing plan shall describe and illustrate in a written and graphic format the incremental implementation of the Mixed-Use development over a number of years, including the sequence, timing, and responsibility for construction of each building, support facilities, infrastructure, and utilities. The revision of the phasing plan is permitted and must be approved by the Director of Planning and Development prior to each construction phase.

T. Concept Plan

A concept plan must be submitted and approved by the Director after the rezoning process and prior to submittal of an application for a Development Permit. The purpose of the Concept Plan review is to ensure the soundness of the proposed development, compatibility with the surrounding area and compliance with zoning conditions. The Concept Plan shall be developed in substantial conformance with the Zoning Exhibit approved by the City Council, along with any conditions added thereto by the City Council, according to the plan and plat guidelines listed in the Development Regulations.

U. Building Plans

Prior to issuance of a building permit for any occupied structure to be located within the Community Mixed-Use District, the builder shall provide architectural plans and elevations at a scale no smaller than 1/8"=1'-0" that demonstrate compliance with the requirements of the Architectural Design Standards. The Director shall have the authority to review and approve the building plans for conformity with the requirements of this article and [Article 6, Architectural and Design Standards](#).

V. Other Requirements

The applicant shall adhere to all other applicable requirements of this Ordinance and other applicable requirements of the City of Lawrenceville. In any case where the standards and requirements of this district conflicts with other provisions of the City of Lawrenceville Code of Ordinances, the requirements of this district shall govern.

102.10 OI Office Institutional District

A. Purpose

The purpose of the Office Institutional District is to provide for a wide range of office and institutional establishments not involving the sale, storage, or processing of merchandise.

B. Lot Development Standards

| Use | Lot Area | Lot Width | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-----------|---------------------|-----------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Principal | 20,000 sq. ft. min. | 100 ft. | 50 ft. | 10 ft. | 15 ft. 40ft. | 70 % | 35 ft. |

C. Miscellaneous Provisions

The OI District shall be located only on major arterial streets, state highways, or on access roads paralleling expressways.

102.11 BG General Business District

A. Purpose

This district is intended to provide for a wide range of retail and service establishments.

B. Lot Development Standards

| Use | Lot Area Min. | Lot Width Min. | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-----------|---------------|----------------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Principal | None | None | 50 ft. | 10 ft. | 10 ft. | 95% | 35 ft. |

102.12 BGC Central General Business District

A. Purpose

The BGC Central General Business District is intended to preserve the integrity of the historic characteristics of the Downtown area.

B. Lot Development Standards

| Use | Lot Area Min. | Lot Width Min. | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-----------|---------------|----------------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Principal | No min. | No min. | No min. | No min. | No min. | 100% | 40 ft. |

C. Miscellaneous Provisions as they apply to New Development

1. Off-street loading shall be provided for all new buildings.
If off-street parking is provided on-site, then it should be located to the rear or side of the structure and minimize curb cuts along primary streets.

102.13 HSB Highway Service Business District

A. Purpose

This district is intended to provide for the effective use of land near major highways and highway interchanges.

B. Lot Development Standards

| Use | Lot Area Min. | Lot Width Min. | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-----------|----------------|----------------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Principal | 10,000 sq. ft. | 70 ft. | 50 ft. | 10 ft. | 10 ft. | 75% | 45 ft. |

Subject to review by the Director of Planning and Development.

Amended on 9.28.2020

102.14 LM Light Manufacturing District

A. Purpose

This district is intended to provide for a wide range of light industrial uses, all of which shall be able to meet comparatively rigid specifications as to nuisance free performance.

B. Lot Development Standards

| Use | Lot Area Min. | Lot Width Min. | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-----------|----------------|----------------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Principal | 25,000 sq. ft. | 50 ft. | 50 ft. | 0 ft. | 0 ft. | 85% | 50 ft. |

C. Miscellaneous Provisions

Standards in [Article 6 Architectural and Design Standards](#), for light manufacturing shall apply.

102.15 HM Heavy Manufacturing District

A. Purpose

The HM Heavy Manufacturing District is intended to provide for the widest range of industrial operations permitted in the City.

B. Lot Development Standards

| Use | Lot Area Min. | Lot Width Min. | Front Setback | Min. Side Setback | Min. Rear Setback | Impervious Surface Coverage | Max. Height |
|-----------|----------------|----------------|---------------|-------------------|-------------------|-----------------------------|-------------|
| Principal | 20,000 sq. ft. | 100 ft. | 50 ft. | 10 ft. | 40 ft. | 85% | 70 ft. |

C. Miscellaneous Provisions

Standards in [Article 6 Architectural and Design Standards](#), for heavy manufacturing shall apply.

Uses

103.1 Classification of Allowed Uses

- A. Allowed uses in each zoning district are identified in Section 103.1, Use Table. The table identifies each use as described below:
1. Permitted Use (P)
Identifies that a use is permitted as of right in the specified district but may be subject to certain requirements of the Zoning Code.
 2. Special Use (S)
Indicates that a use is not allowed in a district as a matter of right, but is permitted upon findings of the City Council, after a recommendation of the Planning Commission, that under particular circumstances present such use is in harmony with the principal permitted uses of the district. Allowable conditions are specifically listed under the district regulations. Procedure for a special use permit shall follow that which is required for a rezoning, including the fees.
 3. Supplemental or Accessory Regulations (√)
See [Article 2, Supplementary Regulations](#).
- B. Any use not identified as permitted, special, or accessory and not determined to be part of a similar use determination by the Director of Planning and Development is prohibited from the applicable zoning district.

103.2 Use Table

The uses set forth in the table below shall be permitted only as listed within each zoning district and only in the manner for which is listed. Any use not listed in said table shall be prohibited, except contained herein. Additionally, for any use not listed in said table, the Director of Planning and Development shall have the authority to determine the most appropriate zoning district(s) and/or Special Use Permit requirements for such use, after receiving documentation from the property owner adequately outlining and describing the specific details of the proposed use.

P- Permitted

S- Requires a Special Use Permit

Blank- Use not permitted

SAR- Supplemental or Accessory Regulations √- See [Article 2, Supplemental Regulations](#)

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|---|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Accessory Building and Structure | √ | P | P | P | P | | | | | | | | | | | |
| Acupuncture, Holistic Medicine | | | | | | | | | | S | P | P | | P | | |
| Adult Uses | √ | | | | | | | | | | | | | S | | |
| Agriculture (crop or animal production) | √ | P | | | | | | | | | | | | | | |
| Aircraft Factory | | | | | | | | | | | | | | | | P |
| Aircraft Hangar and Maintenance | | | | | | | | | | | | | | | P | P |
| Aircraft Landing Field, Heliport, Helipad | | | | | | | | | | | | S | | S | S | P |
| Ambulance or Medical Transport Company | | | | | | | | | | | | S | | S | P | P |
| Animal Hospital or Veterinary Clinic | √ | S | | | | | | | | S | S | P | | P | P | P |
| Antique Shop | | | | | | | | | | P | | P | P | P | S | |
| Art and School Supply Store | | | | | | | | | | P | | P | P | P | S | |
| Art Gallery | | | | | | | | | | P | | P | P | P | | |
| Asphalt Plant | | | | | | | | | | | | | | | | S |
| Auction House | | | | | | | | | | S | | S | S | P | P | P |
| Automatic Teller Machine, Attached | | | | | | | | | | P | P | P | P | P | P | P |

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Automatic Teller Machine-Freestanding | √ | | | | | | | | | P | | P | P | P | | |
| Automobile Accessories Sales and Installation | | | | | | | | | | | | S | | S | P | P |
| Automobile Body Repair, Painting or Rebuilding | √ | | | | | | | | | | | S | | S | P | P |
| Automobile Manufacturing Plant | | | | | | | | | | | | | | | | P |
| Automobile, Truck or Vehicle Storage Lot (excl. junk/wrecked vehicles) | √ | | | | | | | | | | | S | | S | S | P |
| Automobile Parts Store (with installation) | | | | | | | | | | | | S | | S | P | P |
| Automobile Parts Store (without installation) | | | | | | | | | | | | P | | P | P | P |
| Automobile Repair and Maintenance | √ | | | | | | | | | | | S | | S | P | P |
| Automobile Sales or Auction and Related Service (outdoor sales) Including Autobroker | √ | | | | | | | | | | | S | | S | S | P |
| Automobile Sales or Auction and Related Services (indoor only) Including Autobroker | √ | | | | | | | | | | | | | | P | P |
| Automobile Wash (Carwash) | √ | | | | | | | | | | | S | | S | P | P |
| Bail Bonding | √ | | | | | | | | | | | S | | S | | |
| Bakery (Industrial) | √ | | | | | | | | | | | | | | P | P |
| Bakery (Retail) | | | | | | | | | | P | | P | P | P | | |
| Bank or Financial Services Institution | | | | | | | | | | P | P | P | P | P | P | |
| Bed and Breakfast Inn | √ | S | S | S | | | | | | | | | S | | | |
| Beverage Bottling Plant | | | | | | | | | | | | | | | P | P |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Bicycle Shop | | | | | | | | | | P | | P | P | P | P | P |
| Boat and Marine Equipment Sales and Service | | | | | | | | | | | | S | | S | S | S |
| Book, Music and Media Store | | | | | | | | | | P | | P | P | P | S | |
| Bowling Alley (accessory use) | | | | | | | | | | P | | P | P | P | S | |
| Bowling Alley (principle use) | | | | | | | | | | S | | P | S | P | S | |
| Brewery, Craft | | | | | | | | | | S | | S | S | P | P | P |
| Brewery, Distillery or Winery | | | | | | | | | | | | | | | S | S |
| Building Materials Sales (indoors) | | | | | | | | | | | | P | | P | P | P |
| Building Materials Sales (outdoors) | | | | | | | | | | | | S | | S | P | P |
| Bulk Storage Tank | | | | | | | | | | | | | | | P | P |
| Cabinet Shop | | | | | | | | | | | | S | | | P | P |
| Call Center | | | | | | | | | | | S | P | | P | P | P |
| Carpet and Upholstery Cleaning Service | | | | | | | | | | | | P | | P | P | P |
| Catering Service | | | | | | | | | | | | P | P | P | P | P |
| Cement, Concrete or Masonry Plant | | | | | | | | | | | | | | | | S |
| Cemetery or Mausoleum | √ | S | | | | | | | | | | | | | | |
| Cemetery, Family | √ | P | P | P | | | | | | | | | | | | |
| Check Cashing, Wire Transfer, Payday Loan Facility | √ | | | | | | | | | | | S | | S | | |
| Chemical Plant (non-pharmaceutical) | | | | | | | | | | | | | | | S | S |
| Child Caring Institutions (CCI) | √ | S | S | S | | | | | | | | | | | | |
| Clothing, Apparel and Shoe Stores | | | | | | | | | | P | | P | P | P | S | |
| Clothing, Apparel or Shoe Manufacturing | | | | | | | | | | | | | | | P | P |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|---|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Club, Lodge or Fraternal Organization | | | | | | | | | | S | S | P | P | P | S | |
| Cold Storage Plant | | | | | | | | | | | | | | | P | P |
| Community Center or Cultural Facility | √ | P | P | P | | | | | | P | P | P | P | P | S | S |
| Community Garden | √ | P | P | P | P | P | P | P | P | P | | | | | P | P |
| Community Living Arrangement (CLA) | √ | S | S | S | | | | | | | | | | | | |
| Composting Facility (municipal solid waste) | | | | | | | | | | | | | | | | S |
| Composting Facility (yard trimmings) | √ | | | | | | | | | | | | | | S | P |
| Consignment Shop, Clothing | | | | | | | | | | P | | P | P | P | S | |
| Consignment Shop, General | | | | | | | | | | P | | P | | P | S | |
| Contractors Office, Building Construction | √ | | | | | | | | | | | P | | P | P | P |
| Contractors Office, Heavy/Civil | √ | | | | | | | | | | | | | | S | P |
| Contractors Office, Landscape | √ | | | | | | | | | | | S | | S | P | P |
| Convenience Store (with fuel pumps) | | | | | | | | | | | | P | | P | | |
| Convenience Store (without fuel pumps) | | | | | | | | | | | | P | S | P | | |
| Convention Facility | | | | | | | | | | | | P | | | P | P |
| Copy Shop and Parcel Shipping Store | | | | | | | | | | P | | P | P | P | P | |
| Corporate Training and Education Centers | | | | | | | | | | P | S | P | P | P | P | P |
| Crematory (principal use) | | | | | | | | | | | | | | | S | P |
| Customary Home Occupation | √ | P | P | P | P | P | P | P | P | | | | | | | |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Data Center | | | | | | | | | | | P | P | | P | P | P |
| Day Care Facility | | | | | | | | | | S | S | P | P | P | S | S |
| Day Care Facility (family) | √ | S | S | S | | | | | | | | | | | | |
| Department Store, Big Box Specialty Store or Supercenter | √ | | | | | | | | | | | S | | P | | |
| Depot / Passenger Terminal (bus or rail) | | | | | | | | | | | | S | | S | P | P |
| Die Casting | | | | | | | | | | | | | | | P | P |
| Distribution Facility | | | | | | | | | | | | | | | P | P |
| Dollar or Variety Store | | | | | | | | | | | | S | | S | | |
| Driving Instruction/DUI School | | | | | | | | | | | | P | | P | | |
| Drug Abuse Treatment Facility | √ | | | | | | | | | | | S | | S | | |
| Dry Cleaning | | | | | | | | | | P | | P | P | P | P | |
| Dwelling, Mobile or Manufactured Home | | S | | | | | | | P | | | | | | | |
| Dwelling, Multifamily | | | | | | | P | | | P | | | | | | |
| Dwelling, Single-Family Detached | | P | P | P | P | | | | | P | | | | | | |
| Dwelling, Townhouse | | | | | | P | | P | | P | | | | | | |
| Electronics, Cell Phone and Computer (Retail) | | | | | | | | | | P | | P | P | P | P | |
| Emissions Inspection Station | √ | | | | | | | | | | | P | | P | P | P |
| Equestrian Facility, Riding Stables or Academy | √ | P | | | | | | | | | | | | | | |
| Explosives Plant/Storage | | | | | | | | | | | | | | | S | S |
| Farmer's Market (including off-site products) | | S | | | | | | | | | | S | S | | | |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Farmer's Market (on-site products only) | | P | | | | | | | | | | S | S | | | |
| Fat and Bone Rendering Plant | | | | | | | | | | | | | | | | S |
| Feed Processing Facility | | | | | | | | | | | | | | | S | P |
| Fertilizer Plant | | | | | | | | | | | | | | | | S |
| Fireworks Sales (accessory use) | √ | | | | | | | | | | | P | | P | | |
| Fireworks Sales (principal use) | √ | | | | | | | | | | | S | | S | | |
| Florist or Flower Shop | | | | | | | | | | P | S | P | P | P | P | P |
| Food Processing/Packaging/Canning Plant | | | | | | | | | | | | | | | S | P |
| Food Store, Specialty (butcher, greengrocer, bakery) | | | | | | | | | | P | | P | P | P | P | |
| Fortune Telling | √ | | | | | | | | | | | | P | P | | |
| Funeral Home (including accessory crematory) | | | | | | | | | | | | S | | P | P | P |
| Furniture or Home Furnishings Store | | | | | | | | | | P | | P | P | P | P | S |
| Garden Supply Center | | | | | | | | | | | | S | | P | P | P |
| Gift Shop or Greeting Card Shop | | | | | | | | | | P | | P | P | P | | |
| Golf Course | | S | S | S | | | | | | | | | | | | |
| Golf Driving Range | | S | | | | | | | | | | S | | S | S | S |
| Greenhouse or Plant Nursery (wholesale) | | P | | | | | | | | | | | | | P | P |
| Grocery Store | | | | | | | | | | P | | P | P | P | S | |
| Hair Salon, Beauty Parlor or Barber Shop | √ | | | | | | | | | P | S | P | P | P | | |
| Hardware Store | | | | | | | | | | P | | P | P | P | S | |
| Health Club, Spa, or Fitness Center | | | | | | | | | | P | | P | P | P | S | S |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|---|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Heavy or Farm Equipment Sales and Service | | | | | | | | | | | | | | | S | P |
| Home Improvement Center | | | | | | | | | | | | S | | P | S | |
| Hookah/Vapor Bar or Lounge | √ | | | | | | | | | | | S | S | S | | |
| Hospice Home | | | | | | | | | | | S | S | | P | | |
| Hospital | | | | | | | | | | | | P | | P | P | P |
| Hotel or Motel | √ | | | | | | | | | | | S | S | P | | |
| Human Services Ministry | | | | | | | | | | | | P | | P | P | P |
| Interior Decorating Shop | | | | | | | | | | P | | P | P | P | P | P |
| Janitorial and Maid Services | | | | | | | | | | | | P | | P | P | P |
| Jewelry Store | | | | | | | | | | P | | P | P | P | | |
| Joint Living Residence | √ | | | | | S | | | | | S | | | | | |
| Kennel or Pet Boarding, Indoor | √ | P | | | | | | | | | | P | | P | P | P |
| Kennel or Pet Boarding, with Outdoor Facilities | √ | S | | | | | | | | | | S | | S | S | S |
| Laboratory (medical or dental) | | | | | | | | | | | S | S | | | P | P |
| Landfill | √ | S | | | | | | | | | | | | | | S |
| Laundry / Dry Cleaning Plant | | | | | | | | | | | | | | | P | P |
| Lawn Treatment Service | | | | | | | | | | | | | | P | P | P |
| Liquid Waste Treatment/Recycling | | | | | | | | | | | | | | | S | S |
| Livestock Sales Pavilion or Auction Facility | √ | S | | | | | | | | | | | | | | |
| Livestock, keeping of (for personal utility) | √ | P | S | S | | | | | | | | | | | | |
| Live/Work | √ | | | | | | | | | P | | | P | | | |
| Locksmith | | | | | | | | | | | | P | | P | P | P |
| Machine Shop | | | | | | | | | | | | S | | | P | P |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Maintenance Shop (fleet vehicles) | | | | | | | | | | | | | | | P | P |
| Manufactured Building or Mobile Home Sales | √ | | | | | | | | | | | | | S | S | P |
| Manufacturing, General | | | | | | | | | | | | S | S | S | P | P |
| Massage Therapy | √ | | | | | | | | | | | P | | P | | |
| Medical Office or Clinic | | | | | | | | | | | P | P | P | P | P | P |
| Metal Smelting / Forging Works | | | | | | | | | | | | | | | | P |
| Motorcycle and Personal Watercraft Sales and Related Service | | | | | | | | | | | | S | | S | P | P |
| Motorcycle and Personal Watercraft Service and Repair | | | | | | | | | | | | S | | S | P | P |
| Motorcycle Parts, Accessories and Apparel Store | | | | | | | | | | | | P | | P | P | P |
| Movie Studio | | | | | | | | | | | | | | | P | P |
| Movie Theater, Cineplex, or Multiplex | | | | | | | | | | P | | P | S | P | | |
| Moving Company | | | | | | | | | | | | S | | P | P | P |
| Museum or Library | | | | | | | | | | P | | P | P | P | P | P |
| Musical Instrument Store | | | | | | | | | | P | | P | P | P | P | P |
| Nightclub, Dance Club, or Lounge | | | | | | | | | | S | | S | S | P | | |
| Nursing Home | | | | | | | | | | | S | P | | P | S | S |
| Showroom Facility (accessory) | | | | | | | | | | | | P | | P | P | P |
| Outdoor Sales, or Display (retail) | √ | | | | | | | | | | | S | | S | S | S |
| Outdoor Storage (other than junk/salvage yards) | √ | | | | | | | | | | | | | | P | P |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|---|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Paper / Pulp Mill | | | | | | | | | | | | | | | | S |
| Parking Garage or Lot (principal use) | √ | | | | | | | | | S | | P | P | P | P | P |
| Pawn Shop | √ | | | | | | | | | | | S | | S | | |
| Personal Care Home, Commercial | | | | | | | | | | | S | P | S | P | | |
| Personal Care Home, Family | √ | S | S | S | | | | | | | | | | | | |
| Pest Control / Extermination Business | | | | | | | | | | | | P | | P | P | P |
| Pet Grooming | | | | | | | | | | P | | P | P | P | S | |
| Pet Shop or Pet Supply Store | | | | | | | | | | P | | P | P | P | | |
| Petroleum Refinery / Processing Plant | √ | | | | | | | | | | | | | | | S |
| Pharmaceutical Manufacturing | | | | | | | | | | | | | | | P | P |
| Pharmacy or Drug Store | | | | | | | | | | P | | P | P | P | | |
| Photo Processing Plant | | | | | | | | | | | | | | | P | P |
| Place of Worship | √ | S | S | S | | | | | | S | P | P | P | P | S | S |
| Plastics Extrusion | | | | | | | | | | | | | | | P | P |
| Plumbing Equipment Dealer | √ | | | | | | | | | | | P | | P | P | P |
| Pool or Billiards Halls | | | | | | | | | | S | | S | | S | | |
| Poultry / Meat Processing Plant | | | | | | | | | | | | | | | | S |
| Printing, Bookbinding or Publishing Plant | | | | | | | | | | | | S | | | P | P |
| Quarry, Mining, Borrow Pit | √ | | | | | | | | | | | | | | S | S |
| Radio and Television Station or Studio | | | | | | | | | | | | P | | P | P | P |
| Railroad Repair or Storage Yard | | | | | | | | | | | | | | | S | P |
| Recording / Rehearsal Studio | | | | | | | | | | | | P | S | P | P | P |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Recovered Materials Processing Facility | √ | | | | | | | | | | | | | | S | P |
| Recreation and Entertainment Facility (indoor) | | | | | | | | | | | | P | P | P | P | S |
| Recreation and Entertainment Facility (outdoor) | | | | | | | | | | | | S | | S | S | S |
| Recreational Vehicle Park or Campground | | S | | | | | | | | | | | | | | |
| Recreational Vehicle Rental, Sales and Service | | | | | | | | | | | | S | | S | S | P |
| Rental, Automobile | | | | | | | | | | | | P | | P | P | P |
| Rental, Consumer and Commercial | | | | | | | | | | | | S | | S | P | P |
| Rental, Industrial | | | | | | | | | | | | | | | S | P |
| Repair Shop, Electronics and Small Appliance | | | | | | | | | | | | P | | P | P | P |
| Repair Shop, Major Appliance | | | | | | | | | | | | S | | P | P | P |
| Repair Shop, Shoe and Leather | | | | | | | | | | | | P | P | P | P | P |
| Research or Testing Facility (indoor) | | | | | | | | | | | | S | | | P | P |
| Research or Testing Facility (outdoor) | | | | | | | | | | | | | | | S | S |
| Restaurant (coffee shop, doughnut shop, or ice cream parlor) | | | | | | | | | | P | | P | P | P | S | |
| Restaurant (drive-in or drive-thru fast food) | | | | | | | | | | | | P | | P | | |
| Restaurant (full service) | | | | | | | | | | P | | P | P | P | S | S |
| Retirement Community, Continuing Care | √ | | | | | | | | | P | | | | | | |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|---|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Retirement Community, Independent Living | √ | | | | | | P | | | P | | | | | | |
| Salvage Operation or Junk Yard | √ | | | | | | | | | | | | | | S | S |
| Sawmills and Logging | | S | | | | | | | | | | | | | S | P |
| School or College, Business | | | | | | | | | | | S | P | | P | P | P |
| School, Montessori | | | | | | | | | | | P | P | P | P | P | S |
| School, Private (College or University) | | S | | | | | | | | | P | P | P | P | P | P |
| School, Private (Primary and Secondary) | √ | S | | | | | | | | | P | P | P | P | P | P |
| School, Trade or Vocational | | | | | | | | | | | | S | | P | P | P |
| Scrap Tire Processing, Grinding or Retreading | | | | | | | | | | | | | | | S | S |
| Self-Storage or Mini-Warehouse Facility | √ | | | | | | | | | | | S | | P | P | P |
| Septic Tank Pumping Company | | | | | | | | | | | | | | | S | P |
| Shelter, Homeless | | | | | | | | | | | | S | | S | S | S |
| Shooting or Archery Range, and similar outdoor recreation | | S | | | | | | | | | | S | | S | S | S |
| Shooting Ranges, Indoor | | | | | | | | | | | | S | S | S | P | |
| Sign Shop (General Fabrication) | | | | | | | | | | | | S | | | P | P |
| Sign Shop (Graphic Printing, Screen Printing) | | | | | | | | | | | | P | P | | P | P |
| Smoke or Novelty Shop | | | | | | | | | | | | S | | S | | |
| Soft Drink Bottling / Distribution Plant | | | | | | | | | | | | | | | P | P |
| Solid Waste Transfer Station | | | | | | | | | | | | | | | | S |

Amended on 9.28.2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Special Events Facility | √ | | | | | | | | | | | S | S | S | S | S |
| Sporting Goods Store | | | | | | | | | | P | | P | P | P | | |
| Sports Training Facility (indoor) | | | | | | | | | | | | P | | P | P | P |
| Sports Training Facility (outdoor) | | | | | | | | | | | | S | | S | P | P |
| Stadium, Concert Hall or Amphitheater | | | | | | | | | | S | | P | S | S | S | S |
| Stone Yard or Stone Cutting | | | | | | | | | | | | | | | P | P |
| Studio, Art | | | | | | | | | | P | P | P | P | P | P | P |
| Studio, Dance or Martial Arts | | | | | | | | | | P | S | P | P | P | P | P |
| Studio, Photography | | | | | | | | | | P | S | P | P | P | P | P |
| Swimming Pool Sales Facility | | | | | | | | | | | | P | | P | P | P |
| Swimming Pool Supply Store | | | | | | | | | | | | P | | P | P | P |
| Tailor, Dressmaker, Sewing Shop | | | | | | | | | | P | | P | P | P | P | P |
| Tall Structures | √ | | | | | | | | | | S | S | S | S | S | S |
| Tanning Salon | | | | | | | | | | P | | P | P | P | | |
| Tattoo and Body Piercing | √ | | | | | | | | | | | S | | S | | |
| Taxi or Limousine Service | √ | | | | | | | | | | | S | | S | P | P |
| Taxidermist | | | | | | | | | | | | P | | S | P | P |
| Textile or Carpeting Factory | | | | | | | | | | | | | | | P | P |
| Thrift Store or Used Merchandise Sales | | | | | | | | | | | | P | | P | P | P |
| Title Loan Facility | √ | | | | | | | | | | | S | | S | | |
| Towing / Wrecker Service and Impound Lot | | | | | | | | | | | | | | | S | S |
| Toy Store, Hobby Shop or Game Store | | | | | | | | | | P | | P | P | P | | |
| Travel Agency | | | | | | | | | | P | P | P | P | P | | |
| Tree Service | | | | | | | | | | | | | | | P | P |

Amended on 9-28-2020

| Uses | SAR | AR | RS-180 | RS-150 | RS-60 | RM-8 | RM-12 | RM-24 | MH | CMU | OI | BG | BGC | HS B | LM | HM |
|--|-----|----|--------|--------|-------|------|-------|-------|----|-----|----|----|-----|------|----|----|
| Truck Sales, Leasing and/or Service, Heavy | √ | | | | | | | | | | | | | S | P | P |
| Truck Terminal or Intermodal Terminal | | | | | | | | | | | | | | | S | P |
| Trucking and Hauling (dirt, gravel, sand, etc.; incl. stockpiling) | | | | | | | | | | | | | | | S | P |
| Tutoring and Learning Centers | | | | | | | | | | P | S | P | P | P | | |
| Upholstery Shop | | | | | | | | | | | | P | | S | P | P |
| Urgent Care Facility | | | | | | | | | | | | P | | P | | |
| Waste Incineration Facility | | | | | | | | | | | | | | | | S |
| Welding Shop | | | | | | | | | | | | S | | | P | P |
| Wholesale Membership Club | | | | | | | | | | | | P | | P | S | S |
| Wholesaling and Warehousing (retail accessory only) | | | | | | | | | | | | | | | P | P |
| Wood Chipping and Shredding | √ | | | | | | | | | | | | | | S | P |

Amended on 9.28.2020