

Dynamic Car Wash Equipment
 48 Acacia Dr
 Sanger, CA 93657 US
 dynamicrepairs559@icloud.com

Estimate

ADDRESS

Tulare Car Wash
 1201 N. West St.
 Tulare, CA 93274

ESTIMATE # 1043
DATE 11/11/2022
EXPIRATION DATE 12/31/2022

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
Sales	Not Motor City Wash Works - (From NS Car Wash)Wheel Brush with multi-diameter HELIX brush, 14" & 16" Pneumatically controlled brush penetration with 2SCFM 1/2 HP electric drive motor (3 phase at 208/230 - 460 VAC @ 60 HZ) at 116 RPM brush rotational speed Water Consumption: 8GPM Tunnel requirement: 14' in length x 13' in width Height: 34" with LED light Height: 22" without LED light Powder Coated	1	17,995.00	17,995.00T
Sales	Not Motor City Wash Works INTERNATIONAL DRYING SYSTEM	1	115,998.00	115,998.00

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	- 60HP WHISPER BLOWER WITH 10HP FLASH DRYER			
Sales	Not Motor City Wash Works MISCELLANEOUS CHARGES/FEEES VFD PANEL FOR DRYERS	1	10,800.00	10,800.00T
Sales	25 Drop Central Vacuum System 40 HP X2	2	37,530.00	75,060.00T
Sales	40 HP Control Pannel	2	11,855.00	23,710.00T
Sales	Hangers Vacuum Tools Kit	24	280.36	6,728.64T
Sales	6" Vacuum Stand with trap For Heavy Items	24	906.9908333	21,767.78T
Sales	Vacuum Air Drops 25	25	430.00	10,750.00T
Sales	Air Compressor 7.5 HP 80 Gal	2	5,765.00	11,530.00T
Sales	ICS 2 Lane Gate System With 72 Function	1	211,126.00	211,126.00T
Sales	ICS Tranning And Setup	1	10,995.00	10,995.00
Sales	RHINO MAT CLEANER	2	9,172.00	18,344.00T
Sales	CE-4 FS Series II 5HP ... EFO Bio-Zone Dosing Con-Serv Eliminator 4, 6,000- 7,200 GPD Base Unit Includes; Aluminum Frame, 2.5x20 - 5 Micron Sediment Pre Filter, Stainless Steel Automatic Feed Water Shut Off Valve, Stainless Steel Multi Stage 1.5HP	1	14,190.00	14,190.00T

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
----------	-------------	-----	------	--------

Pump, Stainless
 Steel Pump
 Throttle Valve,
 Physical Water
 Conditioner,
 Electronic Control
 (UL Listed) w/ Low
 Pressure
 Protection,
 Manual/Auto
 Reset, Water
 Quality Meter, Dry
 Contacts For
 Liquid Level
 Controls and
 Pretreatment
 Lockout, On/Off
 Switch and
 Function LED's,
 Fiberglass
 Pressure Vessels,
 Pressure Gauges-
 Pre Filter In and
 Out, 1st Array
 Feed,
 Concentrate, Flow
 Meters-Permeate
 and Concentrate,
 Stainless Steel
 Concentrate
 Control Valve, 14"
 Auto Backwash
 Carbon Filter w/
 CENTAUR
 Carbon , Liquid
 Level Control,
 Floor Stand Dim.
 46"W x 31.5"D x
 70"H, Pre
 Plumbed and Pre
 Wired, Includes
 Stainless Steel
 Automatic Flush
 Valve
 FRAME
 INCLUDED
 ** ALL
 ELIMINATOR
 SERIES RO
 UNITS REQUIRE
 230V SINGLE
 PHASE, IF 230V
 SINGLE PHASE

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	IS NOT AVAILABLE, A BOOSTING TRANSFORMER MUST BE USED OR WARRANTY WILL BE VOID.** (3-phase available for additional charge)			
Sales	Water Tanks 1000 Gal	3	3,476.00	10,428.00T
Sales	FS COMBINATION SERIES II 5HP 100 GPM Con-Serv Free Standing Combination: - Stainless Steel System (Piping, Frame) - 5 HP Motor, 100 GPM - Self Cleaning Filter w/auto Backwash - Fusion Bonded SCOTCH KOTE Corrosion Resistant Housings - 35 Gallon Ballast Tank - UL Approved Electrical Controls - Touchscreen - Includes Pump Guard Advisor - 3/4 HP Re-Circulation Pump Emergency Fresh Water Override Auto Dose Injection Pumping System, 25' Tubing, Two Cases of Bio-Treatment Concentrate. (approximately 4 Months supply	1	22,490.00	22,490.00T

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
Sales	Emergency Fresh Water Override	1	850.00	850.00T
Sales	Total Equipment Package & Handling	1	10,389.04	10,389.04
Sales	Wall Panels Installation Cost	1	14,000.00	14,000.00
Sales	ExtraTec Wall Panels Sheets for protection for inside tunnel walls	1	35,000.00	35,000.00T
Sales	Utility Tray For Wire, Tubing, and Main Power	1	17,000.00	17,000.00T
Sales	Auto Dose Injection Pumping System, 25' Tubing, Two Cases of Bio-Treatment	1	1,190.00	1,190.00T
Sales	Installation Hardware Cost, Wire, Cable, Plumbing, Material for Welding and to complete installation	1	37,500.00	37,500.00T
Sales	Motor City Wash Works Equipment	1	456,240.30	456,240.30T
				Subtotal: 1,154,081.76
Labor	Labor- Installation	1	276,108.00	276,108.00
Sales	Discount 10%	1	-132,268.90	-132,268.90
Sales	Fright & Shipping TBD	1	0.00	0.00

40% down to get Started \$561,917.50
 Full payment two weeks before equipment ships out.

SUBTOTAL	1,297,920.86
TAX	82,722.73
TOTAL	\$1,380,643.59

Accepted By

Accepted Date