



**BLUE RIDGE MEAT
GREENWOOD, MS
LOCATION**

NOTE : Dimentions Could Vary a few inches in all offices and break room etc Around the Cooler, Processing Room and Freezer as the metal wall panel thickness will dictate.

- Notes:
1. All interior walls will be painted sheetrock in the offices
 2. All ceilings will be 2x2 acoustical lay in tile
 3. Lunch room walls to be FRP panels
 4. Cook room to be FRP panels USDA grade
 5. All Ceilings to be 10'-0 high
 6. All office doors to be wood prefinished doors with gunshot glass slot
 7. All office flooring, and lunch room to be VCT floors with Rubber Base
 8. Restroom and Locker Room Floors to be ceramic tile floors