

- REMOVE, RELOCATE, & REWORK EXIST'G CASEWORK & PL TOPS TO RM 006 4004
- VERIFY EXACT SIZE OF COMPUTER ACCESS FLOOR
- REMOVE WOOD SLEEPER FLOOR TO CONG. SLAB @ COMPUTER RM.
- FILL IN GUP BETWEEN PLASTER & W/ WOOD G FLOOR

REMOVE EXIST'G S.A.T. & G.P. S.D. SOFFIT. REMOVE ALL ABANDONED ELECTRICAL EMT ETC., REMOVE ALL MISC BLOCKING, CLAMPS, HANGERS ETC. REWORK DUCT & DIFFUSERS AS REQ'D. PAINT ALL EMT, DUCTS, & EXPOSED CEILING BEAMS & DECK. SEMI-GLOSS WHITE

EXIST'G CABINET & PL TOP TO REMAIN ON OFFICE SIDE OF WALL.

REMOVE 6'-6" BASE CAB. & CUT PL TOP @ NEW WALL

REMOVE EXIST'G CONG PAVING & WALKS NEW 4" CONG W/ 6"x6 10/10 W/M REWORK GRAVE, REPAIR TENCH DRAIN

REPAIR, WATERMETER VALVE MANHOLE

NEW WOOD FLOOR FLUSH W/ EXIST'G @ DOCK SLAB.

NEW 12" CMU & STUCCO INFILL WALL NEW WINDOW, WINDSOR 4036 (OR ALTERNATE)

CAN-CUT & REMOVE EXIST'G REMING @ R/W. NEW 4" CONG SLAB.

MASS-BLOCK FROST PROOF SLAB @ DOOR 3'-6" BELOW GRADE MIN.

NEW SOUTH STAIR, 1 HOUR MIN. RATED CONG. MASONRY UNIT ENCLOSURE SEE SHEET A-14 FOR DETAILS

COLT 4" THICK CONG. SLAB.

EXIST'G ASPHALT PAVING TO REMAIN

SEE SHEET A-13 FOR TOILET RM & NEW STAIR BLOW-UP

REMOVE WALL, STAIR, & RAISED FLOOR VOID UNDER COMPUTER ROOM 12' HIGH X FULL WIDTH.

REMOVE EXIST. S.A.T. NEW G.P. S.D. SOFFIT. NEW FLOOR OPEN'G ABOVE

WEST BLDG.

HAMILTON AVE. GARAGE


EAST BLDG.

REMOVE EXIST'G METAL HANDRAIL AND NEW 2"x12" WOOD STRINGER & SCREW ATTACH TO EXIST'G PROJECT'G TREADS. ADD PCS OF RISER PANEL @ EA. STAIR. SHALL THAT STAIR IS 44" MIN. WIDE. ADD SPINDLE HANDRAIL ON OPEN SIDE OF PAINTED POPLAR, AND METAL OF WOOD HANDRAIL ON WALL SIDES.

SEE SHEET A-11 REGARDING BIDDING ALTERNATES FOR EXIST'G ALUM. & GLASS WINDOWS.

REMOVE EXIST'G ELECTRIC SERVICE EQUIPMT & BACKBOARDS, PATCH ALL HOLES IN BRICK MASONRY REMOVE ALL WEATHER HEADS & BRACKETS

BLAST BRICK TO REMOVE PLANKING & SPALLING. TOUCH POINT AS REQ'D

 FIRST FLOOR  
1/8" = 1'-0"

SELF FUNDED PLANS INC.	
1432 HAMILTON AVE CLEVELAND	
HENRY PIPER, ARCHITECT	
1ST FLOOR	A-4