CONSTRUCTION DRAWINGS MOONDANCER

2 NORTH STAR ROAD BOERNE, TEXAS

NO. 170, ABSTRACT NO. 97, KENDALL COUNTY, TEXAS, RECORDED IN THE OFFICIAL RECORDS OF KENDALL COUNTY, TEXAS.

VERTICAL SITE CONTROL						
NUMBER	NORTHING	EASTING	ELEVATION	DESCRIPTION		
1	13822759.9170'	2064478.3840'	1403.419'	SIRCP		
8000	13822876.5740'	2064176.2560'	1392.909'	FOUND 1/2 MH RED 1008		


- SEQUENCE OF CONSTRUCTION:

 1. INSTALL ALL EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED BY THE STORM WATER POLLUTION PREVENTION PLAN.
 EROSION CONTROL DEVICES ARE TO BE MAINTAINED DURING THE ENTIRE COURSE OF CONSTRUCTION.
- INSTALL ALL TRAFFIC CONTROL DEVICES AS REQUIRED BY KENDALL COUNTY & CITY OF BOERNE UTILITY AND DRIVEWAY PERMITS, NOTE THAT ALL TRAFFIC CONTROL PROCEDURES SHOULD A PAGE TO SECRETARIAL TO A SECRETARIAL TRAFFIC CONTROL PROCEDURES SHOULD A PAGE TO SECRETARIAL TO A SECRETARIAL TO A SECRETARIAL TO A SECRETARIAL TO A SECRETARIAL TRAFFIC CONTROL PROCEDURES SHOULD A PAGE TO SECRETARIAL TO A SECRETARIAL TRAFFIC CONTROL PROCEDURES SHOULD A PAGE TO SECRETARIAL TRAFFIC CONTROL PROCEDURE SHOULD A P
- HOLD PRE-CONSTRUCTION CONFERENCE WITH THE CITY OF BOERNE, OWNER, PROJECT ENGINEER, CONTRACTOR AND SUB-CONTRACTORS
- 4. CONTRACTOR TO COMPLETE ALL STREET, DRAINAGE, & UTILITY IMPROVEMENTS.
- 5 COMPLETE ALL PERMANENT EROSION CONTROL STRUCTURES AND MEASURES AND FINALIZE THE SITE RESTORATION.
- 6. PROJECT ENGINEER SHALL SCHEDULE FINAL WALK THROUGH WITH CONTRACTOR AND CITY OF BOERNE.

- 9. PROJECT ENGINEER TO WRITE CONCURRENCE LETTER AND SUBMIT PLAN OF RECORD DRAWINGS TO CITY OF BOERNE.
- 11. REMOVE TEMPORARY EROSION AND SEDIMENTATION CONTROLS. RESTORE ANY AREAS DISTURBED DURING REMOVAL OF TEMPORARY

OWNER. LOQ. LLC C/O LINDSAY ANDERSON MOONDANCER 559 E. HUISACHE AVENUE

ENGINEER & SURVEYOR: MATKIN HOOVER ENGINEERING & SURVEYING 8 SPENCER ROAD, SUITE 100 BOERNE, TX 78006 (830) 249-0099 FAX



MOONDANCER SHEET LIST TABLE SHEET NUMBER SHEET DESCRIPTION SHEET TITLE TITLE SHEET RECORDED PLAT (SHEET 1) RECORDED PLAT (SHEET 2) V-002 GENERAL NOTES EXISTING CONDITIONS AND DEMOLITION PLAN (SHEET 1) EXISTING CONDITIONS AND DEMOLITION PLAN (SHEET 2) EROSION AND SEDIMENTATION CONTROL PLAN EROSION AND SEDIMENTATION CONTROL DETAILS OVERALL SITE AND DIMENSIONAL CONTROL PLAN FIRE PROTECTION PLAN DETAILED GRADING PLAN (SHEET 1) DETAILED GRADING PLAN (SHEET 2) DETAILED GRADING PLAN (SHEET 3) DETAILED GRADING PLAN (SHEET 4) DETENTION POND PLAN UTILITY PLAN CU501 UTILITY DETAILS SITE CIVIL DETAILS (SHEET 1) SITE CIVIL DETAILS (SHEET 2)

DATE: MAY 2022

SHEET # 01

Job 3224.01

Rev.	Date	Description	Apv.
		Y	

ENGINEER: CODY MORRIS, P.E.

100% DESIGN SET