



1 FIRST FLOOR PLAN - NEW
3/16" = 1'-0"

SCHEDULE - FIRE EXTINGUISHER	
MARK:	SPECIFICATION:
FE-1	NEW MP-10 FIRE EXTINGUISHER SEMI RECESSED
FE-S	NEW MP-10 FIRE EXTINGUISHER SURFACE MOUNTED

FLOOR PLAN NOTES

- CONTRACTORS TO VERIFY ALL FIELD CONDITIONS PRIOR TO COMMENCEMENT AND REPORT ANY DISCREPANCIES TO THE ARCHITECT.
- VERIFY DEPTH AND WIDTH OF BUILD-OUT REQUIRED FOR RECESSED ITEMS INCLUDING, FIRE EXTINGUISHER CABINETS, ACCESSORIES, ETC.
- COORDINATE WITH THE TENANT / OWNER FOR THE INSTALLATION OF INTERIOR SIGNAGE.
- ALL PIPE PENETRATIONS THROUGH RATED ASSEMBLIES MUST MEET UL (OR OTHER APPROVED) STANDARDS - SUBMIT SYSTEM TO ARCHITECT FOR APPROVAL.
- PROVIDE SOLID WOOD BACKING (FIRE-TREATED) IN WALLS TO RECEIVE COUNTERS, CABINETS, DOOR STOPS, SINKS, TOILET ACCESSORIES, CHAIR RAIL AND OTHER REALTED INSTALLATIONS. THE INSTALLATIONS SHALL BE INSPECTED BY THE ARCHITECT PRIOR TO COVERING.
- ALL GYPSUM BOARD WALLS AND CEILINGS SHALL BE PROVIDED WITH A LEVEL 4 FINISH PER "GYPSUM ASSOCIATION - RECOMMENDED LEVELS OF GYPSUM BOARD FINISH (GA-214-M-97)" - UNLESS NOTED OTHERWISE.



S ARCHITECTURE
1800 NORTH MILITARY TRAIL, SUITE 300
BOCA RATON, FL 33431
954.302.9861
WWW.SARCHITECTURE.COM
AA26003746

SEAL:



MATTHEW R. FORGET // REG. FL. NO. AR95364

CLIENT / PROJECT ADDRESS:

Freedman's Office
Furniture

2055 Palm Beach Lakes Blvd.
West Palm Beach, FL

REVISIONS:

NO.	DATE	DESCRIPTION
-----	------	-------------

KEY PLAN:

PROJECT NUMBER: 21-083
DATE ISSUED: 07-13-2022

SHEET TITLE:

FLOOR PLAN

SHEET NO.:

A-121