

LEGEND

- NEW TO REMAIN
- GENERAL
- DOORS
- EXISTING WALLS TO REMAIN
- NEW GWB WALL
- NEW GWB ON EXISTING METAL STUDS
- 1HR FIRE RATED GWB WALL
- 1HR FIRE RATED GWB WALL
- 1HR FIRE SHOCK RATED GWB WALL
- 120A
- DOOR TAG REFER TO DOOR SCHEDULE
- INTERIOR ELEVATION TAG
- WINDOW TAG REFER TO SHEET A7.2

PROPOSED SPACE PROGRAM

DRAWING ROOM NAME	DRAWING ROOM #	ROOM NET SQUARE FOOTAGE	FGI REFERENCE	DRAWING ROOM NAME	DRAWING ROOM #	ROOM NET SQUARE FOOTAGE	FGI REFERENCE
PATIENT INTAKE AREAS							
WAITING ROOM (16 VISITORS)	100	444	2.7.3.5.2.3	EVS CLOSET	136	15	2.7.3.5.2.3
PUBLIC TOILET RM	101	42	2.7.3.5.2.3	PATIENT TOILET RM	137	29	2.7.3.5.2.3
PUBLIC TOILET RM	102	42	2.7.3.5.2.3	CLEAN LINENS CLOSET	138	15	2.7.3.5.2.3
SECURE VESTIBULE	103	69	2.1.3.5.5.5	PRE-POST PROCEDURE BAY #8	139	71	2.7.3.5.2.3
CONSULT. ROOM	104	39	2.7.4.4	STAFFPATIENT HALLWAY	140	189	2.7.3.5.2.3
RECEPTION DESK	105	197	2.7.4.4	CLEAN STORAGE	141A	27	2.7.3.5.2.3
ADMITTING & REGISTRATION	106	60	2.7.4.4	RECEPTION	142	60	2.7.3.5.2.3
PHYSICIAN OFFICE	107	193	2.7.4.4	RECEPTION	143	60	2.7.3.5.2.3
BUSINESS OFFICE	108	62	2.7.4.4	MENS SHOWER ROOM	144	18.5	2.7.3.5.2.3
DIR OF NURSING OFFICE	109	62	2.7.4.4	MED. GAS ROOM	146	114	2.7.3.5.2.3
STAFF HALLWAY	110	37	2.7.3.5.2.3	SOIL WORK ROOM	147	93	2.7.3.5.2.3
PATIENT TOILET RN	111	32	2.7.3.5.2.3	MEDICATION SAFETY ZONE	148	15	2.7.3.5.2.3
STAFFPATIENT HALLWAY	112	138	2.7.3.5.2.3	DICTIONARY ALCOVE	149	15	2.7.3.5.2.3
PRE-POST PROCEDURE BAY #1	113	76	2.7.3.5.2.3	STRETCHER ALCOVE	151	22	2.7.3.5.2.3
NURSE STATION	114	58	2.7.3.6.2	CLEAN ED. & CLEAN & STERILE SFP. ST.	152	252	2.7.3.5.2.3
PATIENT DISCHARGE HALLWAY	115	44	2.7.3.4.3	VESTIBULE	153	72	2.1.3.5.5.5
PRE-POSTPROCEDUREBAY #13	116	66	2.7.3.4.3	MECHANICAL ED. ROOM	154	153	
NOURISHMENT	117	14	2.7.3.4.3	EVS CLOSET	155	27	2.7.3.5.2.3
PRE-POST PROCEDURE BAY #2	118	60	2.7.3.4.3	SOILED WORK ROOM (DECONTAM)	156	301	2.7.3.4.3
PRE-POSTPROCEDUREBAY #3	119	60	2.7.3.4.3	STAFF PATIENCE HALLWAY	158	156	2.7.3.5.2.3
STAFFPAT. HALLWAY	120	199	2.7.3.4.3	STAFF PATIENCE HALLWAY	159	156	2.7.3.5.2.3
CLEAN SUPPLY RM	121	38	2.1.4.5.1	STABLE STORAGE ROOM	159	209.3	2.7.3.2.13
PRE-POSTPROCEDUREBAY #2	122	65	2.7.3.4.3	OPERATING ROOM #4	160	408	2.7.3.14
PRE-POSTPROCEDUREBAY #11	123	67	2.7.3.4.3	SCRUB ALCOVE	161	14	2.7.3.3.3.3
STAFFPAT. HALLWAY	124	395	2.7.3.4.3	OPERATING ROOM #3	162	495	2.7.3.14
STAFF TOILET RN	125	40	2.7.3.5.2.3	OPERATING ROOM #2	163	396	2.7.3.14
PRE-POST PROCEDURE BAY #4	126	67	2.7.3.4.3	SCRUB ALCOVE	164	14	2.7.3.3.3.3
PRE-POST PROCEDURE BAY #5	127	69	2.7.3.4.3	OPERATING ROOM ROOM #1	165	398	2.7.3.14
NURSE STATION	128	63	2.7.3.6.2	EQ. ALCOVE	166	14	
IT ROOM	129	15		WOMEN'S TOILET ROOM	167	38	
MED PREP ROOM	130	31	2.7.3.4.3	WOMEN'S LOCKER ROOM	168	151	
RECEPTION ROOM	131	68	2.7.3.4.3	WOMEN'S LOCKER ROOM	169	151	
PRE-POST PROCEDURE BAY #7	132	67	2.7.3.4.3	STAFF LOCKER	170	233	2.7.3.2.12.7.4
STAFFPAT. HALLWAY	133	227	2.7.3.4.3	ESSENTIAL ELECT. ROOM	171	47	2.7.3.5.3.11
PRE-POSTPROCEDUREBAY #10	134	78	2.7.3.4.3	NORMAL ELECT. ROOM	172	100	2.7.3.5.3.11
PRE-POSTPROCEDUREBAY #9	135	78	2.7.3.4.3	SEMI-RESTRICTED HALLWAY	173	778	2.7.3.5.3.11

KEYNOTES

NOTE: REFER TO ME/P/CR FOR ADDITIONAL INFORMATION

NOTE: FOR MODULAR CUBICLES FURNITURE AT BUSINESS OFFICE CONTRACTOR SHALL COORDINATE ALL ELECTRICAL AND DATA CONNECTIONS WITH FURNITURE VENDOR DRAWINGS AND ELECTRICAL DRAWINGS FOR CONSTRUCTION



NEW WORK FLOOR PLAN

THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON COVER SHEET AND SHALL NOT BE SEPARATED.

A1.1

NEW WORK - FLOOR PLAN

SCALE: 1/8"=1'-0"

BLOC 3 DESIGN

CONSTRUCTION, ARCHITECTURE, INTERIOR DESIGN, LANDSCAPE ARCHITECTURE

7511 VILLES BOULEVARD, SUITE 302
CORAL GABLES, FLORIDA 33134
TEL: 305.441.2449
JACKSONVILLE, FLORIDA 32002
TEL: 321.974.2425

PROPOSED AMBULATORY SURGICAL CENTER
APEX SURGERY CENTER
2699 WOODBRIGHT RD # 4A
BOYNTON BEACH, FL 33436

CLIENT: CHRISTOPHER A. SABLE
DATE: 09/20/2016
PROJECT NO.: 25004.02

CHRISTOPHER A. SABLE
OWNER/ARCHITECT

STATE OF FLORIDA
REGISTERED PROFESSIONAL ARCHITECT
NO. 13612
EXPIRES 12/31/2020

PRINCIPAL, BLOC 3 DESIGN, INC.