

ESTIMATE

Prepared For



Joe Aschauer
2272 NYS Route 9
Malta, NY
(518) 505-9641

High Country Hardscape & Landscape Designs

Estimate # 966

Date 01/09/2025

1101 Mariaville Rd
Schenectady, Ny 12306
Phone: (518) 721-2141
Email: HChardscaping@yahoo.com

Description

Total

2272 NYS Route 9 (Retaining Wall)	\$146,546.56
<ul style="list-style-type: none">- Allan Block (Grey Color)- Wall #1 (3,881SQFT)<ul style="list-style-type: none">* 560LF Base* 10' Maximum Height- ESTIMATE may change depending on stamped plans<ul style="list-style-type: none">* Can provide stamped plans for additional \$5,750- Retaining Walls to be built using Allan Block- Base to consist of:<ul style="list-style-type: none">* 6-8" Crushed 2s* 1-2" Crushed 1s- Backfill to be Crushed 2's (18" Behind Wall) (850 Ton of Stone to be used and included in bid)<ul style="list-style-type: none">* Any additional stone will be priced \$25ton- This BID is for materials, labor to install, compact and run drain behind wall<ul style="list-style-type: none">* Installation of crushed stone base* Installation of drain behind base course block* Installation of Geogrid per drawings Est 1650yrds* Installation of crushed stone behind wall* Compaction- Site for retaining walls must be excavated down to subgrade before we arrive onsite<ul style="list-style-type: none">* We can price out our own excavation if interested- Project is being bid as NON Prevailing Wage- All infill soil to be provided by site contractor APX 750yrds(Need soils report for engineer to determine if infill soil is suitable)	

Subtotal	\$146,546.56
-----------------	--------------

Total	\$146,546.56
--------------	---------------------

Estimate is only valid for 30 Days

By signing this document, the customer agrees to the services and conditions outlined in this document.

Joe Aschauer